



# MARTIN COUNTY ENERGY AND OPERATIONAL SAVINGS PROJECT

# INVESTMENT GRADE AUDIT REPORT July 21, 2025

# Table of Contents

<b>Executive Summary .....</b>	<b>4</b>
<b>Project Scope .....</b>	<b>7</b>
Project Summary .....	7
Energy Conservation Measure (ECM) Matrix .....	7
Facilities Included in the Investment Grade Audit (IGA) .....	12
Existing Conditions .....	15
County-Wide Lighting and Water .....	15
Public Safety Complex (PSC) .....	15
Cummings Library .....	16
Site Utility Summary .....	16
<b>Sources of Savings .....</b>	<b>19</b>
Energy Savings .....	19
Operational Savings .....	19
Lifecycle Cost Savings .....	20
PSC Chiller Replacement: .....	20
Capital Cost Avoidance: .....	21
Lighting Material Savings: .....	19
Life Cycle Cost Analysis .....	22
<b>Energy Conservation Measures .....</b>	<b>23</b>
ECM-01 County-Wide Lighting Retrofit .....	23
ECM-02 Water Conservation .....	47
ECM-04 Public Safety Complex Chiller Plant Tie-In .....	58
ECM-05 Cummings Library A/C Replacement .....	63
ECM-06 Jail Chiller Plant 400 kW Generator Addition .....	70
ECM-07 PSC – Install Two (2) 300 kW Emergency Generators .....	72
ECM-08 Controls Optimization/Intelligent Services .....	74
ECMs Evaluated but Not Recommended .....	78
<b>Project Financing .....</b>	<b>81</b>
<b>Project Financing and Project Pro Forma .....</b>	<b>81</b>
<b>Support Services .....</b>	<b>84</b>
<b>Measurement and Verification .....</b>	<b>85</b>
Savings Measurement Protocol .....	85
Savings Measurement and Verification Plan .....	86
<b>Environmental Benefits .....</b>	<b>92</b>
Trane’s Commitment to Sustainability .....	92
Climate Metrics .....	93
<b>Appendices .....</b>	<b>94</b>


Appendix A Electric Utility Analysis .....	94
.....	98
Appendix B Utility tariff.....	99
Appendix C Savings Calculations .....	102
Lighting.....	102
HVAC .....	103
Water .....	104
Appendix D Lighting Line by Line .....	105
Appendix E Water Line by Line .....	228

# Executive Summary

## Energy Performance Contracting:

Energy performance contracting is a flexible and valuable financial tool for Martin County. Martin County has completed five previous energy projects that will save \$50,614,539 in total energy and operational savings. The recommended project adds an additional \$10,393,413.

Energy performance contracting is a proven vehicle to access low cost financing, manage budget priorities, and reduce operating expenses. Energy performance contracting allows capital projects to pay for themselves over time and captures available clean energy and utility incentives.



## Martin County Sustainability Leadership:

Martin County has achieved a leadership position in energy efficiency and sustainability through using energy performance contracting projects. The projects reduce ongoing energy, operating, and capital improvement costs. The energy projects show strong and consistent financial performance as shown in the table below:

### Martin County - Summary of Energy Project Results

<u>Project Name/ESCO</u>	<u>Contract Years</u>	<u>Current Contract Year</u>	<u>Project Cost</u>	<u>Actual Total Savings to Date</u>	<u>Total Project Savings</u>	<u>Metric Tons of CO2 Equivalent Avoided<sup>2</sup></u>
Jail - FPL	2007-2016	Completed	\$ 2,400,000	\$3,428,571	\$3,428,571	11,484
General Services - Trane	2009-2024	15/16	\$ 4,815,465	\$10,449,871	\$11,146,529.07	33,471
Parks Sports Lighting - Trane	2013-2022	9/10	\$ 8,138,628	\$11,847,020	\$13,163,355.56	7,416
Jail - Trane	2021-2034	3/14	\$ 12,810,301	\$4,449,300	\$20,763,400.98	1,734
Health Department - Trane	2020	n/a	\$ 1,594,000	\$633,805	\$2,112,683.00	34
Martin County 2025 Project	2025-2040	Proposed	\$ 7,021,715	\$0	\$10,393,413.00	997
<b>Totals</b>			<b>\$ 36,780,109</b>	<b>\$ 30,808,567</b>	<b>\$ 61,007,953</b>	<b>55,136</b>

<sup>1</sup> Health Department energy savings calculated but not performed as guaranteed energy savings performance contract

<sup>2</sup> Climate metrics per EPA Greenhouse Gas Equivalencies Calculator

In addition to the financial results, another key measure of the success of the projects is the collective environmental impact. To date, the Martin County energy projects have reduced 54,139 metric tons of CO2 equivalent, which is equal to the annual energy use of 7,324 homes. This information was previously reported to the Martin County BOCC in the August, 2022 resiliency presentation.



## Recommendations:

The project that is recommended by the County is an energy performance contract that includes interior and exterior LED lighting, water conservation, replacement of the a/c systems at Cummings Library, expansion of the Jail chiller plant to provide cooling for the Public Safety Complex, required upgrades to the emergency generator capabilities for the Jail chiller plant and the Public Safety Complex, and energy optimization with Trane Intelligent Services. The recommended project has a value of \$7,021,715. The project costs will be financed and paid through guaranteed energy savings, operational savings, and cost avoidance.

The project addresses these key goals:

- Improves the comfort and safety of the building occupant
- Reduces deferred maintenance costs and downtime for infrastructure repairs.
- Improves energy and water efficiency which results in cost savings

## Financials:

The implementation of the recommended ECMs will reduce consumption by **1,996,915 kWh** annually. The proposed annual energy and energy related cost savings for this project is **\$ 203,306** and annual operational and lifecycle savings, and capital cost avoidance of **\$412,932**. The implementation cost is **\$7,021,715** resulting in a simple payback of **11.4 years**. The program is cashflow positive over the 15-year term.

## Project Summary – Recommended

### Recommended Energy Conservation Measures

Project Scope				Annual Savings				Project Metrics				
x = Included	ECM #	Building or Facility	ECM Description	Energy Savings	Operational Savings	Lifecycle Savings	Capital Cost Avoidance	Utility Rebates	ECM Payback	Service Cost	M&V Cost	ECM Cost
x	1A	Multiple	Interior Lighting	\$ 90,431	\$ 18,651			\$ -	9.1	\$ -	\$ 5,219	\$ 992,745
x	1B	Multiple	Parking Lot Lighting	\$ 7,839	\$ 1,958			\$ -	19.8	\$ -	\$ 517	\$ 193,520
x	2	Multiple	Water Conservation	\$ 15,987	\$ -			\$ -	14.8	\$ -	\$ 1,500	\$ 237,238
	3A	Multiple	Building Envelope	\$ -	\$ -			\$ -	-	\$ -	\$ -	\$ -
	3B	Admin Building	Window Tinting	\$ -	\$ -			\$ -	-	\$ -	\$ -	\$ -
x	4	PSC/Jail Chiller Plant	Chiller Plant Tie-In	\$ 47,288	\$ 15,100	\$ 184,559		\$ 1,786	8.3	\$ 14,500	\$ 9,500	\$ 2,051,650
x	5A	Cummings Library	A/C Replacement	\$ 5,521		\$ 107,740		\$ -	19.7	\$ 12,050	\$ 8,000	\$ 2,234,662
	5B	Cummings Library	Thermal Storage	\$ -			\$ -	\$ -	-	\$ -	\$ -	\$ -
x	6	Jail Chiller Plant	400 kW Generator/ATS	\$ -			\$ 46,230	\$ -	15.0	\$ -	\$ -	\$ 693,450
	7A	PSC	Two New 300 kW Generators	\$ -			\$ -	\$ -	-	\$ -	\$ -	\$ -
x	7B	PSC	One 300 kW Generator/MTS	\$ -			\$ 38,694	\$ -	15.0	\$ -	\$ -	\$ 580,414
x	8A	Blake Library	Intelligent Services	\$ 8,424				\$ -	-	\$ 4,405		\$ -
x	8B	Admin Building	Intelligent Services	\$ 6,497				\$ -	2.6	\$ 4,405		\$ 17,021
x	8C	Courthouse/COB	Intelligent Services	\$ 21,319				\$ -	1.0	\$ 3,805		\$ 21,015
<b>Totals</b>				<b>\$ 203,306</b>	<b>\$ 35,709</b>	<b>\$ 292,299</b>	<b>\$ 84,924</b>	<b>\$ 1,786</b>	<b>11.4</b>	<b>\$ 39,165</b>	<b>\$ 24,736</b>	<b>\$ 7,021,715</b>

## Project Summary - All Evaluated

### All Evaluated Energy Conservation Measures

Project Scope				Annual Savings				Project Metrics				
x = Included	ECM #	Building or Facility	ECM Description	Energy Savings	Operational Savings	Lifecycle Savings	Capital Cost Avoidance	Utility Rebates	ECM Payback	Service Cost	M&V Cost	ECM Cost
x	1A	Multiple	Interior Lighting	\$ 90,431	\$ 18,651			\$ -	9.1	\$ -	\$ 5,219	\$ 992,745
x	1B	Multiple	Parking Lot Lighting	\$ 7,839	\$ 1,958			\$ -	19.8	\$ -	\$ 517	\$ 193,520
x	2	Multiple	Water Conservation	\$ 15,987	\$ -			\$ -	14.8	\$ -	\$ 1,500	\$ 237,238
x	3A	Multiple	Building Envelope	\$ 12,799	\$ -			\$ -	17.3	\$ -	\$ 1,250	\$ 221,000
x	3B	Admin Building	Window Tinting	\$ 7,443	\$ -			\$ -	33.9	\$ -	\$ 600	\$ 252,000
x	4	PSC/Jail Chiller Plant	Chiller Plant Tie-In	\$ 47,288	\$ 15,100	\$ 184,559		\$ 1,786	8.3	\$ 14,500	\$ 9,500	\$ 2,051,650
x	5A	Cummings Library	A/C Replacement	\$ 5,521		\$ 107,740		\$ -	19.7	\$ 12,050	\$ 8,000	\$ 2,234,662
x	5B	Cummings Library	Thermal Storage	\$ 4,270			\$ -	\$ -	66.1	\$ -	\$ 1,250	\$ 282,158
x	6	Jail Chiller Plant	400 kW Generator/ATS	\$ -			\$ 46,230	\$ -	15.0	\$ -	\$ -	\$ 693,450
x	7A	PSC	Two New 300 kW Generators	\$ -			\$ 69,360	\$ -	15.0	\$ -	\$ -	\$ 1,040,400
x	7B	PSC	One 300 kW Generator/MTS	\$ -			\$ 38,694	\$ -	15.0	\$ -	\$ -	\$ 580,414
x	8A	Blake Library	Intelligent Services	\$ 8,424				\$ -	-	\$ 4,405		\$ -
x	8B	Admin Building	Intelligent Services	\$ 6,497				\$ -	2.6	\$ 4,405		\$ 17,021
x	8C	Courthouse/COB	Intelligent Services	\$ 21,319				\$ -	1.0	\$ 3,805		\$ 21,015
<b>Totals</b>				<b>\$ 227,818</b>	<b>\$ 35,709</b>	<b>\$ 292,299</b>	<b>\$ 154,284</b>	<b>\$ 1,786</b>	<b>12.4</b>	<b>\$39,165</b>	<b>\$27,836</b>	<b>\$8,817,273</b>

### Next Step:

Moving forward with the proposed energy performance contract with Trane is highly recommended. The next step is to complete the review and approval of the contract documents and the Bank of America financing term sheet with staff-recommendation of the project for approval by the Board of County Commissioners.

# Project Scope

## Project Summary

Figure 1 summarizes the project scope and financial results for the recommended Energy Conservation Measures (ECMs) included in the project:

**Figure 1: Summary Table of Recommended ECMs**

ECM Name	Annual Energy Savings (\$)	Annual Operational Savings (\$)	Implementation Cost (\$)	Simple Payback Utility Only
ECM-01A/B County-Wide Lighting Retrofit	\$98,270	\$ 20,609	\$ 1,186,265	9.9
ECM-02 Water Conservation	\$18,2		\$ 237,238	14.8
ECM-04 Public Safety Complex Chiller Plant Tie-In	\$47,288	\$ 199,659	\$ 2,051,650	8.3
ECM-05A Cummings Library A/C Replacement	\$6,294	\$ 107,740	\$ 2,234,662	15.9
ECM-06 Jail Chiller Plant Generator Addition	-	\$ 46,230	\$ 693,450	15.0
ECM-07A PSC Two 300 kW Generators/ATS	-	\$ 38,694	\$ 580,414	15.0
ECM-07 Controls Optimization/Intelligent Services	\$36,240	-	\$ 38,036	1.0
<b>TOTAL</b>	<b>\$203,306</b>	<b>\$439,867</b>	<b>\$7,021,715</b>	<b>10.9</b>

## Energy Conservation Measure (ECM) Matrix

Figure 2 provides an energy conservation measure matrix that shows the recommended project scope by building for the project:

**Figure 2: ECM Matrix**

Facility Name	DDC Controls Upgrade	HVAC – Chilled Water System	HVAC - Air Distribution Systems
Administrative Center	X		
Blake Library	X		

Courthouse	X		
Cummings Library	X	X	X
Public Safety Complex	X	X	

Facility Name	Interior/Exterior Lighting
Administration Center Warehouse	X
Blake Library	X
Building Department	X
Citrus Grove Park	X
County Line Park Community Center	X
Court Holding	X
Cummings Library	X
Fire Rescue Fleet Maintenance	X
Fire Rescue LifeStar Hanger	X
Fire Station #16	X
Fire Station #21	X
Fire Station #22	X
Fire Station #23	X
Fire Station #30	X
Fire Station #32	X
General Services Complex	X
Historical Courthouse	X
Hobe Sound Civic Center - Community Center	X
Hoke Library	X
Indian Riverside Park - Children's Museum	X
Indiantown Health Department	X
Jensen Beach Community Center	X
Lahti Library	X
Langford Park	X
Martin County Landfill	X
Martin County Tax Collector	X

Mc DRC (Old EOC)	X
MCSO Aviation Hanger	X
Morgade Library	X
New Monrovia Park Community Center	X
New Monrovia Sheriff Substation	X
Public Safety Complex	X
Supervisor of Elections	X
Witham Field Customs Building	X
Court Holding - Exterior	X
Cummings Library - Exterior	X
Fire Rescue Fleet Maintenance - Exterior	X
Fire Rescue LifeStar Hanger - Exterior	X
Fire Station #16 - Exterior	X
Fire Station #21 - Exterior	X
Fire Station #23 - Exterior	X
Hoke Library - Exterior	X
Indiantown Health Department - Exterior	X
Lahti Library - Exterior	X
Martin County Landfill - Exterior	X
MCSO Aviation Hanger - Exterior	X
Morgade Library - Exterior	X

Facility Name	Water Conservation
Administrative Center	X
Blake Library	X
Hoke Library	X
Jensen Beach Community Center	X
Fire Station 16 Kitchen	X
Fire Station 16 Restroom	X
Fire Station 16 Restrooms near gym	X
Fire Station 16 Shop	X

Langford Park - Vince Bocchino Community Center	X
Langford Park	X
Rio Civic Center	X
Indian Riverside Park-Children'S Museum	X
Indian Riverside Park - Sailing Center Building	X
Jensen Beach Ocean Rescue	X
Jensen Beach Park	X
Fire Rescue Lifestar Hangar	X
Mcso Aviation Hangar	X
Cummings Library	X
Fire Station 21	X
Fire Station 23	X
Jock Leighton Park	X
Fire Station 22	X
Willoughby Commons Usd Office	X
Willoughby Property Appraiser's Office	X
Mary Brogan Park	X
Building Department	X
New Fleet Maintenance	X
Sailfish Splash Water Park	X
Landfill Maintenance Shop	X
Landfill Hazmat/Transfer Station	X
Landfill Breakroom Building	X
Landfill Scalehouse	X
Citrus Grove Park	X
LCpl Justin Wilson Park	X
Timer Powers Park	X
Lahti Library	X
Indiantown Health Department	X
Fire Station 24	X
Indiantown Annex	X
County Line Park - Community Center	X

Fire Station 32	X
Hobe Sound Civic Center - Community Center	X
JV Reed Park	X
Jimmy Graham Park	X
New Monrovia Sheriff Substation	X
Fire Station 30	X
Port Salerno Civic Center	X
Morgade Library	X
Mc Drc (Old Eoc)	X
Park Operations Compound	X
Cob Building	X
Courthouse	X
HOLT ADMINISTRATION	X
Court Holding	X
Supervisor Of Elections Office	X
Stuart Beach Park	X
Field Operations	X
Building Maintenance Shop	X
Mosquito Control Office	X
Vehicle Maintenance Shop	X
Lamar Howard Park	X
Halpatiokee Regional Park	X
Witham Field Customs Building	X
Wojcieszak Park	X
New Monrovia Park - Costella Williams Learning Center/Community Center	X
Public Safety Complex	X



## Facilities Included in the Investment Grade Audit (IGA)

Figure 3 provides a list of all the facilities that were included and evaluated in the Investment grade Energy Audit. While the audit scope was County-wide, not all of the facilities are included in the recommended project scope. For example, many locations, including all of the Park facilities, were not included in the lighting retrofit recommendations since the LED lighting projects were completed in-house.

Figure 3: Facilities Included in the IGA:

BUILDING	BUILDING SQUARE FT. TOTAL
Administrative Center	62000
Administrative Center Warehouse	2700
Blake Library	39000
Building Department	9636
Building Maintenance Shop	6000
Charlie Leighton Park - Palm City Community Recreation Center	3621
Charlie Leighton Park	-
Citrus Grove Park	-
Cob Building	60418
County Line Park - Community Center	1600
Court Holding	10094
Courthouse	50658
Courthouse Cultural Center (Historical Designation)	6023
Csd Building	6000
Cummings Library	21500
Field Operations	11250
Fire Rescue Fleet Maintenance	14240
Fire Rescue Lifestar Hangar	8000
Fire Station 16	12500
Fire Station 21	13092
Fire Station 22	6543
Fire Station 23	9536
Fire Station 24	8160
Fire Station 28	4106
Fire Station 30	10138
Fire Station 32	7158
General Services Administration	5000
Halpatiokee Regional Park	-
Hobe Sound Annex	9680
Hobe Sound Civic Center - Community Center	3160
Hobe Sound Library	11190
Hoke Library	10320
HOLT ADMINISTRATION	18000

BUILDING	BUILDING SQUARE FT. TOTAL
Holt Energy (Maintenance) Building (NOBODY CERTAIN WHAT THIS BUILDING IS)	3000
INDIANTOWN EDUCATION CENTER	5000
Indian Riverside Park - Francis Langford Dockside Pavilion/Recreation Center	10000
Indian Riverside Park - Leach Mansion; Mansion At Tuckahoe	12000
Indian Riverside Park - Sailing Center Building	3000
Indian Riverside Park-Children'S Museum	18000
Indiantown Annex	13544
Indiantown Health Department	6800
JV Reed Park	-
Jensen Beach Building	3829
Jensen Beach Community Center	5122
Jensen Beach Ocean Rescue	3832
Jensen Beach Park	-
Jimmy Graham Park	-
Jock Leighton Park	-
LCpl Justin Wilson Park	-
Lahti Library	10109
Lamar Howard Park - Cassidy Community Center	3360
Lamar Howard Park	-
Landfill Breakroom Building	960
Landfill Hazmat/Transfer Station	31200
Landfill Maintenance Shop	1600
Landfill Scalehouse	1800
Langford Park	-
Langford Park - Vince Bocchino Community Center	9377
Martin County Tax Collector Offices	18600
Mary Brogan Park	-
Mc Drc (Old Eoc)	6000
Mcso Aviation Hangar	8000
Morgade Library	15500
Mosquito Control Office	4640
FIRE STATION 14	12855
FIRE STATION 18	12389
FIRE STATION 33	15000
FIRE STATION 36	6109
New Fleet Maintenance	6000
New Monrovia Park - Costella Williams Learning Center/Community Center	3000
New Monrovia Sheriff Substation	1440
Palm City Tax Collector	3500
Park Operations Compound	12500

BUILDING	BUILDING SQUARE FT. TOTAL
Phipps Park	-
Pineapple Park	-
Port Salerno Civic Center	6319
Public Safety Complex INCLUDING NEW EVIDENCE WAREHOUSE, OUTDOOR LOCKER BUILDING, CHILLER YARD, AND CRIME SCENE GARAGE AND TOY STORAGE	70050
Public Safety Training Building BELIEVE IS "TOY STORAGE" INCLUDED WITH PUBLIC SAFETY COMPLEX?	3000
Rio Civic Center	1000
Sailfish Sands Golf Course	15500
Sailfish Splash Water Park	4500
Stuart Beach Ocean Rescue	1800
Stuart Beach Park	-
Supervisor Of Elections Office	11948
Traffic Management Center	1500
Vehicle Maintenance Shop	10320
William Doc Myers Park	-
Willoughby Commons Usd Office	9055
Willoughby Mpo Office	1730
Willoughby Property Appraiser's Office	13333
Witham Field Customs Building	6700
Wojcieszak Park	-
Timer Powers Park	-
David Anderson Middle School Sports Lighting	-

# Existing Conditions

## County-Wide Lighting and Water

In general the County's lighting systems are a combination of legacy technologies including fluorescent, metal halide and compact fluorescent fixtures. The County has upgraded some fixtures to LED in the recent past.

In general, the County's domestic water fixtures are a mixture of low-flow and standard-flow toilets, sinks and kitchen equipment.

For full breakdown / detailed information on existing lighting and water systems, please refer to Appendix D and E.

## Public Safety Complex (PSC)

Primary cooling for the Public Safety Complex is provided by two (2) 225-ton air-cooled chillers, serial numbers UU06J08529 and U06J08530. These chillers were installed with the original construction of the PSC in 2006. In 2012, the chillers were refurbished to extend their service life, and the compressors and condensing coils were replaced. The chillers require immediate replacement now. The expected service life of an air-cooled chiller on the Treasure Coast is approximately 10-12 years.

The Jail chiller plant was built with future capacity to serve the Public Safety Complex. The Jail chiller plant has two nominal 400-ton water-cooled chillers with associated cooling towers and pumps. The Jail chiller plant serves a total connected cooling load of approximately 430 tons and serves the Holt Correctional Jail as well as additional facilities including Reduced Custody, the Public Safety Gym, and the Sheriff's Kennel. The existing chillers, towers and pumps provide 100% redundancy for current connected cooling loads for the Jail and other connected facilities

Standby power for the PSC is provided by a single 1.5Mw diesel generator. The generator is significantly oversized for the 400 kW peak electrical demand for the PSC. It never fully loads and dates back to the original construction of the PSC in 2009. The electrical load for the PSC generator will drop considerably when the air-cooled chillers are removed. At present there is no redundancy for the PSC if the existing 1.5 Mw generator fails to operate. The PSC was designed to have two standby emergency generators, but only one was installed. Replacement of the oversized 1.5Mw emergency generator is required and added redundancy from a second standby emergency generator is strongly recommended.

Standby power for the Jail chiller plant is provided by a single 400 kW diesel generator. The generator provides power for chiller 1 including the associated pump and cooling tower. Only 400 tons of cooling capacity is available on the existing standby emergency generator. Adding an additional generator to provide additional cooling capacity on standby power is highly recommended with the connection to the PSC.

## Cummings Library

Cummings Library is the last remaining facility in the County with an air conditioning system that utilizes split system direct expansion (DX) air conditioning systems that are based on R-22 refrigerant. R-22 has been phased out of production and use since it is an Ozone Depleting Substance. The air conditioning systems at Cummings Library date back to 2008 when the facility was expanded.

The original library and the two-story expansion utilize split-system air conditioning units. The original library was built in 1995. The two-story addition was added in 2008. The original library uses single zone constant volume air handling units. Outside air is introduced to the main cooling coil without a separate dehumidification system. Humidity control in the original library is very poor due to the use of split system air conditioners that do not provide adequate humidity control. When the space temperature becomes satisfied the compressors shut off and there is no dehumidification. The larger air handling units for the main library spaces use two condensing units per air handler that share an interlaced cooling coil. There are seven air handlers and nine condensing units in the original library. The old section of the library has significant humidity control problems and system upgrade is a priority.

The existing Trane Tracer SC+ system controller was upgraded to replace the original and obsolete building control unit. The controllers for the 13 split system a/c units are obsolete and require replacement. Replacement parts for the existing split system a/c unit controllers are no longer available and are not supported.

Cummings Library does not have a standby emergency generator. This is consistent with the other libraries in the County.

## Site Utility Summary

Overall Trane is performing Site Utility Analysis on the facilities with Chiller Plant, Controls, and Generator upgrades only. The annual baseline, as delineated in Figures below, represents the average values computed over the year 2023-2024. This metric serves as a fundamental benchmark for evaluating the County's performance, trends, and any deviations from the established norm. Detailed information regarding the specific data points, utility provider, accounts, rate, and other contextual analysis of these baseline figures like consumption and costs is meticulously catalogued in Appendix A Electric Utility Analysis.

**Figure 4: Annual Utility Usage Summary**

Facility Name	Electric Consumption kWh	Electric Demand kW	Electric \$
Cummings Library	253,920	1,161	\$34,884
Public Safety	2,013,600	3696	\$198,468
Court House Complex	846,240	3224	\$106,880
Blake Library	753,360	2,158	\$85,420
Admin Center	762,000	2,113	\$82,577
<b>Total</b>	<b>4,629,120</b>	<b>12,352</b>	<b>508,228</b>

The following table summarizes the energy use intensity (EUI) and the energy cost index. These baseline benchmarks helped identify buildings to target for this project.

**Figure 5: Baseline Energy Use Intensity**

Building	Square Foot	Total Usage (kBtu)**	EUI (kBtu/SF)	ECI (\$/SF)
Cummings Library	21,398	866,375	40.5	\$1.63
Public Safety	65,491	6,870,403	104.9	\$3.03
Court House Complex	127,193	2,887,371	22.7	\$0.84
Blake Library	39,000	2,570,464	65.9	\$2.19
Admin Center	78,000	2,599,944	33.3	\$1.06

*\*Includes natural gas data*

*\*\*Total energy usage (electricity, natural gas)*

Martin County receives its electricity services from FPL and water from the City of Stuart.

**Figure 6: Utility Providers and Rates**

Facility	Electricity		Water
	Provider	Rate	
Cummings Library	FPL	GSD-1	City of Stuart
Public Safety	FPL	HLFT-1	City of Stuart
Court House Complex	FPL	GSD-1	City of Stuart
Blake Library	FPL	GSD-1	City of Stuart
Admin Center	FPL	GSD-1	City of Stuart

The following table summarizes the applied baseline utilities and escalation rates used for the cost savings for this project for the contract term with detailed information in Appendix B.

**Figure 7: Baseline Utility Rates**

Building	Electricity (\$/kWh)	Electricity (\$/kW)	Water/Sewer (\$/kgal)*
Cummings Library	\$14.05	\$0.0625	\$ 3.02/4.94
Public Safety	\$17.91	0.0558	\$ 4.32/7.15
Court House Complex	\$14.05	\$0.0625	\$ 4.32/7.15
Blake Library	\$14.05	\$0.0625	\$ 4.32/7.15
Admin Center	\$14.05	\$0.0625	\$ 4.32/7.15

**Figure 8: Baseline Utility Escalation Rates**

Utility	Escalation Rate
Electric \$ / kW demand	4.00 %
Electric \$ / kWh (incremental)	4.00 %



# Sources of Savings

## Energy Savings

Trane performed an investment grade energy audit and detailed energy modeling of the facilities included in the project. The projected energy savings for the project are summarized in the table below. The savings measurement and verification of the energy savings will be based on an Option A comparison of sampled pre-retrofit energy usage measurement and sampled post-retrofit measurements. Building envelope and water savings will be stipulated and mutually agreed and not measured or monitored. Trane has very high confidence in the energy savings calculations and the energy savings guarantee. At the request of County staff, the energy savings includes the 14% projected FPL rate increase for 2026.

Energy Savings Summary				
Building Name	Electric Dollar Savings	Electric Consumption kWh Saved	Electric Demand kW Saved	Water kGal Saved
Lighting All Interior LED	\$90,431	814,383	2887	
Parking Lot Lighting	\$7,839	125,505		
Water Conservation	\$15,997	23,336		1649
PSC Jail Chiller Expansion	\$23,642	381,268	753	-2536
PSC Controls	\$23,646	295,201	401	
Cummings Library	\$5,521	3,065	379	
Court House Complex	\$21,319	219,908	540	
Blake Library	\$8,424	74,296		
Admin Center	\$6,497	59,953		
<b>Total</b>	<b>\$203,306</b>	<b>1,996,915</b>	<b>4,960</b>	<b>-887</b>

## Operational Savings

In addition to energy savings, operational savings are a major contributor to the economic justification of the project. Operational savings are existing annual expenses that are replaced or no longer required due to the improvements provided in the scope of the energy project.

### Lighting Material Savings:

The lighting material savings is calculated from the number of existing lighting fixtures that are replaced with longer-life LED light sources. The lighting material savings is \$20,609 per year.

### **Replaced Maintenance Agreement:**

The air-cooled chillers are currently maintained by Trane under a service contract. This service contract is eliminated when the air-cooled chillers are removed and the PSC is connected to the Jail chiller plant. The value of the replaced maintenance agreement is \$15,100.

## **Lifecycle Cost Savings**

The lifecycle cost savings is essentially the cost avoidance associated with the a/c replacement projects. In other words, if the projects are not done now under the recommended energy performance contracting project, the County will have to budget and spend capital funds to replace the a/c systems. In addition to capital cost avoidance, the operational savings also result from reduced replacement and repair expenses over the 25 year expected life of the proposed water-cooled chiller and air handling systems. This matches the approach from previous energy projects that included operational savings in the project justification.

Cummings Library A/C System - The current HVAC system at Cummings Library is at the end of its useful life and requires replacement. The conversion to a chilled water HVAC system for Cummings Library is the lowest lifecycle cost option and provides superior dehumidification and environmental control for the library. The current split system a/c design is not effective and not recommended for replacement.

Unlike the existing split systems at Cummings Library, the proposed chilled water system has a service lifetime of at least 25 years. Also, the new HVAC system provides additional electrical system capacity that allows future expansion and growth on the site. The approach to this project reduces major risk elements to the County by providing proper cooling capacity, improved dehumidification control, and eliminates future system replacement costs that are required with the existing split system a/c design. Replacing the 24 DX split system eliminates a substantial and ongoing maintenance and repair costs liability the County in the amount of \$10,000 annually. Replacing the Cummings Library split-system a/c units with a chilled water system provides a calculated lifecycle savings of \$2,693,503 or \$107,740 per year over the next 25 years.

**The total lifecycle replacement cost savings for the water cooled chiller plant is \$134,675 per year**

## **PSC Chiller Replacement:**

The PSC has two 225 ton air cooled chillers which were installed in 2006. The chillers require replacement immediately. In addition, air-cooled chillers will require future replacement every 12 years at \$1,900 per ton. Replacing the PSC chillers by connecting and expanding the Jail/PSC water-cooled chiller plant provides the calculated lifecycle savings of \$4,613,975 or \$184,559 per year over the next 25 years.

**The total lifecycle replacement cost savings for the water cooled chiller plant is \$184,559 per year.**

## Capital Cost Avoidance:

Including the generators for the Jail Chiller Plant and the PSC eliminates the need for capital budgeting and creates a capital cost avoidance.

The cost of the generator installation for the Jail chiller plant (ECM 6) is \$693,450. The cost of the generator installation for the PSC (ECM 6A) is \$580,414. The annual avoided capital cost of the generators over the 15 year project term is \$84,924 per year.

**The total capital cost avoidance for the generator project is \$84,924 per year.**

The lifecycle replacement cost savings calculations and other non-energy savings information are shown in detail on the following page for your information.

# Life Cycle Cost Analysis

## Martin County Energy and Operational Savings Project - 25 Year Lifecycle Cost Analysis

### LIFECYCLE COST SAVINGS

#### Jail/PSC Chiller Plant Tie-In

##### PSC Air Cooled Chiller Replacement Cost

Replace PSC Air Cooled Chillers	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	25 Year Totals
Equipment	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
PSC Chillers												\$1,183,520												\$1,687,416		\$3,725,936
Inflation Rate												3%														
Assumptions:																										
Replace every 12 years																										
Installation Cost \$1,000/ton																										

##### PSC Chiller Milestone/Repair Savings

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25		
	\$24,357	\$	25,088	\$ 25,840	\$ 26,616	\$ 27,414	\$ 28,236	\$ 29,084	\$ 29,956	\$ 30,855	\$ 31,780	\$ 32,734	\$ 33,716	\$ 34,727	\$ 35,769	\$ 36,842	\$ 37,947	\$ 39,086	\$ 40,258	\$ 41,466	\$ 42,710	\$ 43,991	\$ 45,311	\$ 46,671	\$ 48,071	\$ 49,513	\$888,038

##### PSC Chiller Plant Lifecycle Cost Savings Summary

Chiller Replacement Cost	\$3,725,936
Milestone/Repair Savings	\$888,038
<b>Total PSC Air Cooled Chiller Lifecycle Cost</b>	<b>\$ 4,613,975</b>
<b>Annual PSC Lifecycle Cost Savings</b>	<b>\$ 184,559</b>

#### Cummings Library A/C Replacement

##### Cummings Library A/C Replacement Cost

Replace DX Split Systems	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	25 Year Totals
Equipment	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
Cummings DX Split Systems												\$899,752												\$1,282,831		\$2,832,583
Inflation Rate												3%														
Assumptions:																										
Replace 15 Air Handlers and 20 Condensing Units every 12 years																										
Installation Cost: \$650,000																										

Replace 80 ton Air Cooled Chiller	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	25 Year Totals
Equipment	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
Cummings Air Cooled Chiller												\$-207,635												\$-296,038		\$-503,673
Inflation Rate												3%														
Assumptions:																										
Replace 15 Air Handlers and 20 Condensing Units every 12 years																										
80-ton Air Cooled Chiller Replacement Cost: \$150,000																										

Cummings Library Annual GSD Repair Savings	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	25 Year Totals
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
\$10,000	\$	10,300	\$ 10,609	\$ 10,927	\$ 11,255	\$ 11,593	\$ 11,941	\$ 12,299	\$ 12,668	\$ 13,048	\$ 13,439	\$ 13,842	\$ 14,258	\$ 14,685	\$ 15,126	\$ 15,580	\$ 16,047	\$ 16,528	\$ 17,024	\$ 17,535	\$ 18,061	\$ 18,603	\$ 19,161	\$ 19,736	\$ 20,328	\$364,593

##### Cummings Library Lifecycle Cost Savings Summary

DX Split System Replacement Cost	\$2,832,583
Chiller Replacement Cost	\$503,673
Service Savings	\$364,593
<b>Total Cummings Library Lifecycle Cost</b>	<b>\$ 2,693,503</b>
<b>Annual Cummings Lifecycle Cost Savings</b>	<b>\$ 107,740</b>

### CAPITAL COST AVOIDANCE

#### Generator Cost Avoidance

Jail Chiller Plant Emergency Generator Installation	
Emergency generator installation cost	\$693,450
Assumptions: 15 project term	
<b>Annual Cost Avoidance for Emergency Generator</b>	<b>\$46,230.00 per year</b>
PSC Emergency Generator Replacement	
Emergency generator replacement cost	\$580,414
Assumptions: 15 Year Project Term	
<b>Annual Cost Avoidance for Emergency Generator</b>	<b>\$38,694.27 per year</b>
<b>Total Generator Cost Avoidance</b>	<b>\$84,924 per year</b>

### OPERATIONAL SAVINGS

#### Lighting Replacement Savings

Calculated lamp and ballast replacement savings from long life LED light sources	
<b>Total Lighting Replacement Savings</b>	<b>\$20,609 per year</b>

#### Replaced HVAC Maintenance Agreement

Chiller Service Contract for PSC Air-Cooled Chillers is Eliminated	
<b>Total Maintenance Agreement Savings</b>	<b>\$15,100 per year</b>

**Grand Total Annual Non-Energy Savings:** **\$412,932 per year**

# Energy Conservation Measures

## ECM-01 County-Wide Lighting Retrofit

For most existing lighting fixtures, the solution that Trane recommends is a Type C LED tube and driver retrofit or optional retrofit fixture. This solution is similar but more energy efficient than a Type A which relies on the existing fluorescent ballast which may or may not be in good working order or fully compatible. Type C LED retrofits provide better energy efficiency, reduced maintenance costs, and enhanced controllability, making them a more advantageous long-term solution. For the libraries, we recommend retrofit of the existing florescent troffer fixtures with center-basket "door kits" to improve aesthetics and lighting quality and uniformity. The door kit is essentially a new LED fixture that snaps into the existing fixture once the ballast, lamps, and lamp holders are removed. The center-basket style was chosen to match the style of recent LED fixtures that have been installed by the County staff in several facilities, including the Courthouse, Administration Building, and a portion of Blake Library.

The recommended lighting scope of work is represented by two energy conservation measures. ECM# 1A is the recommended interior lighting. ECM#1B is the recommended exterior pole-mounted lighting fixtures. The entire list of retrofit solutions can be found in the lighting project summary in Appendix D.

### Project Scope:

<b>Administration Center Warehouse</b>	<b>Quantity</b>
8' StripF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
8' StripF96T8 / 2L Electronic Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	12
<b>Blake Library</b>	<b>Quantity</b>
1x4 Rec. ParabolicF32T8 / 2L Electronic Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	242
2' VanityF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	4
2x2 Rec. ParabolicF32T8/U / 2L Electronic Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	268
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
4' Strip Cove / SoffitF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10

<b>Blake Library (Cont'd)</b>	<b>Quantity</b>
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	20
4' Wall BracketFP28T5 / 2L Electronic Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	3
Cylinder CFL 13w PL / CFL Replace fixture with LED Wall Brick (20w / 2700lm) - White	1
Cylinder CFL 13w PL / CFL Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	2
Jelly Jar CFL 13w PL / CFL Replace fixture with LED Wall Brick (20w / 2700lm) - White (Requires pipe & wire work)	5
Recessed Can 10" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm) w/10" Goof Ring	4
Recessed Can 12"100w MH / HID Pulse Start Retrofit fixture with 10" LED Recessed Can Kit (38w / 3600lm) w/12" Goof Ring	6
Recessed Can 12"175w MH / HID-175Retrofit fixture with 10" LED Recessed Can Kit (38w / 3600lm) w/12" Goof Ring	5
Recessed Can 6"75w Incandescent / N/A Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	2
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
<b>Building Department</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	10
<b>Citrus Grove Park</b>	<b>Quantity</b>
4' Vapor Tight w/BatteryFP28T5 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	3
4' Vapor TightFP28T5 / 2L Electronic Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	17

<b>County Line Park Community Center</b>	<b>Quantity</b>
Flood150w Incandescent / N/A Relamp fixture with PAR38 LED	1
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
<b>Court Holding</b>	
Wall Pack150w MH / HID-150Replace fixture with LED Wall Pack (35w / 4655lm)	1
<b>Court Holding - Exterior</b>	
Bollard100w MH / HID Pulse Start Retrofit fixture with LED Direct Drive Lamp - Remove ballast and direct wire socket	27
Flood250w MH / HID-250Replace fixture with LED Flood (90w / 13950lm)	1
Post Top100w MH / HID-100Relamp fixture with LED Corn Cob lamp (45w / 6300lm) - remove existing ballast and direct wire socket	8
Shoebox250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	7
Shoebox250w MH / HID-250Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	12
<b>Cummings Library</b>	<b>Quantity</b>
12' Direct/IndirectF32T8 / 2L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	5
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	12
2x2 Rec. ParabolicFB31T8/U / 3L Electronic Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	14
2x2 Rec. Parabolic PLL 40w Biax / 2L Electronic Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	3
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
2x4 Rec. Parabolic w/BatteryF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	15
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	38
4' Direct/IndirectF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	59



<b>Cummings Library (Cont'd)</b>	<b>Quantity</b>
4' Direct/IndirectF32T8 / 2L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	4
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
4' Wrap - Emergency BatteryF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Decorative Chandelier CFL 42w PL / CFL Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	65
Decorative Low Bay CFL 42w PL / CFL Retrofit fixture with (2) 16w LED Direct Drive lamp - remove ballast & direct wire socket	8
Flood CFL 42w PL / CFL Replace fixture with LED Flood (35w / 5250lm)	6
Recessed Can 10" – Horz CFL 13w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	19
Recessed Can 8" - Horz - Emergency Battery CFL 13w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	15
Recessed Can 8" – Horz CFL 13w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	42
Recessed Can 8" - Vert w/Battery CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) - Emergency Battery	11
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	15
Track SpotPAR30 75w / N/A Relamp fixture with PAR30 LED	7
Wall Mount UpLight100w MH / HID-100Relamp fixture with LED Corn Cob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	3
Wall Pack - FCT - UpLight175w MH / HID-175Relamp fixture with LED Corn Cob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	5
Wall Pack - Full Cut CFL 13w PL / CFL Replace fixture with LED Wall Pack (25w / 3525lm)	1

<b>Cummings Library (Cont'd)</b>	<b>Quantity</b>
Wall Pack CFL 42w PL / CFL Replace fixture with LED Wall Pack (25w / 3525lm)	3
<b>Cummings Library – Exterior</b>	<b>Quantity</b>
Cobrahead250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	14
<b>Fire Rescue Fleet Maintenance</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	24
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
4' Vapor TightF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	25
4' Vapor TightF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	15
High Bay400w MH / HID-400Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	15
<b>Fire Rescue Fleet Maintenance - Exterior</b>	<b>Quantity</b>
Cobrahead250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	7
<b>Fire Rescue LifeStar Hanger</b>	<b>Quantity</b>
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	35
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
High Bay1000w MH / HID-1000Replace fixture with LED High Bay (320w / 50550lm) w/wireguard & microwave motion sensor step dimming	5
<b>Fire Rescue LifeStar Hanger - Exterior</b>	<b>Quantity</b>
Flood250w MH / HID-250Replace fixture with LED Flood (90w / 13950lm)	2

<b>Fire Station #16</b>	<b>Quantity</b>
2' Wall BracketF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	9
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	21
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
4' Vapor TightF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	22
High Bay400w MH / HID-400Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	6
Recessed Can 8" – Horz CFL 32w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	25
Recessed Can 8"75w Incandescent / N/A Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	26
SconceI100A / N/A Relamp fixture with (2) A19 LED	2
<b>Fire Station #16 - Exterior</b>	<b>Quantity</b>
Cobrahead250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	8
<b>Fire Station #21</b>	<b>Quantity</b>
2' Wall BracketF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	13
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	37
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
4' Vapor TightF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	22
High Bay1000w MH / HID-1000Replace fixture with LED High Bay (320w / 50550lm) w/wireguard & microwave motion sensor step dimming	12
Recessed Can 8" – Vert CFL 18w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4

<b>Fire Station #21 (Cont'd)</b>	<b>Quantity</b>
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	25
Recessed Can 8"75w Incandescent / N/A Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
<b>Fire Station #21 - Exterior</b>	<b>Quantity</b>
Cobrahead250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	10
Flood150w MH / HID-150Replace fixture with LED Flood (35w / 5250lm)	2
<b>Fire Station #22</b>	<b>Quantity</b>
2x2 Rec. AcrylicF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	17
2x2 Rec. Parabolic w/BatteryF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	2
2x4 High BayFP54T5HO / 4L Electronic Replace fixture with LED High Bay (100w / 16500lm) w/Clear Reflector & microwave motion sensor step dimming	7
2x4 Rec. Acrylic w/BatteryF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	2
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
4' Vapor TightF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	9
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	14
Recessed Can 8" – Horz CFL 32w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Recessed Can 8" – Horz CFL 42w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	9
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Wall Pack CFL 42w PL / CFL Replace fixture with LED Wall Pack (25w / 3525lm)	2

<b>Fire Station #23</b>	<b>Quantity</b>
2' Wall BracketF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	6
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	22
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
4' Vapor TightF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Bulkhead CFL 26w PL / CFL Replace fixture with LED Wall Pack (25w / 3525lm)	11
High Bay400w MH / HID-400Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	9
Jelly Jar CFL 23w Screw In / Integral CFL Relamp fixture with PAR30 LED	1
Jelly JarI100A / N/A Relamp fixture with A19 LED	1
Recessed Can 8" - Vert w/Battery CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	4
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	25
Recessed Can 8" – Vert CFL 32w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Recessed CanI100A / N/A Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	30
SconceI100A / N/A Relamp fixture with (2) A19 LED	2
<b>Fire Station #23 - Exterior</b>	<b>Quantity</b>
Flood CFL 42w PL / CFL Replace fixture with LED Flood (35w / 5250lm)	4
Shoebox250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	2
Shoebox250w MH / HID-250Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	2

<b>Fire Station #30</b>	<b>Quantity</b>
2' Wall BracketF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	2
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
2x4 Rec. Parabolic w/BatteryF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	4
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	17
4' Strip Cove / SoffitF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
4' Vapor TightF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	9
Exit Sign w/battery & lightsI20T / N/A Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	2
High Bay400w MH / HID-400Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	9
Recessed Can 8" – Horz CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	20
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Recessed Can 8"CFL 18w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Track Head CFL 23w Screw In / Integral CFL Relamp fixture with PAR30 LED	2
<b>Fire Station #32</b>	<b>Quantity</b>
1x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	11

<b>Fire Station #32 (Cont'd)</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	19
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	13
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Decorative Wall Coach70w MH / HID-70Relamp fixture with LED Corn Cob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	1
High Bay400w MH / HID-400Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	16
Jelly Jar CFL 13w Screw in / Integral CFL Relamp fixture with A19 LED	2
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Recessed Can 8"75w Incandescent / N/A Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	7
Wall Pack150w MH / HID-150Replace fixture with LED Wall Pack (35w / 4655lm)	3
<b>General Services Complex</b>	<b>Quantity</b>
2' StripF20T12 / FL Magnetic ES Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
2' Wall BracketF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
2x2 Rec. ParabolicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
2x2 Surf. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	11
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
2x4 Surf. AcrylicF32T8 / 2L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	17
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8



<b>General Services Complex (Cont'd)</b>	<b>Quantity</b>
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
4' WrapF32T8 / 2L Electronic Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	4
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	31
4' WrapF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	30
4' WrapF34T12 / FL Magnetic ES Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
8' StripF96T8 / 2L Electronic Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	4
Ceiling Mount60w Incandescent / N/A Relamp fixture with A19 LED	1
Decorative Suspended60w Incandescent / N/A Relamp fixture with A19 LED	1
Exit Sign w/battery & lightsI20T / N/A Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	1
Recessed Can 6"II100A / N/A Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	1
Wall Pack - FLD70w MH / HID-70Replace fixture with LED Wall Pack (15w / 2160lm)	3
Wall Pack175w MH / HID-175Replace fixture with LED Wall Pack (25w / 3525lm)	1
Wall Pack CFL 26w PL / CFL Replace fixture with LED Wall Pack (25w / 3525lm)	2
<b>Historical Courthouse</b>	<b>Quantity</b>
Ceiling Drum CFL 13w PL / CFL Replace fixture with LED Flush Mount	3
Decorative Surface CFL 32w / CFL Replace fixture with LED Flush Mount	5
<b>Hobe Sound Civic Center - Community Center</b>	<b>Quantity</b>
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	7
4' WrapF34T12 / FL Magnetic ES Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Exit Sign w/battery & lightsI20T / N/A Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	3

<b>Hoke Library</b>	<b>Quantity</b>
2x2 Rec. ParabolicF32T8/U / 2L Electronic Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	5
2x4 Rec. Parabolic w/Battery4' TLED T8 / N/A Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
2x4 Rec. Parabolic w/BatteryF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	6
2x4 Rec. Parabolic4' TLED T8 / N/A Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	15
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	120
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
4' Strip Cove / SoffitF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Modular TrackMR16 / N/A Relamp fixture with LED MR16 (Verify base & optics)	12
Recessed Can 6" – Vert CFL 18w PL / CFL Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	6
Recessed Can 6" – Vert CFL 26w PL / CFL Retrofit fixture with 6" LED Recessed Can Kit (13w / 1250lm)	6
Recessed Can 8" – Vert CFL 18w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	7
Recessed Can 8" – Ver tCFL 32w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
SconceI100A / N/A Relamp fixture with (2) A19 LED	2
Surface Mount CFL 13w PL / CFL Replace fixture with LED Wall Brick (20w / 2700lm) - White	3
Wall Pack - FCT - UpLight175w MH / HID-175Relamp fixture with LED Corn Cob lamp (45w / 6300lm) - remove existing ballast and direct wire socket	4

<b>Hoke Library (Cont'd)</b>	<b>Quantity</b>
Wall Pack175w MH / HID-175Replace fixture with LED Wall Pack (25w / 3525lm)	3
<b>Hoke Library - Exterior</b>	<b>Quantity</b>
Shoebox250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	5
Shoebox250w MH / HID-250Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	4
<b>Indian Riverside Park - Children's Museum</b>	<b>Quantity</b>
2' VanityF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	4
2' Wrap2' TLED / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	13
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
2x4 Rec. Acrylic4' TLED T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	16
4' Direct/Indirect4' TLED T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	35
4' Strip4' TLED T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	16
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
4' Wrap4' TLED T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
4' Wrap4' TLED T8 / 2L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
4' WrapF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Exit Sign w/battery & lightsI20T / N/A Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	2
Wall Pack150w MH / HID-150Replace fixture with LED Wall Pack (35w / 4655lm)	6

<b>Indiantown Health Department</b>	<b>Quantity</b>
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	16
2x2 Rec. AcrylicF34T12/U / FL Magnetic ES Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	5
2x2 Surf. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	84
2x4 Rec. AcrylicF34T12 / FL Magnetic ES Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
4' WrapF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	7
4' WrapF34T12 / FL Magnetic ES Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Sconce CFL 13w Screw in / Integral CFL Relamp fixture with A19 LED	1
<b>Indiantown Health Department - Exterior</b>	<b>Quantity</b>
Shoebox250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	3
<b>Jensen Beach Community Center</b>	<b>Quantity</b>
3' Decorative SconceF25T8 / 2L Electronic Retrofit fixture with (2) 3' T8 LED Linear Tube and Normal Power LED Driver	9
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	9
Keyless CFL 55w / N/A Relamp fixture with A19 LED	1
Recessed Can 8" - Vert w/Battery CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	7
Recessed Can 8" - Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	11
Lahti Library	229
2x2 Rec. Parabolic w/BatteryF32T8/U / 2L Electronic Retrofit fixture with 2x2 LED Door Kit w/Emergency Battery (24w / 3168lm)	2
2x2 Rec. ParabolicF32T8/U / 2L Electronic Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	41
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	4

<b>Jensen Beach Community Center (Cont'd)</b>	<b>Quantity</b>
4' Direct/IndirectF32T8 / 2L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	20
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
4' WrapF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Recessed Can 4"MR16 / N/A Relamp fixture with LED MR16 (Verify base & optics)	3
<b>Lahti Library - Exterior</b>	<b>Quantity</b>
Shoebox250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	4
<b>Langford Park</b>	<b>Quantity</b>
1x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
2' StripF20T12 / FL Magnetic ES Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	95
4' StripF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
4' StripF34T12 / FL Magnetic ES Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
4' VanityF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Exit Sign w/battery & lightsI20T / N/A Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	3
Recessed Can 10" - Horz w/battery CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	14
Recessed Can 6"60w Incandescent / N/A Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	8

<b>Langford Park (Cont'd)</b>	<b>Quantity</b>
Recessed Can 8" – Horz CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	3
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
SconceI100A / N/A Relamp fixture with (2) A19 LED	2
<b>Martin County Landfill</b>	<b>Quantity</b>
2' WrapF17T8 / 2L Electronic Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	2
2x4 Rec. Acrylic4' TLED T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
2x4 Rec. Parabolic4' TLED T8 / N/A Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	8
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	28
4' Direct/Indirect4' TLED T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	18
4' Vapor TightF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	37
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	5
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
4' WrapF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
8' IndustrialF96T8 / 2L Electronic Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	26
8' StripF96T12ES / F2em96Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	5
High Bay400w MH / HID-400Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	1
Recessed Can 8" I100A / N/A Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Wall Pack150w MH / HID-150Replace fixture with LED Wall Pack (35w / 4655lm)	5

<b>Martin County Landfill - Exterior</b>	<b>Quantity</b>
Flood400w MH / HID-400Replace fixture with LED Flood (90w / 13950lm)	1
<b>Martin County Tax Collector</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	180
Globe60w Incandescent / N/A Relamp fixture with A19 LED	2
<b>Mc DRC (Old EOC)</b>	<b>Quantity</b>
1x4 Rec. ParabolicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	9
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	5
<b>MCSO Aviation Hanger</b>	<b>Quantity</b>
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	20
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
<b>MCSO Aviation Hanger - Exterior</b>	<b>Quantity</b>
Flood250w MH / HID-250Replace fixture with LED Flood (90w / 13950lm)	2
<b>Morgade Library</b>	<b>Quantity</b>
1x4 Rec. ParabolicF32T8 / 2L Electronic Retrofit fixture with 1x4 LED Door Kit (24w / 3168lm)	10
2x2 Rec. ParabolicF32T8/U / 2L Electronic Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	22
2x4 Rec. Acrylic4' TLED T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	7
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	18
2x4 Rec. Parabolic - Emergency BatteryF32T8 / 4L Electronic Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	6
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
2x4 Rec. ParabolicF32T8 / 4L Electronic Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	125

<b>Morgade Library (Cont'd)</b>	<b>Quantity</b>
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	8
4' Strip Cove / SoffitF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	48
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Decorative Chandelier CFL 42w PL / CFL Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	14
Exit Sign w/battery & lightsI20T / N/A Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	3
Recessed Can 4"MR16 / N/A Relamp fixture with LED MR16 (Verify base & optics)	4
Recessed Can 8" – Vert CFL 18w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	41
Recessed Can 8" – Vert CFL 26w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	18
TrackI100A / N/A Relamp fixture with PAR30 LED	4
Wall Mount UpLight100w MH / HID-100Relamp fixture with LED Corn Cob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	8
<b>Morgade Library - Exterior</b>	<b>Quantity</b>
Shoebox250w MH / HID-250Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	8
Shoebox250w MH / HID-250Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	4
<b>New Monrovia Park Community Center</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
2x4 Rec. ParabolicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	22
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Jelly Jar60w Incandescent / N/A Relamp fixture with A19 LED	1



<b>New Monrovia Park Community Center (Cont'd)</b>	<b>Quantity</b>
Recessed Can 8" – Horz CFL 13w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	9
<b>New Monrovia Sheriff Substation</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	24
Wall Pack150w MH / HID-150Replace fixture with LED Wall Pack (35w / 4655lm)	3
<b>Public Safety Complex</b>	<b>Quantity</b>
12' Direct/IndirectF32T8 / 2L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	45
1x4 Rec. Acrylic4' TLED T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	9
1x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	21
1x4 Rec. ParabolicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	27
2x2 Rec. Acrylic4' TLED - T8U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	211
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	17
2x2 Rec. AcrylicF34T12/U / FL Magnetic ES Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
2x2 Rec. ParabolicFB31T8/U / 3L Electronic Retrofit fixture with (3) 2' T8 LED Linear Tube and Normal Power LED Driver	4
2x4 High BayFP54T5HO / 4L Electronic Replace fixture with LED High Bay (100w / 16500lm) w/Clear Reflector & microwave motion sensor step dimming	34
2x4 Rec. Acrylic4' TLED T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	25
2x4 Rec. Acrylic4' TLED T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	35
2x4 Rec. Acrylic4' TLED T8 / N/A Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	142
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	81

<b>Public Safety Complex (Cont'd)</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	38
2x4 Rec. AcrylicF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	148
2x4 Rec. VolumetricF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	176
4' Direct/IndirectF32T8 / 2L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	11
4' IndustrialF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	39
4' Vapor Tight4' TLED T8 / N/A Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
4' Vapor TightF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	23
4' Wall Bracket w/BatteryF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	10
4' Wall BracketF32T8 / 2L Electronic Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	16
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
4' WrapF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
8' Indirect Up4' TLED T8 / N/A Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	10
8' Industrial4' TLED T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
8' IndustrialF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	7
8' Louvered Up/Down4' TLED T8 / N/A Retrofit fixture with (6) 4' T8 LED Linear Tube and (3) Normal Power LED Driver	18
Bulkhead CFL 26w PL / CFL Relamp fixture with LED Corn Cob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	2
High Bay1000w MH / HID-1000Replace fixture with LED High Bay (320w / 50550lm) w/wireguard & microwave motion sensor step dimming	1
Recessed Can 10" – Horz CFL 13w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	8

<b>Public Safety Complex (Cont'd)</b>	<b>Quantity</b>
Recessed Can 4"MR16 / N/A Relamp fixture with LED MR16 (Verify base & optics)	5
Recessed Can 6"60w Incandescent / N/A Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	2
Recessed Can 6"100A / N/A Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	10
Recessed Can 8" – Horz CFL 32w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	30
Recessed Can 8" - Vert w/Battery CFL 32w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	14
Recessed Can 8" – Vert CFL 13w PL / CFL Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	12
Recessed Can 8"60w Incandescent / N/A Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	42
Recessed Square70w HPS / HID-70Retrofit fixture with LED Rectangular Kit (12w / 1600lm)	39
Surface Mount CFL 13w PL / CFL Retrofit fixture with LED Circular Kit (13.5w / 2150lm)	5
Track100A / N/A Relamp fixture with PAR30 LED	3
Wall Pack150w MH / HID-150Replace fixture with LED Wall Pack (35w / 4655lm)	38
Wall Pack70w HPS / HID-70Replace fixture with LED Wall Pack (15w / 2160lm)	1
<b>Supervisor of Elections</b>	<b>Quantity</b>
2x2 Rec. AcrylicF32T8/U / 2L Electronic Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
2x4 Rec. AcrylicF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	61
4' WrapF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
8' StripF32T8 / 4L Electronic Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	13
Keyless CFL 23w Screw In / Integral CFL Relamp fixture with A19 LED	1
Recessed Can 8"75w Incandescent / N/A Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	10

<b>Witham Field Customs Building</b>	<b>Quantity</b>
2x4 Rec. AcrylicF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10
2x4 Rec. Volumetric w/BatteryF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	5
2x4 Rec. VolumetricF32T8 / 2L Electronic Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	18
4' Tamper ProofF32T8 / 3L Electronic Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Recessed Can 10" – Horz CFL 26w PL / CF LRetrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm) w/10" Goof Ring	16
<b>Grand Total</b>	<b>8168</b>

### Interior Lighting Operating Hours

<b>Area Type</b>	<b>Average of Annual Hrs. (Adjusted -20% for Existing Sensors)</b>
Auditorium	1560
Auditorium - Seating	2080
Auditorium - Stage	1560
Break / Lounge	2269
Bunk Room	1037
Café / Dining Area	2340
Chiller Plant Area	1040
Classroom - Computer Lab	3120
Classroom - General	2080
Classroom - Shop / Vocational	2080
Classroom - Study Room	2212
Conference Room	2000
Copy Room	2080
Corridor / Hallway	2543
Corridor / Hallway - Suite / Dept	2586
Custodial Closet	1012
Dayroom	4230
Electrical / Mech	501
Exam / Treatment	2080
Exterior	4363
Exterior - Parking / Grounds	4368
Food Services Areas	2080
Generator Room	1040

<b>Area Type</b>	<b>Average of Annual Hrs. (Adjusted -20% for Existing Sensors)</b>
Gymnasium	1729
Hanger	3640
Holding Cell	4368
Kitchen	2024
Kitchen - Storage	2080
Lab Area	2080
Laundry - Small	1780
Library	2214
Lobby Area - Main	2510
Locker Room	2092
Locker Room - Showers	1040
Mail Room / Distribution Center	2340
Maintenance Shop	3120
Mechanical Room	1037
Multi Purpose	2304
Office - Admin Area	2321
Office - Open Cubicals	2330
Office - Private	2323
Restroom - Public	1997
Server / Com Room	1004
Stairwell - Interior	8611
Storage - Equipment	2011
Storage - General	2046
Storage - Records	2080
Training Room	2080
Truck Bay	8584
Vestible / Foyer	2542
Waiting Room	2175
Warehouse	2556
Workroom	2256
Average	2532

## Energy Savings

Savings for this measure were calculated with spreadsheet calculations. A detailed line-by-line of the existing and proposed conditions for each lighting fixture is shown in Appendix C. The electric demand (kW) savings were calculated by subtracting the proposed wattage from the existing wattage. The electric consumption (kWh) savings were calculated by multiplying the demand savings by the runtime hours. Occupancy sensor savings were also factored into the calculations by reducing the runtime hours in certain areas. Additionally, savings were also included for

reduced air conditioning load due to the reduced heat gain from LED lights as compared to fluorescent fixtures.

**Figure 9: Interior Lighting Energy Savings**

**Calculated Energy Savings**

Facility	Electric Consumption kWh Saved	Electric Demand kW Saved	Water kgal Saved
Martin County	939,888	2,887	

**Operation and Maintenance Savings**

There are operation and maintenance savings because of implementing this ECM. The new LED lighting upgrades are expected to reduce the materials and labor necessary to maintain lighting across the College. The implementation of this ECM reduces the cost expenditure for materials that were formerly required to maintain the existing lighting, offering longer material life span than fluorescents and reducing the instance of failed lamps. An LED upgrade can result in fewer lamps needing to be changed and eliminate the labor hours of servicing lights.

## ECM-02 Water Conservation

Trane audited bathroom and potable water fixtures at all Martin County locations in all areas. Our auditors recorded fixture locations, quantities, makes and models, and rated flows. The auditors also took water pressure measurements, noted site conditions, and documented site conditions for the project. Many of the existing fixtures meet current design guidelines and are not recommended for replacement. The recommended replacement scope of work is shown below. The showerhead replacements for the fire stations were removed from the project. More detailed scope and warranty information is included in Appendix E.

### Project Scope:

Location/Pre and Post Retrofit	Sum of QTY
<b>Administrative Center</b>	
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm 1.6 GPF Diaphragm Toilet Valve Kit	1
2.2 GPM Faucet Aerator Female 1.5 GPM Kitchen Faucet Aerator	1
<b>Blake Library</b>	
1.0 GPM Faucet Aerator Female 0.5 GPM Faucet Aerator	2
1.5 GPM Faucet Aerator Female 0.5 GPM Faucet Aerator	3
1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm 1.6 GPF Diaphragm Toilet Valve Kit	1
2.0 GPM Faucet Aerator Female 0.5 GPM Faucet Aerator	5
2.2 GPM Faucet Aerator Female 0.5 GPM Faucet Aerator	5
2.5 GPM Faucet Aerator Female 0.5 GPM Faucet Aerator	2
<b>Building Department</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount 0.5 GPF Diaphragm Urinal Valve Kit	2
1.8 GPM Faucet Aerator Female 1.5 GPM Kitchen Faucet Aerator	2
<b>Building Maintenance Shop</b>	
1.8 GPM Faucet Aerator Female 1.5 GPM Kitchen Faucet Aerator	1
<b>Citrus Grove Park</b>	
2.0 GPM Faucet Aerator Female 1.5 GPM Kitchen Faucet Aerator	1
4.0 GPM Faucet Aerator Female 1.5 GPM Kitchen Faucet Aerator	2
<b>Cob Building</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount 0.5 GPF Diaphragm Urinal Valve Kit	2

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Cob Building (Cont'd)</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	2
1.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
1.25 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	3
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	16
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	6
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	4
1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	3
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	3
2.2 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	5
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>County Line Park - Community Center</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)0.5 GPF Diaphragm Urinal Valve Kit	1
3.5 GPF/3.5 GPF Floor Mount Tank Type Water Closet1.28 GPF Floor Mount Tank Type Toilet with Gravity Tank and Bowl STD w/ Seat minus cover	1
<b>Court Holding</b>	
1.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	1
1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
3.5 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm1.28 GPF Floor Mount Top Spud Toilet STD, Diaphragm Flush Valve w/Seat minus Cover	1
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Courthouse</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	40



<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Courthouse (Cont'd)</b>	
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	2
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	5
1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	1
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	2
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	9
<b>Courthouse Cultural Center (Historical Designation)</b>	
<b>Cummings Library</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	2
1.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	3
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	3
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	4
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
<b>Field Operations</b>	
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
2.2 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
<b>Fire Rescue Lifestar Hangar</b>	
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Fire Station 16 Kitchen</b>	
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Fire Station 16 Restroom</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
<b>Fire Station 16 Restrooms near gym</b>	
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
<b>Fire Station 16 Shop</b>	
3.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Fire Station 21</b>	
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	1
1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Side Mount <6vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	3
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	5
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Fire Station 22</b>	
4.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
<b>Fire Station 23</b>	
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
<b>Fire Station 24</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	2
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	5
<b>Fire Station 30</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
4.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	3
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Fire Station 32</b>	
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	3
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Halpatickee Regional Park</b>	
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	5

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Hobe Sound Civic Center - Community Center</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	1
1.25 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
3.5 GPF/3.5 GPF Floor Mount Tank Type Water Closet1.28 GPF Floor Mount Tank Type Toilet with Gravity Tank and Bowl STD w/ Seat minus cover	1
<b>Hoke Library</b>	
1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Holt Administration</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	4
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
3.5 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 21vBt Diaphragm1.28 GPF Floor Mount Top Spud Toilet STD, Diaphragm Flush Valve w/Seat minus Cover	1
<b>Indian Riverside Park - Sailing Center Building</b>	
1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	2
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	4
2.2 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	4
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	4
<b>Indian Riverside Park-Children'S Museum</b>	
1.5 GPM Faucet Aerator Faucet Sensor Female0.5 GPM Faucet Aerator	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Indiantown Annex</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	6
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	4

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Indiantown Education Center</b>	
<b>Indiantown Health Department</b>	
1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	3
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Jensen Beach Community Center</b>	
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	2
<b>Jensen Beach Ocean Rescue</b>	8
1.25 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	1
<b>Jensen Beach Park</b>	
1.75 GPM Standard Showerhead1.5 GPM Standard Showerhead	6
<b>Jimmy Graham Park</b>	
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
<b>Jock Leighton Park</b>	
1.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	5
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	1
1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
3.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
<b>JV Reed Park</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)0.5 GPF Diaphragm Urinal Valve Kit	2
2.5 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
3.5 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm1.28 GPF Floor Mount Top Spud Toilet STD, Diaphragm Flush Valve w/Seat minus Cover	1
<b>Lahti Library</b>	
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Lahti Library (Cont'd)</b>	
2.2 GPM Faucet Aerator Faucet Sensor Female1.5 GPM Kitchen Faucet Aerator	1
<b>Lamar Howard Park</b>	
2.0 GPM Faucet Aerator Female0.5 GPM 4in Centerset, Deck Mount, Faucet	1
<b>Lamar Howard Park - Cassidy Community Center</b>	
<b>Landfill Breakroom Building</b>	
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Landfill Hazmat/Transfer Station</b>	
0.5 GPM Faucet Aerator	3
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.2 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
4.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
<b>Landfill Maintenance Shop</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
<b>Landfill Scalehouse</b>	
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	1
<b>Langford Park</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)0.5 GPF Diaphragm Urinal Valve Kit	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Langford Park - Vince Bocchino Community Center</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)0.5 GPF Diaphragm Urinal Valve Kit	2
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>LCpl Justin Wilson Park</b>	
2.0 GPM Faucet Aerator Female0.5 GPM 4in Centerset, Deck Mount, Faucet	6
<b>Martin County Tax Collector Offices</b>	
<b>Mary Brogan Park</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Mc Drc (Old Eoc)</b>	
0.125 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	1
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Mcso Aviation Hangar</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	2
<b>Morgade Library</b>	
1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	5
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
<b>Mosquito Control Office</b>	
4.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
<b>New Fleet Maintenance</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	1
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>New Monrovia Park - Costella Williams Learning Center/Community Center</b>	
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	3
<b>New Monrovia Sheriff Substation</b>	
1.25 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Park Operations Compound</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	2
<b>Pineapple Park</b>	

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Port Salerno Civic Center</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)0.5 GPF Diaphragm Urinal Valve Kit	1
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Public Safety Complex</b>	
0.5 GPM Faucet Aerator	3
1.5 GPM Faucet Aerator Faucet Sensor Female0.5 GPM Faucet Aerator	1
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	5
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Piston1.6 GPF Diaphragm Toilet Valve Kit	1
1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston1.6 GPF Diaphragm Toilet Valve Kit	2
1.8 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	3
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	6
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	2
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	9
<b>Rio Civic Center</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	1
3.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Sailfish Splash Water Park</b>	
1.75 GPM Standard Showerhead1.5 GPM Standard Showerhead	8
2.2 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	1
2.5 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	3
4.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Stuart Beach Park</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	4
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	3
2.0 GPM Standard Showerhead1.5 GPM Standard Showerhead	12
<b>Supervisor Of Elections Office</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	5
2.0 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>Timer Powers Park</b>	
0.125 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	2

<b>Location/Pre and Post Retrofit</b>	<b>Sum of QTY</b>
<b>Timer Powers Park (Cont'd)</b>	
1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	1
1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed 21vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	4
2.0 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	4
<b>Traffic Management Center</b>	
<b>Vehicle Maintenance Shop</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	4
2.2 GPM Faucet Aerator Female1.5 GPM Kitchen Faucet Aerator	1
<b>William Doc Myers Park</b>	
<b>Willoughby Commons Usd Office</b>	
1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed0.5 GPF Diaphragm Urinal Valve Kit	1
<b>Willoughby Mpo Office</b>	
<b>Willoughby Property Appraiser's Office</b>	
0.125 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount0.5 GPF Diaphragm Urinal Valve Kit	1
<b>Witham Field Customs Building</b>	
1.5 GPM Faucet Aerator Female0.5 GPM Faucet Aerator	4
2.5 GPM Standard Showerhead1.5 GPM Standard Showerhead	2
<b>Wojcieszak Park</b>	
1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm1.6 GPF Diaphragm Toilet Valve Kit	5



Energy Savings

Savings for this measure were calculated with spreadsheet calculations.

Figure 11: Water Conservation Calculated Energy Savings

Facility	Electric Consumption kWh Saved	Water kgal	Therms Saved
Martin County	23,336	1,649	1,077

Operation and Maintenance Savings

The existing plumbing fixtures are inefficient and require replacement due to age and condition. If replacement plumbing fixtures were not provided in this Agreement, then the direct cost would be incurred by Customer to repair or replace water fixtures.


## ECM-04 Public Safety Complex Chiller Plant Tie-In

Primary cooling for the Public Safety Complex is provided by two (2) 225-ton air-cooled chillers, serial numbers UU06J08529 and U06J08530. These chillers were installed with the original construction of the PSC in 2006. In 2012, the chillers were refurbished to extend their service life and the compressors and condensing coils were replaced. The chillers require immediate replacement now. The expected service life of an air cooled chiller on the Treasure Coast is approximately 10-12 years.

The Jail chiller plant was built with future capacity to serve the Public Safety Complex. The Jail chiller plant has two nominal 400-ton water-cooled chillers with associated cooling towers and pumps. The Jail chiller plant is a packaged chiller plant that was designed with a spare chiller bay with pumps, piping, and electrical switchgear for a future third water-cooled chiller. The Jail chiller plant serves a total connected cooling load of approximately 430 tons and serves the Holt Correctional Jail as well as additional facilities including Reduced Custody, the Public Safety Gym, and the Sheriff's Kennel. The existing chillers, towers and pumps provide 100% redundancy for current connected cooling loads for the Jail and other connected facilities.

Connecting the Jail Chiller Plant to the Public Safety Complex eliminates the need to replace the existing PSC air-cooled chillers. Also, the repair and maintenance cost the PSC air-cooled chillers are avoided. The water-cooled chillers in the Jail chiller plant are 5 years old and have an expected service lifetime of 25 years. Connection to the Jail chiller plant provides significant energy and operational savings.

### Connection of PSC to Jail Chiller Plant:



## **Proposed Solution**

The Jail chiller plant will be expanded with the addition of a new nominal Trane HDWA 400-ton chiller and Tower Tech 400-ton cooling tower cell. The new cooling tower matches the existing towers at the jail chiller plant. The Jail chiller plant will be connected to the PSC with new 6" chilled water supply and return piping. The new chilled water lines will be installed with directional boring for the new HDPE underground chilled water piping. The existing chiller plant was designed to add a third chiller. The chiller and tower connect to the existing piping and switchgear which is designed for the new chiller #3. The existing 225 ton air-cooled chillers at the Public Safety Complex (PSC) will be removed. Changes to the generator capacity for the Jail chiller plant and the PSC are also recommended and are described as part of additional energy conservation measures below.

## **Equipment Selections:**

One (1) 400- ton HDWA Trane magnetic bearing water-cooled chiller

One (1) Tower Tech TTXR 400-ton crossflow cooling tower

One (1) 30 HP (480/3) Trane TRD200 variable frequency drive for new cooling tower

Trane will provide MEP and structural permit type design drawings and specifications to cover the proposed scope of work.

## **Scope of Work - Mechanical**

Project will be phased to install new chiller/tower and underground piping while the Jail and other connected facilities continue to run on existing chiller plant. Scheduled shutdowns for piping connections will be scheduled and planned in advance with County staff.

Trane will furnish a 400 ton water cooled Agility chiller and a 400 ton Tower Tech cooling tower. Trane will receive chiller and cooling tower. All required handling, shipping, rigging, and crane service is included.

Trane will install new 400-ton HDWA water-cooled chiller in the Jail Chiller Plant. New chillers will be rigged into place through existing rollup door and set by without disassembly into the empty chiller #3 bay in the existing plant.

Trane will modify the plant to accept a new steel structure to support the new chiller which has a shorter overall length. The plate floor will be modified as required.

Trane will rig and set the new chiller in place. Trane will provide complete mechanical and electrical installation of the new 400-ton HDWA water-cooled chiller. New valves and piping specialties will be furnished and installed. The new piping will be insulated in cellular foam glass to match existing.

Trane will install new concrete footers and anchor bolts for new cooling tower cell to extend and add additional tower cell to the existing two-cell tower. Trane will extend existing condenser water piping, drain piping, and makeup water piping to new cooling tower cell as required.

Trane will furnish and install new chilled water supply and return piping in 6" HDPE from the Jail Chiller Plant to the PSC chiller connection point. Piping installation will be performed by directional boring for new the new chilled water mains. Piping specification is SDR-11 200psi class HDPE. The HDPE piping will be installed without insulation.

Trane will connect new chilled water supply and return piping to the existing chiller connection at the PSC and will furnish and install new manual isolation valves. The chillers will be demolished and removed from the jobsite. A blank flange and manual isolation valve will be added to the remaining existing chiller connection to provide a new temporary cooling connection point.

Trane will provide factory startup of new chiller and cooling tower. Trane will address any installation issues noted on chiller startup.

No mechanical modifications are required at the PSC to the existing building chilled water pumps. The existing ball valves in the bypass leg of the existing three-way control valves will be closed to convert the existing valves to two-way operation.

After the PSC is running on the new piping from the Jail Chiller Plant, Trane will demo two (2) existing 225 ton Trane RTAA air-cooled chillers located at the PSC in the equipment yard. Trane will remove and dispose of the chillers off site. The removal and replacement of the chiller/generator yard roof screening will be coordinated with the County.

### **Scope of Work – Chiller Plant Controls**

The Trane BAS consists of a Trane centralized system controller which will provide a web based graphical interface to include trending, reporting, archiving, scheduling, and alarm management capabilities. The Trane BAS is a BACnet/IP system and Martin County shall be responsible for providing all BACnet/IP network connection points. The scope includes controllers, necessary new end devices, labor, engineering, project management, and installation as noted below.

## **TIE-IN TO EXISTING TRACER ENSEMBLE ENTERPRISE-WIDE FACILITY MANAGEMENT SYSTEM**

### **EXISTING TRACER SC+ WEB ENABLED SYSTEM CONTROLLER**

- Tie-in new Trane BACnet controller to existing Tracer SC+
- 5-year Software Maintenance Plan (SMP)
- AHU Trends capability
- Local & Remote Alarms Set-up
- Web-based mobile access available

### **CHILLED WATER SYSTEM CONTROLS, INCLUDING:**

- Chiller-3 CHWS Temperature Sensor
- Chiller-3 CHWR Temperature Sensor
- Chiller-3 CWS Temperature Sensor
- Chiller-3 CWR Temperature Sensor
- Chiller-3 CHW Differential Pressure Transmitter
- Chiller-3 CW Differential Pressure Transmitter
- Replacement of existing Chiller-1 & 2 CHW Differential Pressure Transmitter
- Replacement of existing Chiller-1 & 2 CW Differential Pressure Transmitter
- Chiller-3 Start/Stop
- BTU Meter (qty: 2)
- Chiller-3 Chilled Water Isolation Valve Control
- Chiller-3 Condenser Water Isolation Valve Control
- Cooling Tower-3 Condenser Water Supply Isolation Valve Control
- Cooling Tower-3 Condenser Water Return Isolation Valve Control
- BACnet CCD Controller

## **Scope of Work – PSC Controls**

## **TIE-IN TO EXISTING TRACER ENSEMBLE ENTERPRISE-WIDE FACILITY MANAGEMENT SYSTEM**

### **EXISTING TRACER SC WEB ENABLED SYSTEM CONTROLLER**

- Upgrade to new Tracer SC+ web enabled system controller
- Tie-in new Trane BACnet controller to new Tracer SC+
- 5-year Software Maintenance Plan (SMP)
- AHU Trends capability
- Local & Remote Alarms Set-up
- Web-based mobile access available

### **TERTIARY CHILLED WATER PUMP CONTROLS, INCLUDING:**

- Chilled Water Differential Pressure Transmitter
- Trane TRD200 Variable Frequency Drive with Manual Bypass

**SPACE TEMPERATURE AND HUMIDITY MONITORING, TYPICAL FOR (20), INCLUDING:**

- AirFi Wireless Coordinators (two per floor)
- AirFi Wireless Space Temperature, relative humidity, carbon dioxide (CO<sub>2</sub>) and occupancy sensors

**Calculated Utility Savings**

**Calculated Energy Savings**

Facility	Electric Consumption kWh Saved	Electric Demand kW Saved	Water kgal Saved
Public Safety Complex	676,469	1,154	-2536

## ECM-05 Cummings Library A/C Replacement

Cummings Library is the last remaining facility in the County with an air conditioning system that utilizes split system direct expansion (DX) air conditioning systems that are based on R-22 refrigerant. R-22 has been phased out of production and use since it is an Ozone Depleting Substance. The air conditioning systems at Cummings Library date back to 2008 when the facility was expanded. Replacement of the air conditioning systems is required now.

### Existing Systems:

The original library and the two-story expansion utilize split-system air conditioning units. The original library was built in 1995. The two-story addition was added in 2008. The original library uses single zone constant volume air handling units. There are seven air handlers and nine condensing units in the original library. The old section of the library has significant humidity control problems and system upgrade is a priority. Outside air is introduced to the main cooling coil without a separate dehumidification system. Humidity control in the original library is very poor due to the use of split system air conditioners without adequate humidity control. When the space temperature becomes satisfied the compressors shut off and there is no dehumidification. The new section of the library has a dedicated outside air system. The air conditioning units for the new library section require replacement due to age and condition.

The existing Trane Tracer SC+ system controller was upgraded to replace the original and obsolete building control unit. The controllers for the 13 split system a/c units are obsolete and require replacement. Replacement parts for the existing split system a/c unit controllers are no longer available and are not supported.

### Refrigerant Phaseout and Global Warming Potential:

Refrigerants have been phased out of production and use in air conditioning systems based initially on their Ozone Depletion Potential (ODP). R-22, which is present at Cummings Library, is an Ozone Depleting Substance. Conversion to a similar refrigerant that does not harm the ozone layer, R-410a, was completed by EPA phaseout in 2013.

A new refrigerant phaseout is happening now based on Global Warming Potential (GWP) which is the relative emissions of the refrigerant versus carbon dioxide as a baseline. Refrigerants that were chosen as alternatives based on their low Ozone Depletion Potential (ODP) are now being phased out based on their Global Warming Potential (GWP). For example, the ODP of R-410a is 0.055 but the GWP of R-410a is 2,087. This means that R-410a traps heat in the upper atmosphere 2,087 times as much as carbon dioxide. The phase out date for R-410a in commercial split systems a/c units was January 1, 2025.

There is no consensus among the air conditioning industry about which alternative refrigerant will be selected. It appears that major manufacturers will select different refrigerants for the

same type of equipment. The major concern about the available alternative refrigerants is flammability and safety. The secondary concern is compatibility.

There is very limited guidance available now on how to manage life safety issues related to flammable refrigerants in commercial and residential buildings from a code compliance perspective. The current guidance is that each a/c system will require a leak detection system that is installed by the original equipment manufacturer as a UL listed assembly. In effect, the new refrigerants will require complete system replacement. With respect to compatibility, we have no expectation that the new refrigerants will be compatible at all with current refrigerant systems, refrigeration oils, existing lineset sizing, or existing pressure temperature curves of the current refrigerants. We expect that these phaseouts will come at significantly increased equipment cost and service complexity.

With the prior phaseouts based on Ozone Depletion Potential (ODP) we had consensus across the industry and common-sense alternatives. The current Global Warming Potential (GWP) phaseout options are completely different. We do not know which refrigerants will be winners or losers. We do not know what will happen with the use of potentially flammable refrigerants. The long-term operational issues are unknown.

Our best guidance now related to the refrigerant phaseout issues is that refrigerants be removed entirely from the buildings by conversion from split system a/c units to air-cooled chilled water systems. The chilled water system effectively removes the refrigerant circuits from the occupied building and removes any potential flammability/safety issue to the exterior. Also, servicing or replacing an individual refrigeration circuit on a chiller is much easier than replacing the a/c system within an occupied building if the new refrigerants become an issue for any reason. With a chilled water system, maintenance and operating costs are reduced, and the future risks of the refrigerant transitions are isolated from the air handling systems in the facility.

### **Proposed Solution**

Trane will replace the split system DX air conditioning systems with a new chilled water system. Constant volume Air Handling Units will be replaced with new stacked dehumidification chilled water Air Handling Units and converted to variable volume with new Variable Air Volume boxes. One (1) new 80 ton Air Cooled chiller will be furnished and installed, and two (2) new chilled water pumps and HDPE chilled water pipes will be installed to deliver chilled water to the AHUs.

The following equipment will be furnished and installed by Trane:

- One (1) CGAM080 air cooled chillers.
- Two (2) End Suction Child Water Pumps.
- Four (4) CSAA Performance Climate Charger AHUs.
- One (1) BCXE Blower Coil.
- Thirteen (13) VCEF Variable Air volume boxes with Heat.



Trane will provide MEP permit type drawings on all the scopes below.

### **Scope of Work – Installation**

Trane will receive all the equipment and coordinate with County for its installation. All required handling, shipping, rigging, and crane service are included.

Trane will implement these projects in Phases. The new chiller, pumps, and piping specialties will be installed on a new concrete slab adjacent to the first floor mechanical room 113 in the new section of the library. A new pole-mount transformer and new electrical service will be provided for the new chiller and pumps. The underground chilled water piping will be installed with directional boring to minimize disruption to the site.

Once new air-cooled chiller, pumps, and piping are installed, the air handling unit replacement will be phased to minimize downtime to the library. The new section AHU 4N and AHU 5N in the new library will be installed together first, followed by AHU 1E, AHU2E, and AHU3E in the old library to allow continued use of the library during construction.

Trane will perform installation in the first floor new mechanical Room 113 –

- Trane will demo the existing Air Handling Units AHU1, AHU4 and OAU1 and dispose them off site. Trane will demo the existing Condensing Units OACU1A, OACU1B, CU1A, CU1B, and CU4 and dispose them off site. The existing refrigerant / line sets will be demolished and disposed off site. Where the refrigerant lines pass under the existing structure, they will be cut and capped..
- Trane will rig, set, and install new AHU 4N, VAV 4-1 and VAV 4-2 in first floor mechanical room 113 of the new library. The drain line for AHU 4N will be connected to the existing condensate drain line. New chilled water supply and return piping will be installed including required pipe specialties and manual isolation valves. Underground piping will be in HPDE without insulation. Piping in the mechanical rooms will be steel pipe with white mastic jacketed foam glass insulation.
- New VAV boxes will be installed and connected to the existing low pressure supply duct. New sheet metal supply and return ductwork for AHU 4N will be furnished and installed.
- In Room 118 – Install VAV boxes VAV 4-3 and VAV 4-4. Connect to existing duct.

Trane will perform installation in the second floor New Library Mechanical Room 207 –

- Trane will demo the existing Air Handling Units AHU5, AHU6 and AHU7 and dispose them off site. Trane will demo the existing Condensing Units CU5A, CU5B, CU6, and CU7 and dispose them off site. The existing refrigerant / line sets will be demolished and disposed off site. Where the refrigerant lines pass under the existing structure, they will be cut and capped.
- Trane will rig, set, and install new AHU 5N, VAV 5-1 and VAV 5-3 in the second floor mechanical room of the new library. The drain line for AHU 5N will be connected to the existing condensate drain line. New chilled water supply and return piping will be installed including required pipe specialties and manual isolation valves. Underground

piping will be in HPDE without insulation. Piping in the mechanical rooms will be steel pipe with white mastic jacketed foam glass insulation.

- New VAV boxes will be installed and connected to the existing low pressure supply duct. New sheetmetal supply and return ductwork for AHU 5N will be furnished and installed.
- The new VAV box 5-2 will be installed in the hallway outside of the mechanical room and connected to the existing duct.

Trane will perform installation in the first floor Old Library Mechanical Room 126 –

- Trane will demo the existing Air Handling Units AHU-E4 AHU- E5 and AHU-E6 and dispose them off site. Trane will demo the existing Condensing Units CU-E4, CU-E5, and CU- E6 and dispose them off site. The existing refrigerant / line sets will be demolished and disposed off site. Where the refrigerant lines pass under the existing structure, they will be cut and capped..
- The existing mechanical room will be expanded to allow service access to the new air handling unit. The existing interior wall and bookshelf will be relocated to provide the required space. The existing ceiling in the mechanical room will be removed to allow access for the ductwork and VAV box replacements.
- Trane will rig, set, and install new AHU 2E in the first floor of the old library. The drain line for the new air handling unit will be connected to the existing condensate drain line. New chilled water supply and return piping will be installed for the new air handling unit. Underground piping will be in HPDE without insulation.
- New VAV boxes will be installed and connected to the existing low pressure supply duct. New sheetmetal supply and return ductwork for new AHU 2E will be furnished and installed.
- The new VAV boxes , VAV 2-1, VAV 2-2, and VAV-2-3, will be installed and connected to the existing supply duct. New sheet metal supply and return duct for AHU 2E will be installed. Connect new supply duct to new VAV boxes. The ceiling in the library workroom area will be replaced to match existing.

Trane will perform installation in the first floor Old Library Mechanical Room 130 –

- Demo existing Air Handling Units AHU1, and AHU 2 and dispose off site. Demo existing Condensing Units CU1 and CU2 and dispose off site. Remove/cap line sets and dispose.
- Set and Install new AHU 1E and connect new AHU 1E to existing condensate drain line. Provide new chilled water supply and return piping to the new air handling unit. The existing ceiling in the mechanical room and the library workroom area will be removed to allow access for the ductwork.
- Install VAV boxes VAV 1-1, VAV 1-2, and VAV 1-3 in the library work room outside the mechanical room. Connect VAV boxes to existing supply duct. Provide new sheet metal supply and return duct for AHU 1E. The drop ceiling in the library work room will be replaced to match existing.

Trane will perform installation in the first floor Old Library Mechanical Room 145 –

- Demo existing Air Handling Units AHU3A, and AHU 3B and dispose off site. Demo existing Condensing Units CU3A and CU3B and dispose off site.
- Set and install new AHU 3E. Connect to existing condensate drain line. Provide new chilled water supply and return piping to the new air handling unit.
- Provide new sheet metal supply and return duct for AHU 1E and connect to existing supply and return duct.

## **Scope of Work - Controls**

### **TIE-IN TO EXISTING TRACER ENSEMBLE ENTERPRISE-WIDE FACILITY MANAGEMENT SYSTEM**

#### **EXISTING TRACER SC+ WEB ENABLED SYSTEM CONTROLLER**

- Tie-in new Trane BACnet controllers to existing Tracer SC+
- 5-year Software Maintenance Plan (SMP)
- AHU Trends capability
- Local & Remote Alarms Set-up
- Web-based mobile access available

#### **CHILLED WATER SYSTEM CONTROLS, INCLUDING:**

- Chilled Water Loop Pump SP-1 & 2 Status Switches
- Main Chilled Water Supply (CHWS) and Return (CHWR) Temperature Sensors
- North Loop Chilled Water Supply (CHWS) and Return (CHWR) Temperature Sensors
- South Loop Chilled Water Supply (CHWS) and Return (CHWR) Temperature Sensors
- Chiller-1 CHWS Temperature Sensors
- Chiller-1 CHWR Temperature Sensors
- North Loop Differential Pressure Transmitter
- South Loop Differential Pressure Transmitter
- Outside Air Temperature Sensor
- Outside Air Relative Humidity (%RH) Sensor
- kW Meter
- Pump 1 & 2 Start/Stop
- Chiller-1 Start/Stop
- BACnet DDC Controller

#### **VAV AIR HANDLING UNIT CONTROLS, TYPICAL FOR (4) AHU-1E, AHU-2E, AHU-4N, AHU-5N, INCLUDING:**

- Supply Fan Start/Stop
- Supply Fan Status
- Filter Status
- Supply Air Temperature Sensor

- Mixed Air Temperature Sensor
- Return Air Temperature
- Return Air Humidity Sensor
- Return Air Carbon Dioxide (CO<sub>2</sub>) Sensor
- Outside Air Flow
- Pressure Independent Supply Chilled Water Valve Control
- Pressure Independent Return Chilled Water Valve Control
- Return Air Damper Control
- Outside Air Damper Control
- Supply Fan VFD Speed Control
- BACnet DDC Controller

**BLOWER COIL UNIT CONTROLS, TYPICAL FOR (1) AHU-3E, INCLUDING:**

- Supply Fan Start/Stop
- Supply Fan Status
- Supply Air Temperature Sensor
- Zone Air Temperature
- Pressure Independent Chilled Water Valve Control
- Supply Fan VFD Speed Control
- BACnet DDC Controller

**SHUTOFF TYPE, VAV TERMINAL UNIT CONTROLS, TYPICAL FOR (13) VAV BOXES, INCLUDING:**

- Supply Air Temperature Sensor
- Heating stage control (where applicable)
- Space Temperature Sensor with Digital Display
- Space Carbon Dioxide (CO<sub>2</sub>) Sensor
- Space Relative Humidity (%RH) Sensor
- Trane UC210 BACnet DDC Controller with electronic actuator (factory mounted)

## Calculated Utility Savings

### Calculated Energy Savings

Facility	Electric Consumption kWh Saved	Electric Demand kW Saved	Water kgal Saved
Cummings Library	3,065	379	-

# ECM-06 Jail Chiller Plant 400 kW Generator Addition

## Existing Conditions

The current Jail chiller plant has two (2) nominal 400-ton water cooling chillers, cooling towers, and pumps. The plant was designed for the 400 ton cooling load of the Jail and was designed to accommodate future expansion with installation of a third 400-ton water-cooled chiller to provide added redundancy required when the PSC is connected. At present, only one 400 kW diesel emergency generator is installed for backup power for the chiller plant which provides standby power for chiller 1 and the related pumps and cooling tower. With the addition of the PSC to the plant and the addition of the third 400-ton chiller, additional emergency generator capacity is required. The current generator is dedicated to chiller #1 and is not able to run chiller #2 or the associated cooling tower and pumps.

## Proposed Solution

A new 400 kW standby emergency generator will be furnished and installed to provide additional standby electric power to the chiller plant. The new generator will power either chiller 2 or chiller 3, as selected by the energy management system. The existing 400 kW standby generator for chiller #1 will remain.

## Scope of Work:

- Install a new concrete pad for the new 400 kW generator adjacent to the existing generator pad outside the plant.
- Install a new 400KW genset in addition to the existing 400KW. Trane to furnish new 400 KW Generac genset and ATS.
- Connect new genset/ATS
- Furnish new 1200A 480/277v NEMA 3R Automatic Transfer Switch. 480Y-277 volt, 3 phase, 4 wire, 50 KAIC, with automatic and manual input selection. Include GFCI protection and arc energy reduction per NEC requirements for new switch as required. Supply and install all conduits and wiring to feed the new ATS and existing Power Panel.

## Martin County Jail - 400 kW Genset and ATS Equipment Furnished by Trane:

Qty	I/L	Description
1	L	<p>One (1) New Generac Diesel Engine Generator set, Rated @ 400 Kw Standby, 277/480 volts, 3 Phase, 60Hz., 1800RPM. Each Diesel Engine Generator Set with the following accessories:</p> <ul style="list-style-type: none"> <li>• UL 2200</li> <li>• EPA Certified</li> <li>• MPS Control Panel</li> <li>• KO400064N21 Alternator</li> <li>• Permanent Magnet Generator Excitation System</li> <li>• Lead –Acid Starting Batteries, Rack &amp; Cables</li> <li>• Battery Charger (Shipped Loose)</li> <li>• Certified Test Report</li> <li>• Remote Annunciator</li> <li>• Emergency Stop Switch</li> <li>• Critical Grade Silencer and Exhaust Flexible Connector</li> <li>• Circuit Breaker 700 amp</li> </ul>
1	I	One (1) Aluminum Sound Enclosure Level 1A 180 mph Rated
1	I	One (1) 2100 Gallon 72 Hour UL 142 FDEP Sub Base Fuel Tank
1	L	Five (5) Year Factory Warranty
0	L	Automatic Transfer Switch: 1200A 480/277v NEMA 3R Automatic Transfer Switch. 480Y-277 volt, 3 phase, 4 wire, 50 KAIC, with automatic and manual input selection.
1	L	Package Start-Up and Testing On Site per NFPA 110

# ECM-07 PSC – Install 300 kW Emergency Generator

## Existing Conditions

The current PSC has a single 1.5MW diesel emergency generator installed for backup power for the facility. This generator is significantly oversized and is not able to load and run properly as a result. The current peak electrical load at the PSC, with the air-cooled chillers and before the planned LED lighting retrofit, is approximately 400 kW. The emergency generator should be sized to run at 80% of generator capacity.

The PSC was originally designed with two standby generators, but only one was installed. With the addition of the PSC to the Jail chiller plant and removal of the air-cooled chillers at the PSC, smaller sizing of the standby emergency generator is required. One (1) new 300 kW standby emergency generators are proposed with a 72-hour fuel tank. Installation of a 600-amp manual transfer switch with cam lock electrical connections is also included to provide an electrical connection tap box to connect a portable temporary emergency generator for added resiliency.

## Proposed Solution

One new 300 kW standby emergency generators will be furnished and installed to provide standby electric power with additional redundancy for the PSC. The existing transfer switch for the building will be reused. A 600 amp manual transfer switch will be added to provide an electrical connection point for a portable temporary emergency generator.

## Scope of Work:

- Install one new 300KW genset. Demo and remove existing 1.5MW genset. Trane to furnish new 300 KW Generac genset. The new generator is furnished with a five year warranty
- Install (1) new 300KW genset in the empty pad at the PSC.
- Remove and dispose of the existing 1.5M genset and make ready for the new 300KW genset.
- Supply and install additional underground conduits and feeders to the new service as needed.
- Install new service entrance rated 600 amp Nema 3R manual transfer switch for the connection of a portable emergency generator.
- Existing MDP are to remain and reuse.
- All rigging of the old genset and new genset is included.
- Supply and install all necessary conduit, wire, circuit breakers and miscellaneous materials for a professionally installed project.
- Provide crane service and rigging. Remove and reinstall fencing above generator enclosure. Salvage of the existing generator is included by Trane.



**Martin County PSC – 300 kW Genset and Equipment Furnished by Trane:**

<u>Qty</u>	<u>I/L</u>	<u>Description</u>
1	L	<p>One new Generac Diesel Engine Generator sets, Rated @ 300 Kw Standby, 277/480 volts, 3 Phase, 60Hz., 1800RPM. Diesel Engine Generator Set is provided with the following accessories:</p> <ul style="list-style-type: none"> <li>• UL 2200</li> <li>• EPA Certified</li> <li>• MPS Control Panel</li> <li>• KO400064N21 Alternator</li> <li>• Permanent Magnet Generator Excitation System</li> <li>• Lead –Acid Starting Batteries, Rack &amp; Cables</li> <li>• Battery Charger (Shipped Loose)</li> <li>• Certified Test Report</li> <li>• Remote Annunciator</li> <li>• Emergency Stop Switch</li> <li>• Critical Grade Silencer and Exhaust Flexible Connector</li> <li>• Circuit Breaker</li> </ul>
1	I	One (1) Aluminum Sound Enclosure Level 1A 180 mph Rated
1	I	One (1) 1600 Gallon 72 Hour UL 142 FDEP Sub Base Fuel Tank
1	L	Five (5) Year Factory Warranty
1	L	Manual Transfer Switch: New service rated Nema 3R 600 amp manual transfer switch with cam lock connections
1	L	Package Start-Up and Testing On Site per NFPA 110

## ECM-08 Controls Optimization/Intelligent Services

The existing County-wide Tracer Ensemble energy management system has advanced capabilities to monitor, trend, and optimize energy use and equipment performance. Intelligent Services combines technology, proprietary analytics and expertise to continuously collect, interpret and act on data from building equipment and controls to optimize the performance of your building. TIS takes the data your building systems produce and translates it into actionable outcome-oriented recommendations that enable Trane engineers to make improvements that help you realize your business mission. TIS produces Active Intelligence that enables your high-performance building.

### Proposed Solution

#### ECM #8A Scope – Blake Library:

Humidity sensors will be installed at Blake Library to enable trim and response control of system scheduling and outside air quantity. Zone humidity sensors are required in the control strategy and analytics to enable the reset of outside air and zone temperature to ensure that the building stays within acceptable ranges at all times.

#### ECM #8B Scope – Administration Building:

Humidity sensors will be installed at the Administration Building to enable trim and response control of system scheduling and outside air quantity. Zone humidity sensors are required in the control strategy and analytics to enable the reset of outside air and zone temperature to ensure that the building stays within acceptable ranges at all times.

### Intelligent Services - Overview:

Starting in September, 2024, Trane reviewed the performance of several County facilities using Intelligent Services. Six buildings, including The Public Safety Complex, Courthouse/COB, Blake Library, Indiantown Government Center, Administration Building, and the Mansion at Tuckahoe were reviewed to determine the operational effectiveness of the controls systems and energy efficiency.

Based on the analytic data, related energy savings targets, and the results of energy modeling, we recommend implementation of Intelligent Services to optimize energy efficiency for the Courthouse/COB, Administration Building, and Blake Library. The additional monitoring and analytics from Intelligent Services will enhance system performance, and reduce energy usage, and drive additional energy cost savings.

Excerpts from our Intelligent Services report are shown below for the recommended facilities:

#### Martin County Courthouse/COB

##### Intelligent Services Action Items:

- CH-1 has indicated approach temperature of five degrees. Need to verify sensor accuracy and determine if heat exchanger is scaled.
- Cooling tower systems in the chiller plant show some instability while operating at fixed set point. Recommend implementing chiller tower optimization program.
- There is an excessive level of reheat during extremely warm weather. Recommend implementing trim and respond program.
- There were several Exceptions for Chilled water instability in recent period. Reviewed and determined chillers are operating during the overnight period with insufficient load and continuously short cycling. There were also exceptions for low delta T, found during daytime operation is satisfactory this exception is due to erratic nighttime operation.


## MCCH CHS Plant

Martin County Courthouse: 100 East Ocean Boulevard



## Chilled Water Temperature Control

August 24, 2024 12:00 AM - September 07, 2024 12:00 AM



### Chart Legend

#### Left Y-Axis 1 (°F)

- Config: Dist Supply Temp Setpoint - Design
- Dist Return Temp
- Dist Supply Temp
- Dist Supply Temp Setpoint: Active
- Outdoor Air Temp (Reference Value)

#### Left Y-Axis 2 (Δ°F)

- Config: Delta T - Design
- Delta T: Active

#### Right Y-Axis (%)

- Chiller-1: Chiller Current Draw (%RLA)
- Chiller-2: Chiller Current Draw (%RLA)
- Dist Flow Rate: Normalized
- Load: Normalized

### Timeline Legend

- Plant Enable
- Low Delta T

## Martin County Administrative Center

### Intelligent Services Action Items:

- AHU-1 serving Growth Management it's not achieving full static pressure and impacting several VAV's. Requires field check.
- VAV-07 has failed to position control with no indicated CFM, suspect failed sensor or transducer. Requires field check.
- There were several AHUS which appear to have exceptions for supply air temperature instability. This is due to compressor cycling and temperatures oscillating, this is also causing unusually high space humidity. As example used following AHUs-14, 17 & 21. This condition is best resolved by installing Rawal Refrigerant bypass valves which keep compressors operating and constant evaporator temperature.

#### Spaces

Actions...							
<input type="checkbox"/>	Name	Space Temperature	Active Setpoint	Discharge Air Temperature	Air Flow	Air Valve Position	Heat/Cool Mode Status
No filter applied							
<input type="checkbox"/>	VAV-01	74.1 °F	73.5 °F	58.9 °F	492.1 cfm	72.6 %	Cool
<input type="checkbox"/>	VAV-02	73.5 °F	73.5 °F	69.8 °F	194.7 cfm	33.0 %	Cool
<input type="checkbox"/>	VAV-03	73.9 °F	73.5 °F	69.8 °F	308.0 cfm	18.5 %	Cool
<input type="checkbox"/>	VAV-04	73.2 °F	74.0 °F	73.1 °F	63.2 cfm	27.1 %	Cool
<input type="checkbox"/>	VAV-05	73.5 °F	74.0 °F	70.1 °F	55.3 cfm	12.3 %	Cool
<input type="checkbox"/>	VAV-06	72.9 °F	73.5 °F	66.0 °F	181.8 cfm	15.4 %	Cool
<input type="checkbox"/>	VAV-07	72.1 °F	71.0 °F	71.3 °F	0.0 cfm	40.0 %	Heat
<input type="checkbox"/>	VAV-08	72.7 °F	72.5 °F	67.0 °F	382.8 cfm	33.8 %	Cool
<input type="checkbox"/>	VAV-10	74.0 °F	73.5 °F	67.6 °F	375.8 cfm	23.8 %	Cool

## Martin County Blake Library

### Intelligent Services Action Items:

- Chiller is operating during the overnight Time period when all other equipment off this is causing short cycling. It is not clear if chiller is in front panel mode or from BAS program. Needs to be corrected ASAP.
- Both AHU- 1 and 2 both have exceptions for low static pressure.
- Most VAVs are using excessive reheat in warmer weather. Recommend upgrading to SC+ and implementing Trim and Respond program along with duct pressure optimization.
- The air-cooled chiller is operating during the overnight period 8:00 PM to 6:00 AM when all schedules are unoccupied, this is causing continuous compressor short cycling on first stage. On review of operation during unoccupied period determined the chilled water pump may be commanded on continuously.


## Chiller

Blake Library, 2351 SE Monterey Rd



## Chilled Water Temperature Control

August 30, 2024 12:00 AM - September 06, 2024 12:00 AM



## Calculated Utility Savings

### Intelligent Services Controls Optimization Calculated Energy Savings

Facility	Electric Consumption kWh Saved	Electric Demand kW Saved	Water kgal Saved
Court House Complex	219,908	540	-
Blake Library	74,296	-	-
Admin Center	59,953	-	-

# ECMs Evaluated but Not Recommended

## ECM-03A Building Envelope – Infiltration

Trane audited the building envelope of all Martin County GSD facilities. We evaluated each entry door, rollup door, window, and unsealed wall opening for opportunities to reduce energy loss and infiltration. The auditors also took photos of each building opening, took measurements, and documented site conditions for the project. A summary of the building envelope project is shown in the table below. More detailed information is included in the appendix.

**Building Envelope Project Summary:**

Martin County Facility	kWh Savings	\$ Savings	Doors	Rollup	Windows	Wall Sealing
Administrative Center	4,341	\$ 347.27	15		1	
Administrative Center Warehouse	5,879	\$ 473.20	3	1		X
Blake Library	5,279	\$ 422.29	17			
Building Department	3,416	\$ 273.25	11			
Building Maintenance Shop	1,998	\$ 159.80	11	1		
Colo Building	3,416	\$ 273.25	11			
Court Holding	2,795	\$ 223.57	9			
Courthouse	5,279	\$ 422.29	17			
Courthouse Cultural Center (Historical)	1,553	\$ 124.20	5			
CSD Building	3,105	\$ 248.41	10			
Cummings Library	3,416	\$ 273.25	11			
Field Operations	994	\$ 79.49	8			
Fire Rescue Fleet Maintenance	1,192	\$ 95.39	8	1		
Fire Rescue Lifestar Hangar	652	\$ 52.16	6			
Fire Station 16	1,921	\$ 156.09	14			
Fire Station 21	2,981	\$ 238.47	16			
Fire Station 22	1,087	\$ 86.94	7			
Fire Station 23	1,956	\$ 156.49	9			
Fire Station 24	2,927	\$ 234.16	10	1		
Fire Station 30	2,826	\$ 226.05	13			
Fire Station 32	932	\$ 74.52	6			
General Services Department	1,553	\$ 124.20	5			
Hobe Sound Annex	2,059	\$ 165.72	6			
Hoke Library	3,105	\$ 248.41	10			
Indiantown Education Center	5,123	\$ 409.87	4			X
Indian Riverside Park - Dockside Pavilion/Rec. Center	16,995	\$ 1,359.61	53	1		
Indiantown Annex	3,726	\$ 298.09	12			
Indiantown Health Department	2,174	\$ 173.88	7			
Jensen Beach Community Center	4,037	\$ 322.93	13			
Lahti Library	1,863	\$ 149.04	6			
Landfill Hazmat/Transfer Station	621	\$ 49.68	2			
Langford Park - Vince Bocchino Community Center	3,105	\$ 248.41	10			
Martin County Tax Collector Offices	5,279	\$ 422.29	17			
MC DRC (Old Eoc)	932	\$ 74.52	3			
Mco Aviation Hangar	1,553	\$ 124.20	5			
Morgade Library	3,726	\$ 298.09	12			
Mosquito Control Office	172	\$ 14.07	2			
New Monrovia Sheriff Substation	621	\$ 49.68	2			
Park Operations Compound	745	\$ 59.62	8			
Port Salerno Civic Center	2,795	\$ 223.57	9			
Public Safety Complex	15,629	\$ 1,250.31	43	1		
Public Safety Gym / Lawn Maintenance	5,548	\$ 443.82	16	1		
Supervisor Of Elections Office	2,484	\$ 198.73	8			
Traffic Management Center	1,029	\$ 82.85	3			
Willoughby Commons	2,174	\$ 173.88	7			
Willoughby Property Appraiser's Office	1,863	\$ 149.04	6			
Witham Field Customs Building	2,174	\$ 173.88	7			

## Calculated Utility Savings

### Calculated Energy Savings

Facility	Electric Consumption kWh Saved	Electric Demand kW Saved	Water kgal Saved
	165,580	-	-

### ECM-03B Building Envelope – Window Tinting

Trane we evaluated the Administration Building for window film installation. The existing clear, single-pane windows have very poor thermal performance. There are several areas that have consistent comfort concerns due to high heat gain from solar loads. A previous window film application was applied but has not been effective. The existing film will be removed and replaced with a new high-performance thermal film to reduce heat gain to the occupied spaces. Application of the new window film will help mitigate heat gain and comfort issues associated with solar heat transmission. The window area, solar gain, and annual energy savings are shown in the table below for each side of the Administration Building.

#### Window Film Project Summary:

Building	Glass Type	Direction	Insolation (kwh/m^2)	Window Qty	Solar Heat Gain (SHGC)		Annual \$ Savings
					Pre	Post	
<b>Totals</b>				<b>1,411</b>			<b>\$7,443.38</b>
Administrative Center - West	Single Pane - Tinted	West	945	665	0.45	0.20	\$3,447
Administrative Center- East	Single Pane - Tinted	East	945	394	0.45	0.20	\$2,044
Administrative Center - North	Single Pane - Tinted	North	472	100	0.45	0.20	\$259
Administrative Center - South	Single Pane - Tinted	South	1,228	251	0.45	0.20	\$1,694

Calculated Utility Savings

Calculated Energy Savings

Facility	Electric Consumption kWh Saved	Electric Demand kW Saved	Water kgal Saved
	70,943	-	-



# Project Financing

## Project Financing and Project Pro Forma

Trane recommends that project financing is provided for the project utilizing the existing Master Tax Exempt Lease that is currently in place with Bank of America Public Capital Corp.

The financial model for the project utilizes the 4.092% indicative rate and lease factors from the Bank of America Term Sheet dated March 31, 2025 for their existing Master Tax Exempt Lease with Martin County. The actual financing rates, terms, and costs may vary. Please refer to the Bank of America term sheet. One year of construction-period financing is also included which is added to the project cost to arrive at the total amount financed. Please see the cash flow model for the project based on the recommended Energy Conservation Measures selected by the County. The cash flow model uses the indicative rate from the Bank of America term sheet dated 3/31/2025 which is included under separate cover.

Please see the Letter of Interest below from Bank of America:



**Ben Taube**  
Senior Vice President  
Energy Services

Bank of America Public Capital Corp  
3455 Peachtree Rd, NE  
Suite GA7-024-12-03  
Atlanta, GA 30326  
Email: ben.taube@bofa.com  
Tel: (404) 607.5561  
Fax: (415) 796.1601

February 20, 2025

**Mr. Don Donaldson**  
Martin County  
2407 SE Monterey Road  
Stuart, FL 34996

Re: Trane Guaranteed Energy Performance Contract Financing

Dear Mr. Donaldson:

We appreciate the opportunity to support the County with the forthcoming next phase of the guaranteed energy performance project. As part of our longstanding and highly valued banking and credit relationship with Trane, Banc of America Public Capital Corp ("BAPCC") and its Bank of America, N.A. affiliated companies ("BAC") regularly extend credit to finance energy efficiency and renewable energy projects for Trane customers across the U.S., and we are excited to support the County, again, for this Phase with a schedule to the Master Tax Exempt Lease we currently have in place with the County.

With annual fundings in excess of \$1.5 billion, BAPCC is a leading provider of tax-exempt equipment finance solutions for the public sector. Our Energy Services and Capital Markets teams offer a wealth of specialized financial, structural and industry expertise to deliver smooth closings to our customers, and we are confident that our partnership with Trane will provide the County with exceptional resources for a successful and highly efficient financing of the proposed project.

At any time upon your request, we can provide a term sheet with applicable rates and lock terms. As we have done in the past, we are happy to take the interest rate risk off the table by providing options to lock a rate as you finalize the scope of the project for implementation. Purely for indicative purposes, 15 year rates are around 4.42% and we have provided a sample amortization table as well.

Please note that this letter is not a commitment or offer to lend or finance, and does not create any obligation for BAPCC or BAC. All prospective transactions must meet internal approval requirements for funding.

We look forward to learning more about this opportunity and to the possibility of working with the County again in support of our mutual goals of energy and cost saving efficiencies.

Please do not hesitate to contact me at any time with any questions.

Sincerely yours,

**Ben Taube**  
Senior Vice President

Project Financial Model

Recommended Scope - 15 Year Level Amortization with \$1.8M Down Payment

Martin County General Services Department - Energy and Operational Savings Project

Year	Construction Year 0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	Total
Program Savings																	
Energy and Water Savings	\$ 101,653	\$ 203,306	\$ 211,438	\$ 219,896	\$ 228,692	\$ 237,839	\$ 247,353	\$ 257,247	\$ 267,537	\$ 278,238	\$ 289,368	\$ 300,943	\$ 312,980	\$ 325,499	\$ 338,519	\$ 352,060	\$ 4,070,916
Operational Savings	\$ -	\$ 35,709	\$ 36,780	\$ 37,884	\$ 39,020	\$ 40,191	\$ 41,397	\$ 42,638	\$ 43,918	\$ 45,235	\$ 46,592	\$ 47,990	\$ 49,430	\$ 50,912	\$ 52,440	\$ 54,013	\$ 664,149
Lifecycle Savings	\$ -	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 292,299	\$ 4,384,485
Capital Cost Avoidance	\$ -	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 84,924	\$ 1,273,864
Utility Rebate	\$ 1,786																
Annual Program Savings	\$ 103,439	\$ 616,238	\$ 625,442	\$ 635,003	\$ 644,935	\$ 655,253	\$ 665,973	\$ 677,109	\$ 688,678	\$ 700,697	\$ 713,183	\$ 726,156	\$ 739,633	\$ 753,635	\$ 768,183	\$ 783,297	\$ 10,393,413
Program Cumulative Savings	\$ 103,439	\$ 616,238	\$ 1,241,680	\$ 1,876,683	\$ 2,521,618	\$ 3,176,871	\$ 3,842,844	\$ 4,519,952	\$ 5,208,630	\$ 5,909,327	\$ 6,622,510	\$ 7,348,666	\$ 8,088,299	\$ 8,841,934	\$ 9,610,117	\$ 10,393,413	
Program Costs																	
Principal & Interest	\$ -	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 479,773	\$ 7,196,595
Annual M&V Cost	\$ -	\$ 24,736	\$ 25,478	\$ 26,242	\$ 27,030	\$ 27,841	\$ 28,676	\$ 29,536	\$ 30,422	\$ 31,335	\$ 32,275	\$ 33,243	\$ 34,240	\$ 35,268	\$ 36,326	\$ 37,415	\$ 38,538
Scheduled Service Support	\$ -	\$ 39,165	\$ 40,732	\$ 42,361	\$ 44,055	\$ 45,818	\$ 47,650	\$ 49,556	\$ 51,538	\$ 53,600	\$ 55,744	\$ 57,974	\$ 60,293	\$ 62,704	\$ 65,213	\$ 67,821	\$ 784,224
Annual Program Costs	\$ -	\$ 543,674	\$ 545,983	\$ 548,376	\$ 550,858	\$ 553,431	\$ 556,099	\$ 558,865	\$ 561,734	\$ 564,708	\$ 567,792	\$ 570,990	\$ 574,306	\$ 577,745	\$ 581,311	\$ 585,010	\$ 8,440,882
Program Cumulative Costs	\$ -	\$ 543,674	\$ 1,089,657	\$ 1,638,033	\$ 2,188,891	\$ 2,742,322	\$ 3,298,421	\$ 3,857,286	\$ 4,419,020	\$ 4,983,728	\$ 5,551,520	\$ 6,122,510	\$ 6,696,816	\$ 5,561,473	\$ 6,142,784	\$ 6,727,794	
Cash Flow																	
Annual Cash Flow	\$ 103,439	\$ 72,564	\$ 79,459	\$ 86,626	\$ 94,077	\$ 101,822	\$ 109,874	\$ 118,243	\$ 126,944	\$ 135,989	\$ 145,391	\$ 155,166	\$ 165,327	\$ 175,890	\$ 186,871	\$ 198,287	\$ 2,055,971
Cumulative Net Cash Flow	\$ 103,439	\$ 176,003	\$ 255,462	\$ 342,089	\$ 436,166	\$ 537,988	\$ 647,862	\$ 766,105	\$ 893,049	\$ 1,029,038	\$ 1,174,429	\$ 1,329,595	\$ 1,494,922	\$ 1,670,812	\$ 1,857,684	\$ 2,055,971	
Net New Debt Service Cost	\$ -	\$ 240,758	\$ 231,554	\$ 221,994	\$ 212,061	\$ 201,743	\$ 191,024	\$ 179,888	\$ 168,319	\$ 156,300	\$ 143,813	\$ 130,841	\$ 117,363	\$ 103,361	\$ 88,814	\$ 73,700	\$ 2,461,531

\* Annual Principal & Interest payment modeled based on lease factors from Bank of America Term Sheet dated June 5, 2025. Tax-Exempt Interest Rate is 4.118%.

Debt Service Breakdown	Borrowing Cost	Lifecycle Savings
PSC Generators	\$ 798,419	\$ -
Jail Chiller Plant Generators	\$ 953,912	\$ -
Rest of Project	\$ 709,200	\$ 4,384,485

\* Net New Debt Service Cost is Principal & Interest less Energy and Operational Savings

Program Financial Summary	
Program Construction Cost	\$ 7,021,715
Utility Rebates	\$ 1,786
Customer Down Payment	\$ 1,800,000
Lease Proceeds	\$ 5,221,715
Year 1 - Program Savings	\$ 616,238
Year 1 - Simple Payback (years)	11.4
Term - Program Costs	\$ 8,440,882
Term - Program Savings	\$ 10,393,413
Annual Interest Rate	4.118%
Loan/Lease Term (years)	15
Construction Interest (12 months)	Yes
Annual Energy Cost Escalation Factor	4.0%
Annual Operational Cost Escalation Factor	3.0%
Annual Service Program Cost Escalation Factor	4.0%

## Support Services

The services included in the project include mechanical maintenance services, building automation maintenance services, and Trane Intelligent energy optimization services. The proposed services are described further below:

<u>ECM#</u>	<u>Facility</u>	<u>Annual Cost</u> <u>(Year 1)</u>	<u>Service Description</u>
4	PSC/Jail Chiller Plant	\$14,500	HDWA 400 ton chiller - Annual inspection and three quarterly run inspections  Cooling Tower – Annual tower inspection and cleaning and three quarterly run inspections
5	Cummings Library	\$12,050	CGAM080 chiller – Annual inspection and condenser coil cleaning and three quarterly run inspections
8A	Blake Library	\$3,729	BAS System Maintenance – Annual BAS system inspection
8A	Blake Library	\$4,405	Intelligent Services – Two semi-annual digital inspections and four quarterly IS consultations
8B	Admin Building	\$3,729	BAS System Maintenance – Annual BAS system inspection
8B	Admin Building	\$4,405	Intelligent Services – Two semi-annual digital inspections and four quarterly IS consultations
8C	Courthouse/COB	\$3,805	Intelligent Services – Two semi-annual digital inspections and four quarterly IS consultations

# Measurement and Verification

## Savings Measurement Protocol

Trane adheres to the well-established International Performance Measurement and Verification Protocol (IPMVP) for confirming the benefits of the installed ECMs. The four IPMVP methods are summarized below. Together, we will select whichever Option proves to be the most prudent for each individual ECM after the project is fully developed.

**Figure 9: IPMVP M&V Guidelines Summary of M&V Plan**

IPMVP Protocol		Typical Uses for this Option
<b>A</b>	<b>Retrofit Isolation: Key Parameter Measurements</b>	<i>This is applied to ECMs where there is one specific and key variable that best indicates the potential for energy savings.</i>
The verification techniques for Option A determine energy savings by measuring the capacity or efficiency of a system before and after a retrofit, and multiplying the difference by an agreed-upon or “stipulated” factor, such as hours of operation or load on the system. Careful review of ECM design and installation ensures that stipulated values fairly represent the probable actual value.		
<b>B</b>	<b>Retrofit Isolation: All Parameter Measurements</b>	<i>Verification techniques for Option B are designed for projects where long-term continuous measurement of performance is desired.</i>
Under Option B, individual loads are continuously monitored to determine performance, and this measured performance is compared with a baseline to determine savings. Option B M&V techniques provide long-term persistence data on ECM operation and performance. This data can be used to improve or optimize the operation of the equipment on a real-time basis, thereby improving the benefit of the retrofit. Option B also relies on the direct measurement of affected end uses.		
<b>C</b>	<b>Whole Facility</b>	<i>Verification techniques for Option C determine savings by studying overall energy use in a facility and identifying the effects of energy projects from changes in overall energy use patterns.</i>
This approach is intended for measurements of the whole-facility or specific meter baseline energy use, and measurements of whole-facility or specific meter Post-implementation (Post) energy use can be measured. The methodology to establish baseline and Post-parameter identification, modeling approach and baseline or model adjustments will be defined in the performance contract document. Periodic inspections of baseline energy usage, operating practices, facility equipment and meter measurements will be necessary to verify the ongoing efficient operation of the equipment, systems, practices and facility, and savings attainment.		

IPMVP Protocol		Typical Uses for this Option
<b>D</b>	<b>Calibrated Simulation</b>	<i>Option D is intended for energy retrofits where calibrated simulation of baseline energy use and calibrated simulations of post-installation energy consumption are used to measure savings from the retrofit.</i>
<p>Option D can involve measurements of energy use both before and after the retrofit for specific equipment/systems or whole-building data for calibrating the simulation(s). Simulation routines must be demonstrated to adequately model actual energy performance measured in the facility. This option usually requires considerable skill in calibrated simulation. Energy use simulation is calibrated with hourly or monthly utility billing data and/or end use metering.</p>		

The following table summarizes the proposed M&V plans for each ECM, in accordance with the IPMVP guidelines shown above and the performance risk.

**Figure 10: Summary ECM M&V Plan**

ECM	M&V Option
Chiller Retrofit	Option A
Chiller Plant Improvements	Option A
Variable Chilled Water Flow	Option A
DDC Controls Upgrade	Option A
Lighting	Option A
Exterior Lighting	Option A
Water Efficiency	Option A

## Savings Measurement and Verification Plan

The savings measurement and verification (M&V) plan is described below. This provides the guarantee type and savings verification process for each of the proposed Energy Conservation Measures.

ECM No.	ECM Description	Source of Savings (Tool)	IPMVP M&V Option Used	Summary of M&V Plan and determination of savings
<b>1A</b> (All buildings Lighting ECM)	Interior Lighting (The entire list of retrofit solutions can be found in the lighting	Excel Worksheet	Option A	<p>Savings Methodology Determination:</p> <p>Measure the Pre (existing) and Post (new) power measurement for a sample of typical lighting fixtures that represent 75% of the total savings. After selecting the sample of light fixtures the average power will be the value representing the entire Lighting ECM population of the selected sample. Of each typical</p>



ECM No.	ECM Description	Source of Savings (Tool)	IPMVP M&V Option Used	Summary of M&V Plan and determination of savings
	project summary in the Appendix)			<p>lighting fixture, at a minimum, five (5) fixtures of each type will be measured.</p> <p><b>Here is how the savings are determined:</b></p> <ol style="list-style-type: none"> <li>1. The difference between the measured Pre and Post power wattage readings will be compared and become the basis for the savings.</li> <li>2. If the measured savings are within 10% of the calculated savings, it is assumed that the savings guarantee has been met.</li> </ol> <p>Where practical, the power measurements will be taken at the light switch. Where light switch measurement is not practical, power readings will be taken at the fixture level.</p> <p>The measurement will be performed 1-time and used for the remainder of the Guarantee term.</p>
<b>1B</b> (Selected exterior lights)	Parking Lot Lighting (The entire list of retrofit solutions can be found in the lighting project summary in the Appendix)	Excel Worksheet	Option A	<p>Savings Methodology Determination:</p> <p>Measure the Pre (existing) and Post (new) power measurement for a sample of typical lighting fixtures that represent 75% of the total savings. After selecting the sample of exterior light fixtures the average power wattage readings will be the value representing the entire Lighting ECM population of the selected sample. Of each typical lighting fixture, at a minimum, five (3) fixtures of each type will be measured.</p> <p><b>Here is how the savings are determined:</b></p> <ol style="list-style-type: none"> <li>1. The difference between the measured Pre and Post power will be compared and become the basis for the savings.</li> <li>2. If the measured savings are within 10% of the calculated savings, it is assumed that the savings guarantee has been met.</li> </ol> <p>Where practical, the power measurements will be taken at the light. Where light measurements are not practical, power readings will be taken at the electric panel.</p> <p>The lighting measurement will be performed 1-time and used for the Guarantee term.</p>

ECM No.	ECM Description	Source of Savings (Tool)	IPMVP M&V Option Used	Summary of M&V Plan and determination of savings
<b>2</b> (All buildings Water Conservation ECM)	Water Conservation (Detailed scope is included in the appendix)	Excel Worksheet	Option A	<p>Measure the Pre (existing) and Post (new) water flow for a sample of Plumbing fixtures that represent 75% of the total savings. The average Flow/Flush rates will be the value representing the entire plumbing fixture population. A sample of each water conservation device will be measured.</p> <p><b>Here is how the savings are determined:</b></p> <ol style="list-style-type: none"> <li>1. The difference between the measured Pre and Post Flow/Flush rates will be compared and become the basis for the savings.</li> <li>2. If the measured savings are within 10% of the calculated savings, it is assumed that the savings guarantee has been met.</li> </ol> <p>The one-time measurement will be used for the remainder of the Guarantee term.</p>
<b>3B</b>	Building Envelope – Window Tinting	Excel Worksheet	Agreed upon	<p>Savings are calculated using standard engineering practice. The savings are agreed to by the Customer and Trane. The energy savings are based on mutually approved solar film performance data and have been validated by a building model.</p>
<b>4</b>	Chiller Plant Tie-In	Trane Trace™ 700	Option A	<p>Chiller Plant Tie-In consists of connecting the Public Safety Complex to the existing jail chiller plant. Two (2) 225-ton air-cooled chillers with estimated efficiency of 1.35 kW/ton will be replaced with a new 400-ton water cooled chiller with a minimum efficacy of 0.583 kW/ton. A multi-point factory performance test will verify the kW/ton post retrofit, including the following parameters: Chilled Water Supply and Return Temperatures; Chilled Water Flow Rate; and Chiller kW on a 15 to 30 minute interval.</p> <p>In addition, to the chiller efficiency improvement, the chilled water pumping will be improved. The existing Constant Volume chilled water pumping will be replaced with Variable Volume pumping.</p>



ECM No.	ECM Description	Source of Savings (Tool)	IPMVP M&V Option Used	Summary of M&V Plan and determination of savings
				<p>This IPMVP approach verifies savings by comparing an adjusted calibrated simulation model of baseline energy, with actual Factory test kW/ton.</p> <p><b>Here is how the savings are determined:</b></p> <ol style="list-style-type: none"> <li>1. If the efficiency of the installed chiller is more efficient than the minimum efficiency stated above, the savings guarantee has been met for the new chiller. If it is not, the efficiency of the new chiller will be entered into the Trace 700 program to calculate actual savings; this will be done one time after installation and become the basis for the savings.</li> <li>2. The basis of this analysis compares energy consumption of Constant Volume pumps with that of Variable Volume pumps for chilled water.</li> <li>3. During the post retrofit phase, a control trend report and equipment inspection will confirm that the VFDs are functioning and modulating to deliver appropriate water volume based on building load.</li> <li>4. During the post retrofit phase, a control's trend report and controls inspection will confirm that the set points are modulating in response to building load.</li> </ol> <p>The post retrofit phase control trend report and controls inspection will confirm that the chilled water pumps and CT fan speed is modulating in response to building load and the ambient wet bulb temperature.</p>
5A	A/C Replacement	Trane Trace™ 700	Option A	<p>This ECM consists of replacing the existing split system direct expansion (DX) system with a chilled water system (using air cooled chillers) for better energy efficiency and dehumidification. The air handling units will be replaced with variable volume stacked-dehumidification air handling units. The stacked dehumidification air handlers have two cooling coils, one for outside ventilation air and one for the main cooling coil.</p> <p>The existing DX units consist of two groups based on efficiency, the east units which have an estimated efficiency of 0.9 kW/ton and west units which have an estimated efficiency of 0.85 kW/ton. These DX units will</p>

ECM No.	ECM Description	Source of Savings (Tool)	IPMVP M&V Option Used	Summary of M&V Plan and determination of savings
				<p>be replaced with a system using an air-cooled chiller with a minimum efficiency of 1.32 kW/ton. The chiller efficiency will be obtained from the manufacturer's AHRI Certified chiller efficiency. This ECM will provide additional savings using variable air volume AHUs.</p> <p>This IPMVP approach verifies savings by comparing an adjusted calibrated simulation model of baseline energy, with actual performance, post retrofit.</p> <p><b>Here is how the savings are determined:</b></p> <ol style="list-style-type: none"> <li>1. If the efficiency of the installed chiller is more efficient than the minimum efficiency stated above, the savings guarantee has been met for the new chiller. If it is not, the efficiency of the new chiller will be entered into the Trace 700 program to calculate actual savings; this will be done one time after installation and become the basis for the savings.</li> <li>2. During the post retrofit phase, a control trend report and equipment inspection will confirm that the fan VFDs are functioning and modulating to deliver appropriate air volume based on building load.</li> <li>3. During the post retrofit phase, a control trend report and controls inspection will confirm that the set points are modulating in response to building load.</li> </ol> <p>During the post retrofit phase, a control's trend report and controls inspection will confirm that the AHUs are modulating in response to building load.</p>
4, 5A	Building Automation Upgrades	Trane Trace™ 700	Option A	<p>This IPMVP approach verifies savings by comparing an adjusted calibrated simulation model of baseline energy, with actual performance, post retrofit. The basis of this analysis confirms the building operation is optimized.</p> <p><b>Here is how the savings are determined:</b></p> <ol style="list-style-type: none"> <li>1. AHU supply air temperature (SAT) reset. Controls report and equipment inspections will confirm that AHUs SAT is being reset in response to the building load (VAV boxes feedback will use critical zone to reset SAT).</li> </ol>

ECM No.	ECM Description	Source of Savings (Tool)	IPMVP M&V Option Used	Summary of M&V Plan and determination of savings
				<p>2. AHU discharge air pressure reset. Control reports and equipment inspections will confirm that the VFD's are functioning, and modulating to deliver the appropriate air volume based on building load, resulting in decreased fan power and increased comfort. Confirm that AHUs discharge pressure is being reset in response to the building load (VAV boxes feedback will use critical zone to reset static pressure).</p> <p>During the post retrofit phase, a control's trend report and controls inspection will confirm that the AHUs modulate in response to building load.</p>
8A,B,C	Building Automation Optimization – Intelligent Services	Excel Worksheet Trace™ 700	Agreed upon	<p>Savings are calculated by benchmarking facility performance using energy cost indexes from similar facilities in our region. Savings are further evaluated by building modeling of anticipated energy optimization measures including scheduling, outside air rest, and humidity control using standard engineering practice. The projected savings are agreed to by the Customer and Trane.</p>

# Environmental Benefits

## Trane's Commitment to Sustainability

### Mission

Trane Technologies is committed to creating a sustainable future by providing innovative, energy-efficient products and services.

### Vision

Our vision is to be a reliable partner, delivering solutions that create efficient, sustainable and comfortable environments that enhance the quality of life.

### Core Values

- Integrity - We believe that ethical behavior and honesty are crucial for building trust with stakeholders, including customers, employees, suppliers, shareholders and the community.
- Respect - We engage with suppliers and partners worldwide and are committed to respecting human rights throughout our global supply chain.
- Innovation - Trane is committed to inventiveness and creativity in developing new solutions that meet the evolving needs of our clients and the planet.
- Sustainability - We have a long-standing commitment to environmental stewardship and social responsibility. We are committed to reducing greenhouse gas emissions, conserving water and energy, advancing workforce diversity and inclusion, and supporting communities.

At Trane, we are dedicated to finding innovative solutions that help our customers achieve their sustainability goals. Our customers have the power to make an impact on the planet, and we want to support them in their journey to make a difference. We lead the way to inspire and show our customers what is possible, and we partner with them to build a sustainable world for future generations.

Our product innovations in electrification, energy efficiency, and the use of low-global warming potential refrigerants help customers reduce the emissions from their buildings and refrigerated transport without sacrificing safety or operating performance. Not only do we extensively test our products and services to ensure optimal performance, but we also help customers of all sizes to reduce costs, become more energy efficient, and meet sustainability targets.

To show our dedication to supporting our customers as they work towards their decarbonization goals, we have committed to our Gigaton Challenge — to eliminate 1 billion metric tons of carbon emissions from our customers' footprint by 2030. This is the first of-its-kind climate commitment related to customer product use of any business-to-business company — and essential to combating climate change.


Helping our customers achieve their sustainability and financial goals drives Trane Technologies' innovation. We are committed to putting the needs of our customers at the center of our conversations so that we can offer products that fit specific needs and help contribute to a sustainable future. We are proud of how our customer partnerships can save money, reduce emissions, and improve indoor environmental quality, among other outcomes, and we will continue to amplify our customers' successes.

# Climate Metrics

The table below depicts the potential associated environmental benefits for the energy & infrastructure improvement program that Martin County can utilize towards achieving any of their sustainability goals.

Figure 12: Environmental Benefits

This is equivalent to greenhouse gas emissions from:





# Appendices

## Appendix A Electric Utility Analysis

General Information	
Site Name: (Tab)	Cummings Library
Address:	2551 SW MATHESON AVE # LIBRARY
Facility Type:	
HVAC System Type:	
Year 1:	2023
Square Footage	
Date Applicable:	Square Feet
January - 23	21,398

Utility Information				
Meter Count	Electric		Other	
	Bill Information		Bill Information	
Meter 1 Elec	Account #:	2025993318	Account #:	
	Meter #:	KU55743	Meter #:	
	Rate Type:		Rate Type:	
Meter 2 Elec	Account #:		Account #:	
	Meter #:		Meter #:	
	Rate Type:		Rate Type:	
Meter 3 Elec	Account #:		Account #:	
	Meter #:		Meter #:	
	Rate Type:		Rate Type:	

1	Baseline Optional	2023							
2023	Month	Electric					Total		
		Usage	Demand		Fees	Total Electric Cos	Active Sq Ft	Electric	
		Total kWh	Total Billed Base	Total Demand \$	\$	Total\$	ft²	kBtu/ ft²	\$/ ft²
	January - 2023	17,400	118	\$0.00	\$2,784.34	\$2,784	21,398	3	\$0.13
	February - 2023	15,480	109	\$0.00	\$2,525.71	\$2,526	21,398	2	\$0.12
	March - 2023	16,440	82	\$0.00	\$2,387.82	\$2,388	21,398	3	\$0.11
	April - 2023	17,160	83	\$0.00	\$2,455.26	\$2,455	21,398	3	\$0.11
	May - 2023	18,960	86	\$0.00	\$2,753.82	\$2,754	21,398	3	\$0.13
	June - 2023	20,640	86	\$0.00	\$2,792.77	\$2,793	21,398	3	\$0.13
	July - 2023	23,880	95	\$0.00	\$3,164.03	\$3,164	21,398	4	\$0.15
August - 2023	25,200	96	\$0.00	\$3,172.81	\$3,173	21,398	4	\$0.15	
September - 2023	26,640	98	\$0.00	\$3,304.22	\$3,304	21,398	4	\$0.15	
October - 2023	24,840	100	\$0.00	\$3,201.99	\$3,202	21,398	4	\$0.15	
November - 2023	25,080	104	\$0.00	\$3,274.42	\$3,274	21,398	4	\$0.15	
December - 2023	22,200	104	\$0.00	\$3,066.77	\$3,067	21,398	4	\$0.14	
Totals	253,920	1,161	\$0	\$34,884	\$34,884	21,398	40	\$1.63	
Partial Year	49,320	309	\$0	\$7,698	\$7,698	21,398	8	\$0.36	

2	Baseline Optional	2024							
2024	Month	Electric					Total		
		Usage	Demand		Fees	Total Electric Cos	Active Sq Ft	Electric	
		Total kWh	Total Billed Base	Total Demand \$	\$	Total\$	ft²	kBtu/ ft²	\$/ ft²
	January - 2024	18,360	110	\$0.00	\$2,950.34	\$2,950.34	21,398	3	\$0.14
	February - 2024	14,880	80	\$0.00	\$2,272.78	\$2,272.78	21,398	2	\$0.11
	March - 2024	18,720	95	\$0.00	\$2,770.73	\$2,770.73	21,398	3	\$0.13
	April - 2024	17,880	82	\$0.00	\$2,470.48	\$2,470.48	21,398	3	\$0.12
	May - 2024	24,360	97	\$0.00	\$2,946.01	\$2,946.01	21,398	4	\$0.14
	June - 2024	26,640	94	\$0.00	\$3,047.28	\$3,047.28	21,398	4	\$0.14
	July - 2024	29,400	95	\$0.00	\$3,235.60	\$3,235.60	21,398	5	\$0.15
August - 2024	26,520	90	\$0.00	\$2,959.87	\$2,959.87	21,398	4	\$0.14	
September - 2024	0	0	\$0.00	\$0.00	\$0.00	21,398	0	\$0.00	
October - 2024	0	0	\$0.00	\$0.00	\$0.00	21,398	0	\$0.00	
November - 2024	0	0	\$0.00	\$0.00	\$0.00	21,398	0	\$0.00	
December - 2024	0	0	\$0.00	\$0.00	\$0.00	21,398	0	\$0.00	
Totals		176,760	743	\$0	\$22,653	\$22,653	21,398	28	\$1.06
Partial Year		51,960	285	\$0	\$7,994	\$7,994	21,398	8	\$0.37



General Information	
Site Name: (Tab)	Public Safety
Address:	800 SE MONTEREY RD # 911/EOC
Facility Type:	Office
HVAC System Type:	RTUs/Split System
Year 1:	2023
Square Footage	
Date Applicable	Square Feet
January - 23	65,491

Utility Information			
Electric		Other	
Meter Count	Bill Information	Bill Information	
Meter 1 Elec	Account #:	2805676059	Account #:
	Meter #:		Meter #:
	Rate Type:	HLFT-1	Rate Type:
Meter 2 Elec	Account #:		Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:
Meter 3 Elec	Account #:		Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:

2023		Total kWh	total Billed Bas	Total Demand \$	\$	Total\$	ft <sup>2</sup>	kBtu/ ft <sup>2</sup>	\$/ ft <sup>2</sup>	Total \$
	January - 2023	167,520	293	\$0.00	\$15,791.36	\$15,791	65,491	9	\$0.24	\$15,791.36
	February - 2023	148,320	274	\$0.00	\$14,750.05	\$14,750	65,491	8	\$0.23	\$14,750.05
	March - 2023	156,960	276	\$0.00	\$15,280.22	\$15,280	65,491	8	\$0.23	\$15,280.22
	April - 2023	156,960	310	\$0.00	\$17,045.22	\$17,045	65,491	8	\$0.26	\$17,045.22
	May - 2023	156,720	329	\$0.00	\$16,702.12	\$16,702	65,491	8	\$0.26	\$16,702.12
	June - 2023	170,160	336	\$0.00	\$17,706.22	\$17,706	65,491	9	\$0.27	\$17,706.22
	July - 2023	187,200	350	\$0.00	\$18,257.41	\$18,257	65,491	10	\$0.28	\$18,257.41
	August - 2023	181,680	353	\$0.00	\$18,028.27	\$18,028	65,491	9	\$0.28	\$18,028.27
	September - 2023	188,400	310	\$0.00	\$17,585.14	\$17,585	65,491	10	\$0.27	\$17,585.14
	October - 2023	168,720	298	\$0.00	\$16,175.82	\$16,176	65,491	9	\$0.25	\$16,175.82
	November - 2023	162,960	286	\$0.00	\$15,523.40	\$15,523	65,491	8	\$0.24	\$15,523.40
	December - 2023	168,000	281	\$0.00	\$15,622.82	\$15,623	65,491	9	\$0.24	\$15,622.82
	Totals	2,013,600	3,696	\$0	\$198,468	\$198,468	65,491	105	\$3.03	\$198,468
	Partial Year	472,800	843	\$0	\$45,822	\$45,822	65,491	25	\$0.70	\$45,822

2	Baseline Optional	2024								
2024	Month	Electric					Total			
		Usage	Demand		Fees	Total Electric Cost	Active Sq Ft	Electric		Total
		Total kWh	total Billed Bas	Total Demand \$	\$	Total\$	ft <sup>2</sup>	kBtu/ ft <sup>2</sup>	\$/ ft <sup>2</sup>	Total \$
	January - 2024	163,920	286	\$0.00	\$16,019.10	\$16,019.10	65,491	9	\$0.24	\$16,019.10
	February - 2024	181,920	310	\$0.00	\$17,544.76	\$17,544.76	65,491	9	\$0.27	\$17,544.76
	March - 2024	166,800	278	\$0.00	\$16,019.25	\$16,019.25	65,491	9	\$0.24	\$16,019.25
	April - 2024	169,200	286	\$0.00	\$15,881.87	\$15,881.87	65,491	9	\$0.24	\$15,881.87
	May - 2024	188,880	305	\$0.00	\$15,946.62	\$15,946.62	65,491	10	\$0.24	\$15,946.62
	June - 2024	177,840	355	\$0.00	\$16,306.80	\$16,306.80	65,491	9	\$0.25	\$16,306.80
	July - 2024	190,080	374	\$0.00	\$17,389.82	\$17,389.82	65,491	10	\$0.27	\$17,389.82
	August - 2024	200,880	370	\$0.00	\$17,703.87	\$17,703.87	65,491	10	\$0.27	\$17,703.87
	September - 2024	0	0	\$0.00	\$0.00	\$0.00	65,491	0	\$0.00	\$0.00
	October - 2024	0	0	\$0.00	\$0.00	\$0.00	65,491	0	\$0.00	\$0.00
	November - 2024	0	0	\$0.00	\$0.00	\$0.00	65,491	0	\$0.00	\$0.00
	December - 2024	0	0	\$0.00	\$0.00	\$0.00	65,491	0	\$0.00	\$0.00
	Totals	1,439,520	2,564	\$0	\$132,812	\$132,812	65,491	75	\$2.03	\$132,812
	Partial Year	512,640	874	\$0	\$49,583	\$49,583	65,491	27	\$0.76	\$49,583



General Information	
Site Name: (Tab)	Court Chiller Plant
Address:	SE FLAGLER AVE # CHILLER STUART 34994
Facility Type:	
HVAC System Type:	
Year 1:	2023
Square Footage	
Date Applicable:	Square Feet
January - 23	127,193

Utility Information			
Electric		Other	
Meter Count	Bill Information	Bill Information	
Meter 1 Elec	Account #:	2318586175	Account #:
	Meter #:	KV75761	Meter #:
	Rate Type:	GSD-1	Rate Type:
Meter 2 Elec	Account #:	271022501	Account #:
	Meter #:	KV87757	Meter #:
	Rate Type:	GSD-1	Rate Type:
Meter 3 Elec	Account #:		Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:

1	Baseline Optional	2023									
2023	Month	Electric					Total				
		Usage		Demand		Fees	Total Electric Cost	Active Sq Ft	Electric		Total
		Total kWh	Total Billed Base	Total Demand \$	\$	Total\$			ft²	kBtu/ ft²	\$/ ft²
	January - 2023	145,760	409	\$0.00	\$15,907.26	\$15,907	127,193	4	\$0.13	0	\$15,907.26
	February - 2023	132,640	387	\$0.00	\$15,238.85	\$15,239	127,193	4	\$0.12	0	\$15,238.85
	March - 2023	142,320	421	\$0.00	\$16,425.34	\$16,425	127,193	4	\$0.13	0	\$16,425.34
	April - 2023	149,440	464	\$0.00	\$18,512.94	\$18,513	127,193	4	\$0.15	0	\$18,512.94
	May - 2023	149,280	462	\$0.00	\$17,771.90	\$17,772	127,193	4	\$0.14	0	\$17,771.90
	June - 2023	160,640	482	\$0.00	\$18,911.04	\$18,911	127,193	4	\$0.15	0	\$18,911.04
	July - 2023	180,800	480	\$0.00	\$19,661.13	\$19,661	127,193	5	\$0.15	0	\$19,661.13
August - 2023	167,520	522	\$0.00	\$19,283.54	\$19,284	127,193	4	\$0.15	0	\$19,283.54	
September - 2023	162,400	542	\$0.00	\$19,190.27	\$19,190	127,193	4	\$0.15	0	\$19,190.27	
October - 2023	134,480	419	\$0.00	\$15,492.46	\$15,492	127,193	4	\$0.12	0	\$15,492.46	
November - 2023	123,440	418	\$0.00	\$14,684.95	\$14,685	127,193	3	\$0.12	0	\$14,684.95	
December - 2023	120,320	490	\$0.00	\$15,450.15	\$15,450	127,193	3	\$0.12	0	\$15,450.15	
	Totals	1,769,040	5,496	\$0	\$206,530	\$206,530	127,193	47	\$1.62	0	\$206,530
	Partial Year	420,720	1,217	\$0	\$47,571	\$47,571	127,193	11	\$0.37	0	\$47,571

2	Baseline Optional	2024									
2024	Month	Electric					Total				
		Usage		Demand	Fees	Total Electric Cost	Active Sq F	Electric			Total
		Total kWh	Total Billed Base	Total Demand \$	\$	Total\$	ft²	kBtu/ ft²	\$/ ft²	KW/ ft²	Total \$
	January - 2024	126,080	337	\$0.00	\$14,166.80	\$14,166.80	127,193	3	\$0.11	0	\$14,166.80
	February - 2024	115,120	322	\$0.00	\$13,144.99	\$13,144.99	127,193	3	\$0.10	0	\$13,144.99
	March - 2024	122,960	341	\$0.00	\$13,994.30	\$13,994.30	127,193	3	\$0.11	0	\$13,994.30
	April - 2024	128,160	372	\$0.00	\$14,435.42	\$14,435.42	127,193	3	\$0.11	0	\$14,435.42
	May - 2024	128,640	558	\$0.00	\$16,052.53	\$16,052.53	127,193	3	\$0.13	0	\$16,052.53
	June - 2024	141,600	408	\$0.00	\$14,745.83	\$14,745.83	127,193	4	\$0.12	0	\$14,745.83
	July - 2024	0	0	\$0.00	\$0.00	\$0.00	127,193	0	\$0.00	0	\$0.00
August - 2024	0	0	\$0.00	\$0.00	\$0.00	127,193	0	\$0.00	0	\$0.00	
September - 2024	0	0	\$0.00	\$0.00	\$0.00	127,193	0	\$0.00	0	\$0.00	
October - 2024	0	0	\$0.00	\$0.00	\$0.00	127,193	0	\$0.00	0	\$0.00	
November - 2024	0	0	\$0.00	\$0.00	\$0.00	127,193	0	\$0.00	0	\$0.00	
December - 2024	0	0	\$0.00	\$0.00	\$0.00	127,193	0	\$0.00	0	\$0.00	
	Totals	762,560	2,338	\$0	\$86,540	\$86,540	127,193	20	\$0.68	0	\$86,540
	Partial Year	364,160	1,000	\$0	\$41,306	\$41,306	127,193	10	\$0.32	0	\$41,306



General Information	
Site Name: (Tab)	Admin Center
Address:	401 SE MONTEREY RD # CNTY ADMIN
Facility Type:	
HVAC System Type:	
Year 1:	2023
Square Footage	
Date Applicable	Square Feet
January - 23	78,000

Utility Information			
Electric		Other	
Meter Count	Bill Information	Bill Information	
Meter 1 Elec	Account #:	2863121634	Account #:
	Meter #:	KU74372	Meter #:
	Rate Type:		Rate Type:
Meter 2 Elec	Account #:		Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:
Meter 3 Elec	Account #:		Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:

1	Baseline Optional	2023									
2023	Month	Electric					Total				
		Usage	Demand		Fees	Total Electric Cost	Active Sq F	Electric			Total
		Total kWh	Total Billed Base	Total Demand \$	\$	Total\$	ft²	kBtu/ ft²	\$/ ft²	KW/ ft²	Total \$
	January - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00
	February - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00
	March - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00
	April - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00
	May - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00
	June - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00
	July - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00
August - 2023	0	0	\$0.00	\$0.00	\$0	78,000	0	\$0.00	0	\$0.00	
September - 2023	80,400	216	\$0.00	\$8,781.75	\$8,782	78,000	4	\$0.11	0	\$8,781.75	
October - 2023	73,440	202	\$0.00	\$8,088.92	\$8,089	78,000	3	\$0.10	0	\$8,088.92	
November - 2023	60,480	185	\$0.00	\$6,923.48	\$6,923	78,000	3	\$0.09	0	\$6,923.48	
December - 2023	56,160	158	\$0.00	\$6,241.82	\$6,242	78,000	2	\$0.08	0	\$6,241.82	
Totals	270,480	761	\$0	\$30,036	\$30,036	78,000	12	\$0.39	0	\$30,036	
Partial Year	0	0	\$0	\$0	\$0	78,000	0	\$0.00	0	\$0	

\$82,577

2	Baseline Optional	2024									
2024	Month	Electric					Total				
		Usage		Demand		Fees	Total Electric Cost	Active Sq F	Electric		Total
	Total kWh	Total Billed Base	Total Demand \$	\$	Total\$	ft²	kBtu/ ft²	\$/ ft²	KW/ ft²	Total \$	
	January - 2024	54,000	139	\$0.00	\$5,997.33	\$5,997.33	78,000	2	\$0.08	0	\$5,997.33
	February - 2024	54,000	151	\$0.00	\$6,167.42	\$6,167.42	78,000	2	\$0.08	0	\$6,167.42
	March - 2024	52,800	154	\$0.00	\$6,121.00	\$6,121.00	78,000	2	\$0.08	0	\$6,121.00
	April - 2024	61,200	161	\$0.00	\$6,659.38	\$6,659.38	78,000	3	\$0.09	0	\$6,659.38
	May - 2024	59,040	166	\$0.00	\$6,095.49	\$6,095.49	78,000	3	\$0.08	0	\$6,095.49
	June - 2024	70,320	182	\$0.00	\$7,031.49	\$7,031.49	78,000	3	\$0.09	0	\$7,031.49
	July - 2024	71,760	190	\$0.00	\$7,235.26	\$7,235.26	78,000	3	\$0.09	0	\$7,235.26
August - 2024	68,400	209	\$0.00	\$7,233.23	\$7,233.23	78,000	3	\$0.09	0	\$7,233.23	
September - 2024	0	0	\$0.00	\$0.00	\$0.00	78,000	0	\$0.00	0	\$0.00	
October - 2024	0	0	\$0.00	\$0.00	\$0.00	78,000	0	\$0.00	0	\$0.00	
November - 2024	0	0	\$0.00	\$0.00	\$0.00	78,000	0	\$0.00	0	\$0.00	
December - 2024	0	0	\$0.00	\$0.00	\$0.00	78,000	0	\$0.00	0	\$0.00	
Totals		491,520	1,352	\$0	\$52,541	\$52,541	78,000	22	\$0.67	0	\$52,541
Partial Year		160,800	444	\$0	\$18,286	\$18,286	78,000	7	\$0.23	0	\$18,286



General Information	
Site Name: (Tab)	Blake Library
Address:	TEREY RD # LIBRARY STUART 3495
Facility Type:	
HVAC System Type:	
Year 1:	2023
Square Footage	
Date Applicable:	Square Feet
January - 23	39,000

Utility Information			
Electric		Other	
Meter Count	Bill Information	Bill Information	
Meter 1 Elec	Account #:	7433841561	Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:
Meter 2 Elec	Account #:		Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:
Meter 3 Elec	Account #:		Account #:
	Meter #:		Meter #:
	Rate Type:		Rate Type:

1	Baseline Optional	2023										
2023	Month	Electric					Total					
		Demand			Fees	Total Electric Cost	Active Sq F	Electric			Total	
		Total kWh	Total Billed Base	Total Demand \$	\$	Total\$	ft²	kBtu/ ft²	\$/ ft²	KW/ ft²	\$/ ft²	Total \$
	January - 2023	55,920	158	\$0.00	\$6,123.66	\$6,124	39,000	5	\$0.16	0	\$0.16	\$6,123.66
	February - 2023	58,080	163	\$0.00	\$6,588.02	\$6,588	39,000	5	\$0.17	0	\$0.17	\$6,588.02
	March - 2023	57,120	168	\$0.00	\$6,585.42	\$6,585	39,000	5	\$0.17	0	\$0.17	\$6,585.42
	April - 2023	58,800	168	\$0.00	\$7,090.96	\$7,091	39,000	5	\$0.18	0	\$0.18	\$7,090.96
	May - 2023	59,040	170	\$0.00	\$6,860.75	\$6,861	39,000	5	\$0.18	0	\$0.18	\$6,860.75
	June - 2023	62,400	185	\$0.00	\$7,322.53	\$7,323	39,000	5	\$0.19	0	\$0.19	\$7,322.53
	July - 2023	70,560	206	\$0.00	\$7,936.83	\$7,937	39,000	6	\$0.20	0	\$0.20	\$7,936.83
August - 2023	71,040	230	\$0.00	\$8,301.19	\$8,301	39,000	6	\$0.21	0	\$0.21	\$8,301.19	
September - 2023	71,280	199	\$0.00	\$7,892.39	\$7,892	39,000	6	\$0.20	0	\$0.20	\$7,892.39	
October - 2023	69,840	175	\$0.00	\$7,459.02	\$7,459	39,000	6	\$0.19	0	\$0.19	\$7,459.02	
November - 2023	60,720	173	\$0.00	\$6,775.83	\$6,776	39,000	5	\$0.17	0	\$0.17	\$6,775.83	
December - 2023	58,560	163	\$0.00	\$6,483.09	\$6,483	39,000	5	\$0.17	0	\$0.17	\$6,483.09	
Totals	753,360	2,158	\$0	\$85,420	\$85,420	39,000	66	\$2.19	0	\$2.19	\$85,420	
Partial Year	171,120	489	\$0	\$19,297	\$19,297	39,000	15	\$0.49	0	\$0.49	\$19,297	

2024	2	Baseline Optional	2024									
	Month	Electric					Total					
		Usage		Demand	Fees	Total Electric Cost	Active Sq F	Electric		Total		
		Total kWh	Total Billed Base	Total Demand \$	\$	Total\$	ft²	kBtu/ ft²	\$/ ft²	KW/ ft²	\$/ ft²	Total \$
		January - 2024	57,120	151	\$0.00	\$6,397.73	\$6,397.73	39,000	5	\$0.16	0	\$0.16
February - 2024	63,600	156	\$0.00	\$6,949.03	\$6,949.03	39,000	6	\$0.18	0	\$0.18	\$6,949.03	
March - 2024	58,560	156	\$0.00	\$6,575.82	\$6,575.82	39,000	5	\$0.17	0	\$0.17	\$6,575.82	
April - 2024	67,440	154	\$0.00	\$7,003.76	\$7,003.76	39,000	6	\$0.18	0	\$0.18	\$7,003.76	
May - 2024	63,120	166	\$0.00	\$6,352.18	\$6,352.18	39,000	6	\$0.16	0	\$0.16	\$6,352.18	
June - 2024	67,920	178	\$0.00	\$6,823.91	\$6,823.91	39,000	6	\$0.17	0	\$0.17	\$6,823.91	
July - 2024	71,520	175	\$0.00	\$7,007.96	\$7,007.96	39,000	6	\$0.18	0	\$0.18	\$7,007.96	
August - 2024	66,240	180	\$0.00	\$6,688.96	\$6,688.96	39,000	6	\$0.17	0	\$0.17	\$6,688.96	
September - 2024	69,840	175	\$0.00	\$6,902.28	\$6,902.28	39,000	6	\$0.18	0	\$0.18	\$6,902.28	
October - 2024	67,920	182	\$0.00	\$6,880.52	\$6,880.52	39,000	6	\$0.18	0	\$0.18	\$6,880.52	
November - 2024	0	0	\$0.00	\$0.00	\$0.00	39,000	0	\$0.00	0	\$0.00	\$0.00	
December - 2024	0	0	\$0.00	\$0.00	\$0.00	39,000	0	\$0.00	0	\$0.00	\$0.00	
Totals	653,280	1,673	\$0	\$67,582	\$67,582	39,000	57	\$1.73	0	\$1.73	\$67,582	
Partial Year	179,280	463	\$0	\$19,923	\$19,923	39,000	16	\$0.51	0	\$0.51	\$19,923	

## Appendix B Utility tariff

### **GENERAL SERVICE DEMAND**

RATE SCHEDULE: GSD-1

AVAILABLE:

In all areas served.

APPLICATION:

For electric service required for general service or industrial lighting, power and any other purpose with a measured Demand of at least 25 kW and less than 500 kW. Customers with a Demand of less than 25 kW may enter an agreement for service under this schedule based on a Demand Charge for a minimum of 25 kW.

SERVICE:

Single or three phase, 60 hertz and at any available standard distribution voltage. All service required on premises by Customer shall be furnished through one meter. Resale of services is not permitted hereunder.

MONTHLY RATE:

Base Charge: \$30.21

Demand Charges:

Base Demand Charge \$11.38 per kW

Non-Fuel Energy Charges:

Base Energy Charge 2.532¢ per kWh

Additional Charges:

General Service Load Management Program (if applicable), See Sheet No. 8.109 See Billing Adjustment section, Sheet No. 8.030, for additional applicable charges.

Minimum: The Base Charge plus the charge for the currently effective Base Demand. For those Customers with a Demand less than 25 kW who have entered an agreement for service under this schedule, the minimum charge shall be the Base Charge plus 25 kW times the Base Demand Charge; therefore the minimum charge is \$314.71.

DEMAND:

The Demand is the kW to the nearest whole kW, as determined from the Company's metering equipment and systems, for the 30-minute period of Customer's greatest use during the month as adjusted for power factor.

TERM OF SERVICE:

Not less than one year.

RULES AND REGULATIONS:

Service under this schedule is subject to orders of governmental bodies having jurisdiction and to the currently effective "General Rules and Regulations for Electric Service" on file with the Florida Public Service Commission. In case of conflict between any provision of this schedule and said "General Rules and Regulations for Electric Service" the provision of this schedule shall apply.

**HIGH LOAD FACTOR – TIME OF USE (OPTIONAL)**

RATE SCHEDULE: HLFT

AVAILABLE:

In all areas served.

APPLICATION:

For electric service required for general service or industrial lighting, power and any other purpose with a measured Demand

of 25 kW or more. This is an optional rate schedule available to customers otherwise served under the GSD-1, GSDD-1, GSDD-2, GSDDT-1, GSDDT-2, or GSDDT-3 Rate Schedules.

SERVICE:

Single or three phase, 60 hertz and at any available standard distribution voltage. All service required on premises by Customer shall be furnished through one meter. Resale of service is not permitted hereunder.

MONTHLY RATE:

	HLFT-1	HLFT-2	HLFT-3
Annual Maximum Demand	<b><u>25-499 kW</u></b>	<u>500-1,999 kW</u>	<u>2,000 kW or greater</u>
Base Charge:	<b>\$30.21</b>	\$88.67	\$256.83
Demand Charges:			
On-Peak Demand Charge	<b>\$13.41</b>	\$14.30	\$13.90
Maximum Demand Charge	<b>\$2.78</b>	\$3.07	\$2.96
Non-Fuel Energy Charges:			
On-Peak Period per kWh	<b>2.178¢</b>	1.251¢	1.080¢
Off-Peak Period per kWh	<b>1.366¢</b>	1.210¢	1.078¢

Additional Charges

See Billing Adjustments section, Sheet No. 8.030, for additional applicable charges. Minimum Charge: The Base Charge plus the currently effective Demand Charges.

RATING PERIODS:

On-Peak:

November 1 through March 31: Mondays through Fridays during the hours from 6 a.m. EST to 10 a.m. EST and 6 p.m. EST to 10 p.m. EST excluding Thanksgiving Day, Christmas Day, and New Year's Day.

April 1 through October 31: Mondays through Fridays during the hours from 12 noon EST to 9 p.m. EST excluding Memorial Day, Independence Day, and Labor Day.

Off-Peak:

All other hours.

## Effective Rate:

Rate	Effective \$ kW	Effective \$ kWh
GS-1		0.1211
GSD-1	14.05	0.0625
HLFT-1	17.91	0.0558

## Appendix C Savings Calculations

### Lighting

The following equations were utilized to quantify the energy savings associated with lighting upgrades. The original lighting audit/scope of work will be modified utilizing the measurements reflected in the sampling plan. The measurements will replace assumed values within the original document. These actual values will supersede the estimated values currently represented in the spreadsheet and be considered "as-built" conditions.

*Demand (kW)*

$$kW Savings = \left[ \frac{kW}{Fixture} \times \#of fixtures \times DF \right]_{Existing} - \left[ \frac{kW}{Fixture} \times \#of fixtures \times DF \right]_{Proposed}$$

Where:

$$Diversity Factor (DF) = \frac{Installed Load}{Running Load}$$

$$kW Savings Guarantee = kW Savings \times HVAC Saving Factor \times Safety Factor$$

*Consumption (kWh)*

$$kWh Savings = kW Savings \times Burn Hours$$

$$kWh Savings_{HVAC} = kWh Savings \times HVAC Savings Factor \times Safety Factor$$

$$HVAC Saving Factor = 1.1$$

$$Safety Factor = 0.95$$

## Savings Calculations

Savings calculations for this ECM were conducted through Trane TRACE modeling software. Trane TRACE models energy savings by considering interrelated Energy Conservation Measures (ECMs) and various factors influencing energy and water consumption. It accounts for a building's physical characteristics, equipment conditions and historical weather data. The software performs annual energy consumption analysis by simulating the building's operation over a full year, using 8,760 hours of operation data. Key factors in the calculations include climatic data, building orientation, building characteristics, operational characteristics, mechanical performance, internal heat generation, and energy consumption by non-HVAC systems. The program calculates design cooling and heating loads, air quantities, and supply air temperatures using standard procedures from the ASHRAE Handbook of Fundamentals. The baseline model is calibrated with utility data to create an adjusted baseline, and energy-saving measures are then applied to determine the post-installation baseline. The difference between the adjusted baseline and the post-installation baseline models the energy savings.

### b) Computation of Savings

Data obtained through BAS trends will confirm the implementation of the BAS savings strategies. Any non-implemented strategies will be utilized to rerun the original energy savings model providing verified savings data. This model will be updated one-time post-installation with measured data. If all strategies are implemented and trending correctly the model will be agreed upon as accurate and not rerun. During the performance period, verified data will be used to estimate savings (models may not be rerun and/or spreadsheets calculations may be used to estimate verified savings).



# Water

The following equations were utilized to quantify the water savings associated with fixture upgrades.

Water and Sewer Savings Calculation for Toilets and/or Urinals:

$$\text{Annual Water Savings (kgal)} = (\text{Existing Flow} - \text{Retrofit Flow}) \times \text{Qty} \times \text{Use} \times \text{Annual Operation}$$

$$\text{Annual Cost Savings} = (\text{Annual Water Savings}) \times (\text{Water Rate} + \text{Sewer Rate})$$

Water and Sewer Savings Calculation for Sink and/or Shower Aerators:

$$\text{Annual Water Savings (kgal)} = (\text{Existing Flow} - \text{Retrofit Flow}) \times \text{Qty} \times \text{Use} \times \text{Annual Operation}$$

$$\text{Annual Cost Savings} = (\text{Annual Water Savings}) \times (\text{Water Rate} + \text{Sewer Rate})$$

Annual Water Heating Savings:

Existing Annual Htg. Usage (Therms)

$$= \frac{(\text{Existing Annual Gallons} \times \% \text{ heated}) \times (\text{Hot Water Temp. (°F)} - \text{City Water Temp}) \times 8.34 \frac{BTU}{°F}}{(\text{Htg. Eff}) \times 100,000 \frac{BTU}{Therm}}$$

Proposed Annual Htg. Usage (Therms)

$$= \frac{(\text{Proposed Annual Gallons} \times \% \text{ heated}) \times (\text{Hot Water Temp.} - \text{City Water Temp}) \times 8.34 \frac{BTU}{°F}}{(\text{Htg. Eff}) \times 100,000 \frac{BTU}{Therm}}$$

OR

Existing Annual Htg. Usage (kW)

$$= \frac{(\text{Existing Annual Gallons} \times \% \text{ heated}) \times (\text{Hot Water Temp.} - \text{City Water Temp}) \times 8.34 \frac{BTU}{°F}}{(\text{Htg. Eff}) \times 3412.14 \frac{BTU}{kW}}$$

Proposed Annual Htg. Usage (kW)

$$= \frac{(\text{Proposed Annual Gallons} \times \% \text{ heated}) \times (\text{Hot Water Temp.} - \text{City Water Temp}) \times 8.34 \frac{BTU}{°F}}{(\text{Htg. Eff}) \times 3412.14 \frac{BTU}{kW}}$$

$$\text{Hot Water Energy Savings (Therms or kWh)} = \text{Existing Htg. Usage} - \text{Proposed Htg. Usage}$$

$$\text{Hot Water Energy Cost Savings} = \text{Hot Water Energy Savings} \times \text{Utility Rate}$$



## Appendix D Lighting Line by Line

Facility / Building	Ref #	Floor	Map ID / Room #	Room Description	Area Type	Existing Fixture Description	Existing Lamp & Ballast Type	Exist. Fixt. Qty	Proposed Retrofit/Replacement	Proposed Qty
Administration Building	1	1	1	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Administration Building	2	1	2	Exterior	Exterior	LED - Wall Brick (Retro)	LED (Screw In / Plug In) / N/A	8	DND - Existing LED fixture	8
Administration Building	3	1	3	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Administration Building	4	1	4	Exterior	Exterior	LED - Recessed Square (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Administration Center Warehouse	5	1	1	100	Warehouse	8' Strip	F96T8 / 2L Electronic	10	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	10
Administration Center Warehouse	6	1	2	101	Storage - General	8' Strip	F96T8 / 2L Electronic	1	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	1
Administration Center Warehouse	7	1	3	102	Storage - General	8' Strip	F96T8 / 2L Electronic	1	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	1
Administration Center Warehouse	8	1	4	102	Storage - General	8' Strip	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Administration Center Warehouse	9	1	5	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Administration Center Warehouse	10	1	6	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	11	1	42	209	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Blake Library	12	1	43	209	Restroom - Public	2' Vanity	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	13	1	44	208	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Blake Library	14	1	45	208	Restroom - Public	2' Vanity	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	15	1	46	207	Storage - General	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	16	1	47	204	Office - Admin Area	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	5	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	5
Blake Library	17	1	48	205	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	5	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	5
Blake Library	18	1	51	Roof Stairs	Stairwell - Interior	Cylinder	CFL 13w PL / CFL	2	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	2
Blake Library	19	1	52	Circulation Reference Desk	Office - Admin Area	LED - Recessed Can 10"	Integral LED / Integral LED Driver	10	DND - Existing LED fixture	10
Blake Library	20	1	53	Circulation Reference Desk	Office - Admin Area	LED - Recessed Can 8"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Blake Library	21	1	54	231	Library	Recessed Can 12"	100w MH / HID Pulse Start	6	Retrofit fixture with 10" LED Recessed Can Kit (38w / 3600lm) w/12" Goof Ring	6
Blake Library	22	1	55	231	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	3	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	3

Blake Library	23	1	56	207	Office - Admin Area	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	4	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	4
Blake Library	24	1	57	207A	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	25	1	58	207B	Storage - General	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	26	1	59	227	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Blake Library	27	1	60	227	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	28	1	61	225	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	29	1	62	225	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	30	1	63	236	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	31	1	64	236	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	32	1	65	221	Break / Lounge	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	6	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	6
Blake Library	33	1	66	233	Vestible / Foyer	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	34	1	68	233	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	35	1	67	226	Custodial Closet	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Blake Library	36	1	69	206	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	3	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	3
Blake Library	37	1	70	205	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	38	1	72	Roof Stairs	Stairwell - Interior	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Blake Library	39	1	73	Roof Stairs	Stairwell - Interior	Cylinder	CFL 13w PL / CFL	1	Replace fixture with LED Wall Brick (20w / 2700lm) - White	1
Blake Library	40	1	74	204	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	41	1	75	203	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	6	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	6
Blake Library	42	1	76	202	Conference Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	43	1	77	202	Conference Room	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	8	DND - Existing LED fixture	8
Blake Library	44	1	78	201	Office - Admin Area	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	3	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	3
Blake Library	45	1	79	201	Office - Admin Area	2x2 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	46	1	80	224	Office - Open Cubicals	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	12	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	12

Blake Library	47	1	81	223	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	48	1	82	229	Corridor / Hallway - Suite / Dept	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	3	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	3
Blake Library	49	1	83	212	Corridor / Hallway - Suite / Dept	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	6	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	6
Blake Library	50	1	84	212	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	51	1	85	212	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	52	1	86	213	Corridor / Hallway - Suite / Dept	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	3	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	3
Blake Library	53	1	87	222A	Copy Room	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Blake Library	54	1	88	222	Corridor / Hallway - Suite / Dept	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	4	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	4
Blake Library	55	1	89	222	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Blake Library	56	1	90	211	Corridor / Hallway - Suite / Dept	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	3	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	3
Blake Library	57	1	91	211	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	58	1	92	210	Vestible / Foyer	LED - Sconce	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Blake Library	59	1	93	234	Server / Com Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	60	1	94	201	Library	1x4 Rec. Parabolic	F32T8 / 2L Electronic	48	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	48
Blake Library	61	1	95	201	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	62	1	96	201A	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	14	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	14
Blake Library	63	1	97	201A	Library	1x4 Rec. Parabolic	F32T8 / 2L Electronic	8	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Blake Library	64	1	98	201A	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Blake Library	65	1	99	202	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	12	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	12
Blake Library	66	1	152	Exterior	Exterior	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	28	DND - Existing LED fixture	28
Blake Library	67	1	32	142	Restroom - Public	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Blake Library	68	1	34	142	Restroom - Public	4' Strip Cove / Soffit	F32T8 / 2L Electronic	5	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Blake Library	69	1	35	143	Restroom - Public	LED - Recessed	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4

						Can 10" (Retro)				
Blake Library	70	1	36	143	Restroom - Public	4' Strip Cove / Soffit	F32T8 / 2L Electronic	5	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Blake Library	71	1	37	102	Vestible / Foyer	2x2 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Blake Library	72	1	38	102	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	73	1	39	101	Lobby Area - Main	2x2 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Blake Library	74	1	40	101	Lobby Area - Main	2x2 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Blake Library	75	1	41	101	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	76	1	100	122	Server / Com Room	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	77	1	101	144	Mechanical Room	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Blake Library	78	1	102	148	Storage - General	2x2 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	79	1	103	124	Electrical / Mech	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	80	1	104	146	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	81	1	105	127	Office - Admin Area	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	5	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	5
Blake Library	82	1	106	126	Storage - Equipment	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	83	1	107	125	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	84	1	108	115	Workroom	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	14	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	14
Blake Library	85	1	109	115	Workroom	2x2 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	86	1	110	147	Electrical / Mech	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	87	1	111	147	Electrical / Mech	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	88	1	112	145	Custodial Closet	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	89	1	113	114	Storage - General	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	90	1	114	120	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Blake Library	91	1	115	120	Restroom - Public	2' Vanity	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Blake Library	92	1	116	121	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Blake Library	93	1	117	121	Restroom - Public	2' Vanity	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	94	1	118	119	Corridor / Hallway - Suite / Dept	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	5	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	5
Blake Library	95	1	119	119	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	96	1	120	118	Classroom - Study Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	97	1	121	117	Classroom - Study Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	98	1	122	116	Classroom - Study Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	99	1	123	111	Office - Open Cubicals	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	10	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	10
Blake Library	100	1	124	112	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	101	1	125	110	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	102	1	126	110	Library	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	12	DND - Existing LED fixture	12
Blake Library	103	1	127	109/108	Classroom - Computer Lab	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	6	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	6
Blake Library	104	1	128	109/108	Classroom - Computer Lab	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	8	DND - Existing LED fixture	8
Blake Library	105	1	129	106	Office - Private	2x2 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Blake Library	106	1	130	104	Workroom	2x2 Troffer	Integral LED / Integral LED Driver	10	DND - Existing LED fixture	10
Blake Library	107	1	131	Circulation Desk	Library	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Blake Library	108	1	132	Circulation Desk	Library	Recessed Can 10" - Vert	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm) w/10" Goof Ring	4
Blake Library	109	1	133	Circulation Desk	Library	LED - Decorative	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Blake Library	110	1	134	Lobby	Lobby Area - Main	2x2 Troffer	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Blake Library	111	1	135	Lobby	Lobby Area - Main	2x2 Troffer	Integral LED / Integral LED Driver	7	DND - Existing LED fixture	7
Blake Library	112	1	136	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Blake Library	113	1	137	107A	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	20	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	20

Blake Library	114	1	138	107A	Library	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Blake Library	115	1	139	107A	Library	LED - Recessed Can 6" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Blake Library	116	1	140	107A	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	117	1	141	107B	Library	LED - Sconce	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
Blake Library	118	1	142	107C	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	4	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	4
Blake Library	119	1	143	107	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	51	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	51
Blake Library	120	1	144	107	Library	2x2 Troffer	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
Blake Library	121	1	145	107	Library	1x4 Rec. Parabolic	F32T8 / 2L Electronic	186	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	186
Blake Library	122	1	146	107	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	4	DND - Existing LED Exit	4
Blake Library	123	1	147	107D	Library	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Blake Library	124	1	148	Stair #1	Stairwell - Interior	LED - Sconce	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Blake Library	125	1	149	Stair #2	Stairwell - Interior	4' Wall Bracket	FP28T5 / 2L Electronic	3	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	3
Blake Library	126	1	150	Stair #2	Stairwell - Interior	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	127	1	151	Stair #2	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library - Exterior	128	1	153	Exterior	Exterior - Parking / Grounds	LED - Bollard	Integral LED / Integral LED Driver	20	DND - Existing LED fixture	20
Blake Library	129	1	154	Exterior	Exterior	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	17	DND - Existing LED fixture	17
Blake Library	130	1	155	Exterior	Exterior	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	14	DND - Existing LED fixture	14
Blake Library	131	1	156	Exterior	Exterior	Recessed Can 12"	175w MH / HID-175	5	Retrofit fixture with 10" LED Recessed Can Kit (38w / 3600lm) w/12" Goof Ring	5
Blake Library	132	1	157	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Blake Library	133	1	1	140	Auditorium - Seating	LED - Recessed Can 10"	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
Blake Library	134	1	2	140	Auditorium - Seating	LED - Recessed Can 12" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Blake Library	135	1	3	140	Auditorium - Seating	LED - Recessed Can 10"	Integral LED / Integral LED Driver	22	DND - Existing LED fixture	22
Blake Library	136	1	4	140	Auditorium - Seating	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2



Blake Library	137	1	5	140	Auditorium - Seating	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Blake Library	138	1	6	149	Auditorium - Stage	LED - Recessed Can 12" (Retro)	LED (Screw In / Plug In) / N/A	18	DND - Existing LED fixture	18
Blake Library	139	1	7	149	Auditorium - Stage	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	3	DND - Existing LED fixture	3
Blake Library	140	1	8	149	Auditorium - Stage	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Blake Library	141	1	9	152	Storage - General	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Blake Library	142	1	10	152	Storage - General	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Blake Library	143	1	11	151	Restroom - Public	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Blake Library	144	1	12	150	Restroom - Public	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Blake Library	145	1	13	140B	Vestible / Foyer	Recessed Can 6"	75w Incandescent / N/A	1	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	1
Blake Library	146	1	14	140A	Vestible / Foyer	Recessed Can 6"	75w Incandescent / N/A	1	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	1
Blake Library	147	1	15	141	Electrical / Mech	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Blake Library	148	1	16	139	Storage - Equipment	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	149	1	17	135	Storage - Equipment	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	150	1	18	134	Kitchen	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	151	1	19	138	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	152	1	20	232	Mechanical Room	4' Strip	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Blake Library	153	1	21	232	Mechanical Room	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Blake Library	154	1	22	232	Mechanical Room	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	155	1	23	Storage	Storage - General	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Blake Library	156	1	24	132	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	157	1	25	131	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Blake Library	158	1	26	130	Conference Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2

Blake Library	159	1	27	130	Conference Room	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Blake Library	160	1	28	103	Corridor / Hallway	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	7	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	7
Blake Library	161	1	29	103	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Blake Library	162	1	30	128	Auditorium	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	16	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	16
Blake Library	163	1	31	128	Auditorium	LED - Track (Retro)	LED (Screw In / Plug In) / Integral LED Driver	8	DND - Existing LED fixture	8
Blake Library	164	1	49	Roof Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Blake Library	165	1	50	Mechanical	Mechanical Room	4' Strip	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Blake Library	166	1	71	Roof Exterior	Exterior	Jelly Jar	CFL 13w PL / CFL	5	Replace fixture with LED Wall Brick (20w / 2700lm) - White (Requires pipe & wire work)	5
Building Department	167	1	1	102	Lobby Area - Main	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Building Department	168	1	2	102	Lobby Area - Main	Recessed Can 8" - Vert	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Building Department	169	1	3	102	Lobby Area - Main	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Building Department	170	1	4	102	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	171	1	5	Room	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Building Department	172	1	6	Room	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Building Department	173	1	7	Room	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Building Department	174	1	8	Room	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Building Department	175	1	9	141	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Building Department	176	1	10	130	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	177	1	11	130	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	178	1	12	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	179	1	13	Room	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	9	DND - Existing LED fixture	9

Building Department	180	1	14	Room	Office - Open Cubicals	Recessed Can 8" - Vert	CFL 26w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Building Department	181	1	15	Room	Workroom	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	182	1	16	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	183	1	17	Room	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	15	DND - Existing LED fixture	15
Building Department	184	1	18	Room	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	185	1	19	Room	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	14	DND - Existing LED fixture	14
Building Department	186	1	20	Room	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	187	1	21	121	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	188	1	22	123	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	189	1	23	124	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Building Department	190	1	24	124	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Building Department	191	1	25	Room	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	192	1	26	Room	Corridor / Hallway	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	193	1	27	Room	Conference Room	2x4 Troffer	Integral LED / Integral LED Driver	11	DND - Existing LED fixture	11
Building Department	194	1	28	Room	Conference Room	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	195	1	29	Room	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	196	1	30	144	Storage - Equipment	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Building Department	197	1	31	Room	Conference Room	2x4 Troffer	Integral LED / Integral LED Driver	11	DND - Existing LED fixture	11
Building Department	198	1	33	Room	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Building Department	199	1	34	143	Storage - Equipment	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Building Department	200	1	35	106	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	201	1	36	116	Conference Room	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Building Department	202	1	37	Room	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	16	DND - Existing LED fixture	16
Building Department	203	1	38	Room	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Building Department	204	1	39	Room	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	205	1	40	Room	Break / Lounge	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Building Department	206	1	41	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	207	1	42	Room	Restroom - Public	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	208	1	43	Room	Restroom - Public	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	209	1	44	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	210	1	45	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	211	1	46	129	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	212	1	47	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	213	1	48	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	214	1	49	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Building Department	215	1	50	107	Workroom	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Building Department	216	1	51	113	Custodial Closet	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Building Department	217	1	52	112	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Building Department	218	1	53	110	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Building Department	219	1	54	Room	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Building Department	220	1	55	Room	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Building Department	221	1	57	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	222	1	56	114	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Building Department	223	1	58	114	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Building Department	224	1	59	Room	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	225	1	60	Room	Lobby Area - Main	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	226	1	61	127	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Building Department	227	1	62	126	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Building Department	228	1	63	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Building Department	229	1	64	Exterior	Exterior	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	18	DND - Existing LED fixture	18
Building Department	230	1	65	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Building Department	231	1	66	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Citrus Grove Park	232	1	1	100	Kitchen	4' Vapor Tight	FP28T5 / 2L Electronic	4	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	4
Citrus Grove Park	233	1	2	100	Kitchen	4' Vapor Tight w/Battery	FP28T5 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	2
Citrus Grove Park	234	1	5	100	Kitchen	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Citrus Grove Park	235	1	3	101	Workroom	4' Vapor Tight	FP28T5 / 2L Electronic	2	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	2
Citrus Grove Park	236	1	4	101	Workroom	4' Vapor Tight w/Battery	FP28T5 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Citrus Grove Park	237	1	6	105A	Restroom - Public	4' Vapor Tight	FP28T5 / 2L Electronic	3	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	3
Citrus Grove Park	238	1	7	105	Mechanical Room	4' Vapor Tight	FP28T5 / 2L Electronic	2	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	2
Citrus Grove Park	239	1	8	105B	Restroom - Public	4' Vapor Tight	FP28T5 / 2L Electronic	3	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	3
Citrus Grove Park	240	1	9	103	Storage - Equipment	4' Vapor Tight	FP28T5 / 2L Electronic	1	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	1
Citrus Grove Park	241	1	10	102	Electrical / Mech	4' Vapor Tight	FP28T5 / 2L Electronic	2	Retrofit fixture with (2) 4' T5HE LED Linear Tube and Normal Power LED Driver	2
Citrus Grove Park	242	1	11	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Citrus Grove Park	243	1	12	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	13	DND - Existing LED fixture	13
County Line Park Community Center	244	1	1	Dance Studio	Auditorium	LED - Recessed Can 8"	Integral LED / Integral LED Driver	17	DND - Existing LED fixture	17

County Line Park Community Center	245	1	2	Dance Studio	Auditorium	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
County Line Park Community Center	246	1	3	Storage	Storage - General	LED - Canopy (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1
County Line Park Community Center	247	1	4	Kitchen	Kitchen	LED - Recessed Can 8"	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
County Line Park Community Center	248	1	5	Kitchen	Kitchen	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
County Line Park Community Center	249	1	6	Restroom	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
County Line Park Community Center	250	1	7	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
County Line Park Community Center	251	1	8	Janitor	Custodial Closet	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
County Line Park Community Center	252	1	9	Restroom	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
County Line Park Community Center	253	1	10	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
County Line Park Community Center	254	1	11	Exterior	Exterior	LED - Flood (20w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
County Line Park Community Center	255	1	12	Exterior	Exterior	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
County Line Park Community Center	256	1	13	Exterior	Exterior	Flood	150w Incandescent / N/A	1	Relamp fixture with PAR38 LED	1
Court Holding - Exterior	257	1	1	Exterior	Exterior - Parking / Grounds	Bollard	100w MH / HID Pulse Start	27	Retrofit fixture with LED Direct Drive Lamp - Remove ballast and direct wire socket	27
Court Holding	258	1	2	Exterior	Exterior	LED - Wall Pack (Retro)	LED Corn Cob / N/A	3	DND - Existing LED fixture	3
Court Holding	259	1	3	Exterior	Exterior	Wall Pack	150w MH / HID-150	1	Replace fixture with LED Wall Pack (35w / 4655lm)	1
Court Holding	260	1	4	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Court Holding	261	1	5	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Court Holding	262	1	6	Exterior	Exterior	LED - Surface Drum	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Court Holding	263	1	7	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Court Holding - Exterior	264	1	8	Exterior	Exterior - Parking / Grounds	Flood	250w MH / HID-250	1	Replace fixture with LED Flood (90w / 13950lm)	1
Court Holding	265	1	9	Exterior	Exterior	LED - Recessed Can 10"	Integral LED / Integral LED Driver	30	DND - Existing LED fixture	30

Court Holding - Exterior	266	1	10	Exterior	Exterior - Parking / Grounds	Post Top	100w MH / HID-100	8	Relamp fixture with LED CornCob lamp (45w / 6300lm) - remove existing ballast and direct wire socket	8
Court Holding	267	1	11	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Court Holding - Exterior	268	1	12	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	269	1	13	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	270	1	14	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	271	1	15	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	272	1	16	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	273	1	17	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	274	1	18	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	275	1	19	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	276	1	20	Rectangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	277	1	21	Triangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	278	1	22	Triangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1



Court Holding - Exterior	279	1	23	Triangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	280	1	24	Triangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	281	1	25	Triangle Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	282	1	26	Courthouse Back Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	283	1	27	Courthouse Back Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	284	1	28	Courthouse Back Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	285	1	29	Courthouse Back Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Court Holding - Exterior	286	1	30	Courthouse Handicap Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library	287	1	38	110	Office - Admin Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Cummings Library	288	1	39	111	Server / Com Room	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Cummings Library	289	1	40	112	Custodial Closet	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	290	1	41	108A	Vestible / Foyer	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	2
Cummings Library	291	1	3	108B	Workroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	4
Cummings Library	292	1	4	108B	Workroom	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	2
Cummings Library	293	1	44	107A	Vestible / Foyer	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	2

Cummings Library	294	1	45	107B	Workroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	4
Cummings Library	295	1	46	107B	Workroom	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	2
Cummings Library	296	1	47	109	Corridor / Hallway	Recessed Can 8" - Horz	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Cummings Library	297	1	48	109	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Cummings Library	298	1	49	109	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	299	1	50	103	Mechanical Room	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	300	1	51	103	Mechanical Room	4' Wrap - Emergency Battery	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Cummings Library	301	1	52	114	Library	12' Direct/Indirect	F32T8 / 2L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	2
Cummings Library	302	1	59	114	Library	4' Direct/Indirect	F32T8 / 2L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Cummings Library	303	1	53	106	Library	12' Direct/Indirect	F32T8 / 2L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	3
Cummings Library	304	1	54	106	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Cummings Library	305	1	55	118	Library	Decorative Chandelier	CFL 42w PL / CFL	26	Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	26
Cummings Library	306	1	56	118	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Cummings Library	307	1	57	118	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	308	1	58	118	Library	Recessed Can 8" - Vert	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	4
Cummings Library	309	1	60	102	Lobby Area - Main	Wall Pack - FCT - UpLight	175w MH / HID-175	4	Relamp fixture with LED CornCob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	4
Cummings Library	310	1	61	102	Lobby Area - Main	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	311	1	62	102	Lobby Area - Main	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Cummings Library	312	1	63	101	Lobby Area - Main	Recessed Can 8" - Horz	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed	4

									Can Kit (16w / 1600lm)	
Cummings Library	313	1	64	101	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	314	1	119	117	Stairwell - Interior	4' Wall Bracket	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Cummings Library	315	1	120	117	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	316	1	121	104	Stairwell - Interior	4' Wall Bracket	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Cummings Library	317	1	122	104	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	318	1	123	120	Stairwell - Interior	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	3	DND - Existing LED fixture	3
Cummings Library	319	1	124	120	Stairwell - Interior	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Cummings Library	320	1	128	104A	Storage - General	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	321	1	129	113	Mechanical Room	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	322	1	130	113	Mechanical Room	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	323	1	65	122	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Cummings Library	324	1	66	123	Electrical / Mech	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	325	1	67	125	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Cummings Library	326	1	68	125	Office - Private	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Cummings Library	327	1	69	124	Break / Lounge	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Cummings Library	328	1	71	124	Break / Lounge	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Cummings Library	329	1	70	146	Storage - General	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	330	1	72	127	Workroom	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	8	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	8
Cummings Library	331	1	73	127	Workroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	332	1	74	126	Mechanical Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	1

Cummings Library	333	1	75	129/133	Workroom	2x2 Rec. Parabolic	FB31T8/U / 3L Electronic	10	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	10
Cummings Library	334	1	76	129/133	Workroom	2x2 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Cummings Library	335	1	77	132	Office - Private	2x2 Rec. Parabolic	PLL 40w Biax / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Cummings Library	336	1	78	131	Electrical / Mech	2x2 Rec. Parabolic	PLL 40w Biax / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Cummings Library	337	1	79	131	Electrical / Mech	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Cummings Library	338	1	80	130	Mechanical Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	339	1	81	125A	Office - Private	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Cummings Library	340	1	82	134A	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	341	1	83	134B	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	342	1	84	134C	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	343	1	85	134D	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	344	1	86	134E	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	345	1	87	134F	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	346	1	88	134G	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	347	1	89	134H	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	348	1	90	134I	Restroom - Public	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	349	1	91	134	Corridor / Hallway - Suite / Dept	Recessed Can 10" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	1
Cummings Library	350	1	92	134	Corridor / Hallway - Suite / Dept	Recessed Can 10" - Horz	CFL 13w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (17w /	3

									1380lm) w/10" Goof Ring & Battery	
Cummings Library	351	1	93	134	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	352	1	94	135	Lobby Area - Main	Recessed Can 8" - Horz	CFL 13w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Cummings Library	353	1	95	135	Lobby Area - Main	Recessed Can 10" - Horz	CFL 13w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	6
Cummings Library	354	1	96	135	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Cummings Library	355	1	97	136	Mechanical Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	357	1	99	137	Conference Room	2x4 Rec. Parabolic	F32T8 / 3L Electronic	17	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	17
Cummings Library	358	1	100	137	Conference Room	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	5	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	5
Cummings Library	359	1	101	137	Conference Room	LED - Track (Retro)	LED (Screw In / Plug In) / Integral LED Driver	39	DND - Existing LED fixture	39
Cummings Library	360	1	102	137	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Cummings Library	361	1	103	133	Storage - Equipment	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Cummings Library	362	1	104	140/141	Classroom - Study Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Cummings Library	363	1	105	142	Classroom - Study Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Cummings Library	364	1	106	143	Conference Room	2x4 Rec. Parabolic	F32T8 / 3L Electronic	3	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	3
Cummings Library	365	1	107	143	Conference Room	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Cummings Library	366	1	108	144	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Cummings Library	367	1	109	144	Office - Private	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Cummings Library	368	1	110	121	Library	Decorative Chandelier	CFL 42w PL / CFL	2	Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	2
Cummings Library	369	1	111	121	Library	Recessed Can 8" - Horz	CFL 13w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Cummings Library	370	1	112	121	Library	Recessed Can 8" - Horz - Emergency Battery	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	1
Cummings Library	371	1	113	128	Library	4' Direct/Indirect	F32T8 / 2L Electronic	59	Retrofit fixture with (2) 4' T8 LED Linear	59

									Tube and Normal Power LED Driver	
Cummings Library	372	1	114	128	Library	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Cummings Library	373	1	115	138/139	Library	Decorative Chandelier	CFL 42w PL / CFL	20	Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	20
Cummings Library	374	1	116	138/139	Library	2x2 Rec. Parabolic	FB31T8/U / 3L Electronic	4	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	4
Cummings Library	375	1	117	138/139	Library	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Cummings Library	376	1	118	138/139	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	377	1	125	Exterior	Exterior	Flood	CFL 42w PL / CFL	6	Replace fixture with LED Flood (35w / 5250lm)	6
Cummings Library	378	1	126	Exterior	Exterior	LED - Recessed Can 10"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Cummings Library	379	1	127	Exterior	Exterior	Wall Pack - FCT - UpLight	175w MH / HID-175	1	Relamp fixture with LED CornCob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	1
Cummings Library	380	1	131	Exterior	Exterior	Wall Pack	CFL 42w PL / CFL	3	Replace fixture with LED Wall Pack (25w / 3525lm)	3
Cummings Library	381	1	132	Exterior	Exterior	Recessed Can 8" - Horz	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Cummings Library	382	1	133	Exterior	Exterior	LED - Recessed Can 10"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Cummings Library	383	1	134	Exterior	Exterior	Wall Mount UpLight	100w MH / HID-100	3	Relamp fixture with LED CornCob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	3
Cummings Library	384	1	135	Exterior	Exterior	Wall Pack - Full Cut	CFL 13w PL / CFL	1	Replace fixture with LED Wall Pack (25w / 3525lm)	1
Cummings Library	385	1	1	211	Workroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Cummings Library	386	1	2	211	Workroom	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Cummings Library	387	1	5	208	Custodial Closet	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Cummings Library	388	1	6	207	Mechanical Room	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Cummings Library	389	1	7	206A	Vestible / Foyer	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	2
Cummings Library	390	1	8	206B	Restroom - Public	Recessed Can 8" - Horz	CFL 13w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Cummings Library	391	1	9	206B	Restroom - Public	Recessed Can 8" - Horz - Emergency Battery	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	4

Cummings Library	392	1	10	205A	Vestible / Foyer	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	2
Cummings Library	393	1	11	205B	Restroom - Public	Recessed Can 8" - Horz	CFL 13w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Cummings Library	394	1	12	205B	Restroom - Public	Recessed Can 8" - Horz - Emergency Battery	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	4
Cummings Library	395	1	13	204	Classroom - Study Room	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Cummings Library	396	1	14	213	Library	Recessed Can 8" - Horz	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Cummings Library	397	1	15	213	Library	Recessed Can 8" - Horz - Emergency Battery	CFL 13w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	2
Cummings Library	398	1	16	213	Library	Track Spot	PAR30 75w / N/A	3	Relamp fixture with PAR30 LED	3
Cummings Library	399	1	17	213	Library	Track Spot	PAR30 75w / N/A	4	Relamp fixture with PAR30 LED	4
Cummings Library	400	1	18	209	Library	Decorative Chandelier	CFL 42w PL / CFL	10	Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	10
Cummings Library	401	1	19	209	Library	LED - Recessed Can 8"	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Cummings Library	402	1	20	209	Library	LED - Recessed Can 8" w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Cummings Library	403	1	21	209	Library	Recessed Can 8" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Cummings Library	404	1	22	209	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	405	1	23	209	Library	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Cummings Library	406	1	24	202	Lobby Area - Main	Decorative Chandelier	CFL 42w PL / CFL	5	Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	5
Cummings Library	407	1	25	202	Lobby Area - Main	Decorative Chandelier	CFL 42w PL / CFL	2	Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	2
Cummings Library	408	1	26	202	Lobby Area - Main	Decorative Low Bay	CFL 42w PL / CFL	8	Retrofit fixture with (2) 16w LED Direct Drive lamp - remove ballast & direct wire socket	8
Cummings Library	409	1	27	202	Lobby Area - Main	Recessed Can 8" - Vert w/Battery	CFL 26w PL / CFL	8	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) - Emergency Battery	8
Cummings Library	410	1	28	202	Lobby Area - Main	Recessed Can 8" - Vert w/Battery	CFL 26w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) - Emergency Battery	3
Cummings Library	411	1	29	202	Lobby Area - Main	LED - Recessed	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3



						Can 8" w/battery				
Cummings Library	412	1	30	202	Lobby Area - Main	Recessed Can 8" - Vert	CFL 26w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	3
Cummings Library	413	1	31	202	Lobby Area - Main	Recessed Can 8" - Horz	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Cummings Library	414	1	32	202	Lobby Area - Main	Emergency Egress WP	Incandescent / N/A	5	DND - Existing Emergency Egress	5
Cummings Library	415	1	33	202	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Cummings Library	416	1	34	202	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Cummings Library	417	1	35	202	Lobby Area - Main	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Cummings Library	418	1	36	201	Vestible / Foyer	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Cummings Library	419	1	37	201	Vestible / Foyer	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Cummings Library	420	1	42	206B	Restroom - Public	Recessed Can 8" - Horz	CFL 13w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Cummings Library	421	1	43	206B	Restroom - Public	Recessed Can 8" - Horz - Emergency Battery	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	4
Cummings Library - Exterior	422	1	136	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	423	1	137	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	424	1	138	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	425	1	139	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	426	1	140	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	427	1	141	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	428	1	142	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1

									TBD) - Slipfit w/Tenon Direct Arm	
Cummings Library - Exterior	429	1	143	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	430	1	144	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	431	1	145	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	432	1	146	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	433	1	148	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	434	1	149	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library - Exterior	435	1	150	Parking Lot	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Cummings Library	436	1	151	Site Sign	Exterior	LED - Flood (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Cummings Library	437	1	152	9-11 Memorial	Exterior	LED - Flood (60w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Cummings Library	438	1	153	9-11 Memorial	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Cummings Library	439	1	154	Flagpole	Exterior	LED - Flood (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Fire Rescue Fleet Maintenance	440	1	2	103	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue Fleet Maintenance	441	1	3	102	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue Fleet Maintenance	442	1	4	Room	Warehouse	High Bay	400w MH / HID-400	15	Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	15
Fire Rescue Fleet Maintenance	443	1	5	Room	Warehouse	4' Strip (20w)	Integral LED / Integral LED Driver	16	DND - Existing LED fixture	16
Fire Rescue Fleet Maintenance	444	1	6	Room	Warehouse	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1

Fire Rescue Fleet Maintenance	445	1	7	Room	Warehouse	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Fire Rescue Fleet Maintenance	446	1	9	Room	Warehouse	4' Wrap	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Rescue Fleet Maintenance	447	1	10	Room	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Rescue Fleet Maintenance	448	1	11	Room	Warehouse	4' Strip (20w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Fire Rescue Fleet Maintenance	449	1	8	117	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue Fleet Maintenance	450	1	12	104	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue Fleet Maintenance	451	1	13	105	Conference Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Rescue Fleet Maintenance	452	1	14	108	Custodial Closet	4' Vapor Tight	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue Fleet Maintenance	453	1	15	106	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue Fleet Maintenance	454	1	16	101	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Rescue Fleet Maintenance	455	1	17	101	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Rescue Fleet Maintenance	456	1	18	101	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Fire Rescue Fleet Maintenance	457	1	19	111	Locker Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Rescue Fleet Maintenance	458	1	20	111A	Laundry - Small	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue Fleet Maintenance	459	1	21	110	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue Fleet Maintenance	460	1	22	110	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Fire Rescue Fleet Maintenance	461	1	23	112	Locker Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue Fleet Maintenance	462	1	24	116	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue Fleet Maintenance	463	1	25	113	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Rescue Fleet Maintenance	464	1	26	Room	Maintenance Shop	LED - High Bay (100w)	Integral LED / Integral LED Driver	18	DND - Existing LED fixture	18
Fire Rescue Fleet Maintenance	465	1	27	Room	Maintenance Shop	Emergency Egress WP	Incandescent / N/A	5	DND - Existing Emergency Egress	5

Fire Rescue Fleet Maintenance	466	1	28	Room	Maintenance Shop	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Fire Rescue Fleet Maintenance	467	1	29	Room	Exterior	4' Vapor Tight	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Rescue Fleet Maintenance	468	1	30	Room	Exterior	4' Vapor Tight	F32T8 / 2L Electronic	5	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Fire Rescue Fleet Maintenance	469	1	31	Room	Exterior	4' Vapor Tight	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue Fleet Maintenance	470	1	32	Room	Exterior	4' Vapor Tight	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Rescue Fleet Maintenance	471	1	33	Room	Office - Admin Area	4' Vapor Tight	F32T8 / 3L Electronic	10	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Fire Rescue Fleet Maintenance	472	1	34	Exterior	Exterior	LED - Wall Brick (Retro)	LED (Screw In / Plug In) / N/A	15	DND - Existing LED fixture	15
Fire Rescue Fleet Maintenance	473	1	35	Exterior	Exterior	LED - Flood (Retro)	LED (Screw In / Plug In) / N/A	3	DND - Existing LED fixture	3
Fire Rescue Fleet Maintenance	474	1	36	Covered Bay	Warehouse	4' Vapor Tight	F32T8 / 2L Electronic	16	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	16
Fire Rescue Fleet Maintenance - Exterior	475	1	37	Perimeter and Parking	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Rescue Fleet Maintenance - Exterior	476	1	38	Perimeter and Parking	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Rescue Fleet Maintenance - Exterior	477	1	39	Perimeter and Parking	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Rescue Fleet Maintenance - Exterior	478	1	40	Perimeter and Parking	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Rescue Fleet Maintenance - Exterior	479	1	41	Perimeter and Parking	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Rescue Fleet Maintenance - Exterior	480	1	42	Perimeter and Parking	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Rescue Fleet Maintenance - Exterior	481	1	43	Perimeter and Parking	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1

Fire Rescue LifeStar Hanger	482	1	1	Room	Bunk Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	483	1	2	Room	Bunk Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	484	1	3	Room	Bunk Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	485	1	4	Room	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	486	1	5	Room	Locker Room - Showers	LED - Recessed Can 6"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Rescue LifeStar Hanger	487	1	6	Room	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	488	1	7	Room	Locker Room - Showers	LED - Recessed Can 6"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Rescue LifeStar Hanger	489	1	8	Room	Dayroom	2x4 Rec. Acrylic	F32T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Fire Rescue LifeStar Hanger	490	1	10	Room	Dayroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Rescue LifeStar Hanger	491	1	11	Room	Dayroom	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Fire Rescue LifeStar Hanger	492	1	9	Room	Corridor / Hallway	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	493	1	12	Room	Kitchen	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Rescue LifeStar Hanger	494	1	13	Room	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	495	1	14	Room	Custodial Closet	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	496	1	15	Room	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue LifeStar Hanger	497	1	16	Room	Training Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Rescue LifeStar Hanger	498	1	17	Room	Server / Com Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	499	1	18	Room	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	500	1	19	Room	Bunk Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2

Fire Rescue LifeStar Hanger	501	1	20	Room	Bunk Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Rescue LifeStar Hanger	502	1	21	Room	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue LifeStar Hanger	503	1	22	Room	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Fire Rescue LifeStar Hanger	504	1	23	Room	Corridor / Hallway	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	505	1	24	Room	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Fire Rescue LifeStar Hanger	506	1	25	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Fire Rescue LifeStar Hanger	507	1	26	Room	Hanger	High Bay	1000w MH / HID-1000	5	Replace fixture with LED High Bay (320w / 50550lm) w/wireguard & microwave motion sensor step dimming	5
Fire Rescue LifeStar Hanger	508	1	27	Room	Hanger	LED - High Bay (100w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Rescue LifeStar Hanger	509	1	28	Room	Hanger	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Fire Rescue LifeStar Hanger	510	1	29	Room	Hanger	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Fire Rescue LifeStar Hanger	511	1	30	Room	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Rescue LifeStar Hanger	512	1	31	Room	Laundry - Small	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	513	1	32	Room	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Rescue LifeStar Hanger	514	1	33	Room	Locker Room - Showers	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Rescue LifeStar Hanger	515	1	34	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Rescue LifeStar Hanger - Exterior	516	1	35	Exterior	Exterior - Parking / Grounds	Flood	250w MH / HID-250	2	Replace fixture with LED Flood (90w / 13950lm)	2
Fire Rescue LifeStar Hanger	517	1	36	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #16	518	1	1	109	Lobby Area - Main	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	7	DND - Existing LED fixture	7
Fire Station #16	519	1	3	109	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #16	520	1	2	111	Exam / Treatment	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #16	521	1	4	112	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Fire Station #16	522	1	5	113	Multi Purpose	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #16	523	1	6	113	Multi Purpose	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	10	DND - Existing LED fixture	10
Fire Station #16	524	1	7	119	Storage - General	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #16	525	1	8	118	Storage - General	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #16	526	1	9	114	Office - Admin Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #16	527	1	10	114	Office - Admin Area	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	10	DND - Existing LED fixture	10
Fire Station #16	528	1	11	108	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #16	529	1	12	107	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #16	530	1	13	105	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #16	531	1	14	104	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #16	532	1	15	104	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #16	533	1	16	143	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	534	1	17	141	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	535	1	18	139	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	536	1	19	137	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	537	1	20	135	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	538	1	21	136	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	539	1	22	138	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	540	1	23	140	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	541	1	24	142	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #16	542	1	25	144	Bunk Room	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1



Fire Station #16	543	1	26	103	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #16	544	1	27	103	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #16	545	1	28	104	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #16	546	1	29	104	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #16	547	1	30	101	Gymnasium	2x4 Rec. Parabolic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #16	548	1	31	129	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #16	549	1	32	134	Corridor / Hallway - Suite / Dept	Recessed Can 8" - Vert	CFL 26w PL / CFL	12	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	12
Fire Station #16	550	1	33	134	Corridor / Hallway - Suite / Dept	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #16	551	1	34	134	Corridor / Hallway - Suite / Dept	Recessed Can 8"	75w Incandescent / N/A	9	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	9
Fire Station #16	552	1	35	134	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #16	553	1	36	134	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #16	554	1	37	127	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #16	555	1	38	120	Café / Dining Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #16	556	1	39	120	Café / Dining Area	Recessed Can 8"	75w Incandescent / N/A	14	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	14
Fire Station #16	557	1	40	120	Café / Dining Area	Recessed Can 8" - Vert	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #16	558	1	41	120	Café / Dining Area	Recessed Can 8"	75w Incandescent / N/A	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Fire Station #16	559	1	42	120	Café / Dining Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #16	560	1	43	121	Kitchen	2x4 Rec. Acrylic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #16	561	1	44	121	Kitchen	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Fire Station #16	562	1	45	125	Truck Bay	High Bay	400w MH / HID-400	6	Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector &	6

									microwave motion sensor step dimming	
Fire Station #16	563	1	46	125	Truck Bay	LED - Recessed Can 8"	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Fire Station #16	564	1	47	125	Truck Bay	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Fire Station #16	565	1	48	126	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #16	566	1	49	128	Workroom	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #16	567	1	50	130	Locker Room	4' Vapor Tight	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #16	568	1	51	131	Laundry - Small	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #16	569	1	52	132	Electrical / Mech	4' Vapor Tight	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #16	570	1	53	133	Mechanical Room	4' Vapor Tight	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #16	571	1	54	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Fire Station #16	572	1	55	Exterior	Exterior	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #16	573	1	56	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Fire Station #16 - Exterior	574	1	57	Exterior	Exterior - Parking / Grounds	LED - Flood (100w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Fire Station #16	575	1	58	Exterior	Exterior	LED - Recessed Can 10"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Fire Station #16	576	1	59	Exterior	Exterior	Recessed Can 8" - Horz	CFL 32w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #16	577	1	60	Exterior	Exterior	Sconce	I100A / N/A	2	Relamp fixture with (2) A19 LED	2
Fire Station #16 - Exterior	578	1	61	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #16 - Exterior	579	1	62	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #16 - Exterior	580	1	63	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #16 - Exterior	581	1	64	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1

									TBD) - Slipfit w/Tenon Direct Arm	
Fire Station #16 - Exterior	582	1	65	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #16 - Exterior	583	1	66	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #16 - Exterior	584	1	67	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #16 - Exterior	585	1	68	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21	586	1	2	126	Lobby Area - Main	Recessed Can 8" - Vert	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #21	587	1	3	126	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #21	588	1	4	130	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	589	1	5	128	Dayroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #21	590	1	6	128	Dayroom	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Fire Station #21	591	1	7	129	Storage - General	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #21	592	1	8	127	Waiting Room	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #21	593	1	9	123	Office - Admin Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #21	594	1	10	123	Office - Admin Area	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Fire Station #21	595	1	11	113	Storage - Equipment	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	596	1	12	123	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	597	1	13	122	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	598	1	14	122	Office - Private	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1

Fire Station #21	599	1	15	120	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	600	1	16	119	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	601	1	17	119	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #21	602	1	18	119	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #21	603	1	19	117/118	Café / Dining Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	10	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Fire Station #21	604	1	20	117/118	Café / Dining Area	Recessed Can 8" - Vert	CFL 18w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #21	605	1	21	117/118	Café / Dining Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #21	606	1	22	115	Storage - Equipment	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	607	1	23	102	Kitchen	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Fire Station #21	608	1	24	102	Kitchen	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Fire Station #21	609	1	25	116	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	610	1	26	116	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #21	611	1	27	114	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	612	1	28	114	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #21	613	1	29	112	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	614	1	30	112	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #21	615	1	31	110	Custodial Closet	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	616	1	32	109	Gymnasium	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #21	617	1	33	111	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	618	1	34	107	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1

Fire Station #21	619	1	35	107	Office - Private	LED - Track (Retro)	LED (Screw In / Plug In) / N/A	3	DND - Existing LED fixture	3
Fire Station #21	620	1	36	106	Corridor / Hallway	Recessed Can 8" - Vert	CFL 26w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Fire Station #21	621	1	37	106	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #21	622	1	38	105J	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	623	1	39	105H	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	624	1	40	105F	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	625	1	41	105E	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	626	1	42	105C	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	627	1	43	105B	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	628	1	44	105A	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	629	1	45	105M	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	630	1	46	105N	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	631	1	47	105L	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	632	1	48	105	Corridor / Hallway - Suite / Dept	Recessed Can 8" - Vert	CFL 26w PL / CFL	9	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	9
Fire Station #21	633	1	49	105	Corridor / Hallway - Suite / Dept	Recessed Can 8"	75w Incandescent / N/A	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #21	634	1	50	105	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #21	635	1	51	132	Truck Bay	High Bay	1000w MH / HID-1000	12	Replace fixture with LED High Bay (320w / 50550lm) w/wireguard & microwave motion sensor step dimming	12
Fire Station #21	636	1	52	132	Truck Bay	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	8	DND - Existing LED fixture	8
Fire Station #21	637	1	53	132	Truck Bay	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Fire Station #21	638	1	54	108	Electrical / Mech	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Fire Station #21	639	1	55	140	Locker Room	4' Vapor Tight	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #21	640	1	56	137	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #21	641	1	57	139	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	8	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Fire Station #21	642	1	58	138	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #21	643	1	59	136	Laundry - Small	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #21	644	1	60	135	Workroom	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #21	646	1	62	131	Mechanical Room	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #21	647	1	63	101A	Corridor / Hallway	2x4 Rec. Parabolic	F32T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Fire Station #21	648	1	64	101A	Corridor / Hallway	Recessed Can 8" - Vert	CFL 26w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Fire Station #21	649	1	65	101A	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Fire Station #21	650	1	66	107	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #21	651	1	67	106	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	652	1	68	105	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	653	1	69	105	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #21	654	1	70	105	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #21	655	1	71	102	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #21	656	1	72	101B	Truck Bay	4' Strip (20w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Fire Station #21	657	1	73	101B	Truck Bay	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #21	658	1	74	101C	Mechanical Room	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #21	659	1	75	Exterior	Exterior	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	16	DND - Existing LED fixture	16

Fire Station #21	660	1	76	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #21	661	1	77	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #21 - Exterior	662	1	78	Exterior	Exterior - Parking / Grounds	Flood	150w MH / HID-150	2	Replace fixture with LED Flood (35w / 5250lm)	2
Fire Station #21	663	1	79	Exterior	Exterior	LED - Sconce	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #21	664	1	90	Exterior	Exterior	LED - Flood (60w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #21 - Exterior	665	1	80	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	666	1	81	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	667	1	82	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	668	1	83	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	669	1	84	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	670	1	85	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	671	1	86	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	672	1	87	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	673	1	88	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #21 - Exterior	674	1	89	Parking and Drive	Exterior - Parking / Grounds	Cobrahead	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1



Fire Station #22	675	1	1	Room	Lobby Area - Main	2x2 Rec. Acrylic	F17T8 / 2L Electronic	2	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	676	1	2	Room	Lobby Area - Main	2x2 Rec. Parabolic w/Battery	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Fire Station #22	677	1	3	Room	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #22	678	1	4	1-190	Mechanical Room	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	679	1	5	1-103	Kitchen	2x2 Rec. Acrylic	F17T8 / 2L Electronic	4	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #22	680	1	6	1-103	Kitchen	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Fire Station #22	681	1	7	1-102	Dayroom	2x2 Rec. Acrylic	F17T8 / 2L Electronic	5	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	5
Fire Station #22	682	1	8	1-102	Dayroom	2x2 Rec. Parabolic w/Battery	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Fire Station #22	683	1	9	1-102	Dayroom	Recessed Can 8" - Horz	CFL 32w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Fire Station #22	684	1	10	1-101	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	685	1	11	1-101A	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	686	1	12	1-101B	Restroom - Public	2x2 Rec. Acrylic	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	687	1	13	1-101B	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #22	688	1	14	1-101B	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #22	689	1	15	1-108	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	690	1	16	1-109	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	691	1	17	1-110	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	692	1	18	1-111	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	693	1	19	1-112	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear	2

									Tube and Normal Power LED Driver	
Fire Station #22	694	1	20	1-113	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	695	1	21	1-115	Restroom - Public	2x2 Rec. Acrylic	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	696	1	22	1-115	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #22	697	1	23	1-115	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #22	698	1	24	1-114	Restroom - Public	2x2 Rec. Acrylic	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	699	1	25	1-114	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #22	700	1	26	1-114	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #22	701	1	27	1-180	Custodial Closet	4' Vapor Tight	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	703	1	29	1-105	Storage - Equipment	2x2 Rec. Acrylic	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	704	1	30	1-104	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #22	705	1	31	1-104	Office - Admin Area	Recessed Can 8" - Horz	CFL 42w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Fire Station #22	706	1	32	1-001	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	707	1	33	1-001	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #22	708	1	39	1-001	Corridor / Hallway	2x4 Rec. Acrylic w/Battery	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Fire Station #22	709	1	34	1-002	Corridor / Hallway	2x2 Rec. Acrylic	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	710	1	35	1-003	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #22	711	1	36	1-003	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Fire Station #22	712	1	37	1-003	Corridor / Hallway	2x4 Rec. Acrylic w/Battery	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Fire Station #22	713	1	38	1-003	Corridor / Hallway	Recessed Can 8" - Horz	CFL 42w PL / CFL	4	Retrofit fixture with 8" LED Recessed	4

									Can Kit (16w / 1600lm)	
Fire Station #22	714	1	40	1-107	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	715	1	41	1-107	Storage - Equipment	4' Vapor Tight (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #22	716	1	42	1-107	Storage - Equipment	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Fire Station #22	717	1	43	1-106	Locker Room	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	718	1	44	1-106	Locker Room	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Fire Station #22	719	1	45	1-290	Mechanical Room	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	720	1	46	1-117	Truck Bay	2x4 High Bay	FP54T5HO / 4L Electronic	7	Replace fixture with LED High Bay (100w / 16500lm) w/Clear Reflector & microwave motion sensor step dimming	7
Fire Station #22	721	1	47	1-117	Truck Bay	LED - High Bay (80w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #22	722	1	48	1-117	Truck Bay	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Fire Station #22	723	1	49	1-004	Vestible / Foyer	2x2 Rec. Acrylic	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #22	724	1	51	1-004	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #22	725	1	50	1-116	Laundry - Small	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #22	726	1	52	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Fire Station #22	727	1	53	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #22	728	1	54	Exterior	Exterior	LED - Wall Pack (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1
Fire Station #22	729	1	55	Exterior	Exterior	Wall Pack	CFL 42w PL / CFL	2	Replace fixture with LED Wall Pack (25w / 3525lm)	2
Fire Station #22	730	1	56	Exterior	Exterior	LED - Flood (60w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #23	731	1	1	Lobby	Lobby Area - Main	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #23	732	1	2	Lobby	Lobby Area - Main	Recessed Can 8" - Vert w/Battery	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	1
Fire Station #23	733	1	3	Lobby	Lobby Area - Main	Recessed Can	I100A / N/A	6	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Fire Station #23	734	1	4	Lobby	Lobby Area - Main	Recessed Can 8" - Vert	CFL 32w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #23	735	1	5	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Fire Station #23	736	1	6	Stor	Storage - General	Jelly Jar	I100A / N/A	1	Relamp fixture with A19 LED	1
Fire Station #23	737	1	7	103	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	738	1	8	Open og	Office - Admin Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #23	739	1	10	Open og	Office - Admin Area	Recessed Can 8" - Vert	CFL 26w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Fire Station #23	740	1	9	106	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #23	741	1	11	107	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #23	742	1	13	108A	Bunk Room	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #23	743	1	15	109	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	744	1	16	109	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #23	745	1	17	109	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #23	746	1	18	110	Dayroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #23	747	1	19	110	Dayroom	Recessed Can	I100A / N/A	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #23	748	1	20	110	Dayroom	Recessed Can	I100A / N/A	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #23	749	1	21	110	Dayroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #23	750	1	22	115	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	751	1	23	111	Kitchen	2x4 Rec. Acrylic	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #23	752	1	24	111	Kitchen	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Fire Station #23	753	1	25	111	Kitchen	LED - Recessed Can 8"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Fire Station #23	754	1	26	112	Café / Dining Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #23	755	1	27	112	Café / Dining Area	LED - Recessed Can 8"	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6

Fire Station #23	756	1	28	112	Café / Dining Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #23	757	1	29	113	Storage - General	Jelly Jar	CFL 23w Screw In / Integral CFL	1	Relamp fixture with PAR30 LED	1
Fire Station #23	758	1	30	123	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	759	1	31	123	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #23	760	1	32	124	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	761	1	33	125	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	762	1	34	126	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	763	1	35	127	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	764	1	36	128	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	765	1	37	129	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	766	1	38	130	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	767	1	39	130	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #23	768	1	40	131	Corridor / Hallway - Suite / Dept	Recessed Can 8" - Vert	CFL 32w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #23	769	1	41	131	Corridor / Hallway - Suite / Dept	Recessed Can	I100A / N/A	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #23	770	1	42	132	Corridor / Hallway - Suite / Dept	Recessed Can 8" - Vert	CFL 26w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Fire Station #23	771	1	43	132	Corridor / Hallway - Suite / Dept	Recessed Can	I100A / N/A	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Fire Station #23	772	1	44	118	Gymnasium	2x4 Rec. Parabolic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #23	773	1	45	120	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	774	1	46	122	Electrical / Mech	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	775	1	47	137	Locker Room	4' Vapor Tight	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6

Fire Station #23	776	1	48	133	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #23	777	1	49	135	Server / Com Room	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	778	1	50	136	Corridor / Hallway	Recessed Can 8" - Vert	CFL 26w PL / CFL	9	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	9
Fire Station #23	779	1	51	136	Corridor / Hallway	Recessed Can 8" - Vert w/Battery	CFL 26w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	3
Fire Station #23	780	1	52	136	Corridor / Hallway	Recessed Can	I100A / N/A	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #23	781	1	53	136	Corridor / Hallway	Recessed Can	I100A / N/A	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #23	782	1	54	136	Corridor / Hallway	Recessed Can	I100A / N/A	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #23	783	1	55	136	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	4	DND - Existing LED Exit	4
Fire Station #23	784	1	56	136A	Corridor / Hallway - Suite / Dept	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Fire Station #23	785	1	57	139	Truck Bay	High Bay	400w MH / HID-400	9	Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	9
Fire Station #23	786	1	58	139	Truck Bay	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Fire Station #23	787	1	59	139	Truck Bay	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Fire Station #23	788	1	60	121	Mechanical Room	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	789	1	61	117	Exterior	Recessed Can	I100A / N/A	6	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Fire Station #23	790	1	69	116	Mechanical Room	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #23	791	1	62	Exterior	Exterior	LED - Track (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Fire Station #23	792	1	63	Exterior	Exterior	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Fire Station #23	793	1	64	Exterior	Exterior	Bulkhead	CFL 26w PL / CFL	4	Replace fixture with LED Wall Pack (25w / 3525lm)	4
Fire Station #23	794	1	65	Exterior	Exterior	Bulkhead	CFL 26w PL / CFL	7	Replace fixture with LED Wall Pack (25w / 3525lm)	7
Fire Station #23	795	1	67	Exterior	Exterior	Sconce	I100A / N/A	2	Relamp fixture with (2) A19 LED	2

Fire Station #23 - Exterior	796	1	68	Exterior	Exterior - Parking / Grounds	Flood	CFL 42w PL / CFL	4	Replace fixture with LED Flood (35w / 5250lm)	4
Fire Station #23 - Exterior	797	1	70	Parking and Drive	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #23 - Exterior	798	1	71	Parking and Drive	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminares (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #23 - Exterior	799	1	72	Parking and Drive	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #23 - Exterior	800	1	73	Parking and Drive	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Fire Station #30	801	1	1	122B	Office - Admin Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #30	802	1	2	122B	Office - Admin Area	Recessed Can 8" - Horz	CFL 26w PL / CFL	7	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	7
Fire Station #30	803	1	3	122B	Office - Admin Area	Recessed Can 8" - Vert	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Fire Station #30	804	1	12	122B	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #30	805	1	4	125A	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	806	1	5	125A	Office - Private	Recessed Can 8" - Horz	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	1
Fire Station #30	807	1	6	126	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	808	1	7	126	Bunk Room	Recessed Can 8"	CFL 18w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #30	809	1	8	126A	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	810	1	9	126A	Restroom - Public	LED - Recessed Can 6"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #30	811	1	10	Room	Café / Dining Area	2x4 Rec. Parabolic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #30	812	1	11	Room	Café / Dining Area	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Fire Station #30	813	1	13	Room	Café / Dining Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1



Fire Station #30	814	1	14	116	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	815	1	15	Room	Kitchen	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #30	816	1	16	Room	Kitchen	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Fire Station #30	817	1	17	6	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	818	1	18	8	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	819	1	19	10	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	820	1	20	9	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	821	1	21	7	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	822	1	22	5	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	823	1	23	3	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	824	1	24	1	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	825	1	25	2	Bunk Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	826	1	26	4	Bunk Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	827	1	27	108	Corridor / Hallway - Suite / Dept	Recessed Can 8" - Horz	CFL 26w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	6
Fire Station #30	828	1	28	108	Corridor / Hallway - Suite / Dept	Recessed Can 8"	CFL 18w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Fire Station #30	829	1	29	108	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #30	830	1	30	110	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	831	1	31	110	Office - Private	Track Head	CFL 23w Screw In / Integral CFL	2	Relamp fixture with PAR30 LED	2
Fire Station #30	832	1	32	112	Gymnasium	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	4
Fire Station #30	833	1	33	112	Custodial Closet	Recessed Can 8" - Horz	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed	1

									Can Kit (23w / 2300lm)	
Fire Station #30	834	1	34	114	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #30	835	1	35	114	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Fire Station #30	836	1	36	114	Restroom - Public	4' Strip Cove / Soffit	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	837	1	37	115	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #30	838	1	38	115	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #30	839	1	39	109	Corridor / Hallway	Recessed Can 8" - Horz	CFL 26w PL / CFL	5	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm)	5
Fire Station #30	840	1	40	109	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #30	841	1	41	117	Storage - Equipment	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	842	1	42	119A	Dayroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Fire Station #30	843	1	43	119A	Dayroom	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Fire Station #30	844	1	44	120	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	845	1	45	122A	Truck Bay	High Bay	400w MH / HID-400	9	Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	9
Fire Station #30	846	1	46	122A	Truck Bay	LED - High Bay (Retro)	LED Corn Cob / N/A	3	DND - Existing LED fixture	3
Fire Station #30	847	1	47	122A	Truck Bay	Exit Sign w/battery & lights	I20T / N/A	2	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	2
Fire Station #30	848	1	48	111	Electrical / Mech	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	850	1	50	122B	Storage - Equipment	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #30	851	1	51	105	Workroom	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #30	852	1	52	104	Laundry - Small	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #30	853	1	53	103	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Fire Station #30	854	1	54	102	Locker Room	2' Wrap	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Fire Station #30	855	1	55	Room	Mechanical Room	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #30	856	1	56	Exterior	Exterior	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	13	DND - Existing LED fixture	13
Fire Station #30	857	1	57	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #30	858	1	58	Exterior	Exterior	Wall Pack (70w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Fire Station #32	859	1	8	Lobby	Lobby Area - Main	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #32	860	1	42	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #32	861	1	9	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #32	862	1	10	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Fire Station #32	863	1	11	Dayroom	Dayroom	2x4 Rec. Acrylic	F32T8 / 2L Electronic	10	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Fire Station #32	864	1	12	It	Server / Com Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	865	1	13	Laundry	Laundry - Small	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Fire Station #32	866	1	14	Laundry	Laundry - Small	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #32	867	1	15	Mech	Mechanical Room	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	868	1	16	Kitchen	Kitchen	2x4 Rec. Acrylic	F32T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Fire Station #32	869	1	17	Kitchen	Kitchen	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	870	1	18	Kitchen	Kitchen	Jelly Jar	CFL 13w Screw in / Integral CFL	2	Relamp fixture with A19 LED	2
Fire Station #32	871	1	19	Kitchen	Kitchen	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #32	872	1	20	Restroom	Restroom - Public	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	873	1	21	Restroom	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1

Fire Station #32	874	1	22	Stor	Storage - General	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	875	1	23	Bay	Truck Bay	High Bay	400w MH / HID-400	16	Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	16
Fire Station #32	876	1	24	Bay	Truck Bay	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Fire Station #32	877	1	25	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	878	1	26	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	879	1	27	Rest	Restroom - Public	1x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	880	1	28	Rest	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #32	881	1	29	Rest	Restroom - Public	1x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	882	1	30	Rest	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Fire Station #32	883	1	31	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	884	1	32	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	885	1	33	Storage	Storage - General	1x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	886	1	34	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	887	1	35	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	888	1	36	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	889	1	37	Bunk	Bunk Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1

Fire Station #32	890	1	38	Hall	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Fire Station #32	891	1	39	Hall	Corridor / Hallway - Suite / Dept	Recessed Can 8"	75w Incandescent / N/A	7	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	7
Fire Station #32	892	1	40	Hall	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Fire Station #32	893	1	41	Hall	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Fire Station #32	895	1	1	Exterior	Exterior	LED - Canopy (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Fire Station #32	896	1	2	Exterior	Exterior	Wall Pack (70w)	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Fire Station #32	897	1	3	Exterior	Exterior	Wall Pack	150w MH / HID-150	1	Replace fixture with LED Wall Pack (35w / 4655lm)	1
Fire Station #32	898	1	4	Exterior	Exterior	Wall Pack	150w MH / HID-150	2	Replace fixture with LED Wall Pack (35w / 4655lm)	2
Fire Station #32	899	1	5	Exterior	Exterior	Decorative Wall Coach	70w MH / HID-70	1	Relamp fixture with LED CornCob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	1
Fire Station #32	900	1	6	Exterior	Exterior	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Fire Station #32	901	1	7	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	902	1	1	Traffic Lab	Workroom	4' Wrap	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
General Services Complex	903	1	2	Storage	Storage - Equipment	4' Wrap	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
General Services Complex	904	1	3	Workroom	Workroom	8' Strip	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	905	1	4	Office	Office - Private	4' Wrap	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	906	1	5	Office	Office - Private	4' Wrap	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
General Services Complex	907	1	6	Workshop	Workroom	4' Wrap	F32T8 / 2L Electronic	8	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
General Services Complex	908	1	7	Restroom	Restroom - Public	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	909	1	8	Restroom	Restroom - Public	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	910	1	9	Corridor	Corridor / Hallway	4' Strip (20w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	911	1	10	Main Workshop	Workroom	LED - High Bay (100w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
General Services Complex	912	1	11	Corridor	Corridor / Hallway	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1

General Services Complex	913	1	12	Loft	Warehouse	LED - High Bay (100w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	914	1	13	Loft	Warehouse	8' Strip	Integral LED / Integral LED Driver	9	DND - Existing LED fixture	9
General Services Complex	915	1	14	Storage	Storage - General	2' Strip	F20T12 / FL Magnetic ES	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	916	1	15	Field Operations Warehouse	Warehouse	LED - High Bay (100w)	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
General Services Complex	917	1	16	Breakroom	Break / Lounge	4' Wrap	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
General Services Complex	918	1	17	Kitchen	Kitchen	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	919	1	18	Office	Office - Private	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	920	1	19	Corridor	Corridor / Hallway	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	921	1	20	Exterior	Exterior	Wall Pack (70w)	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
General Services Complex	922	1	21	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	923	1	22	Exterior	Exterior	Wall Pack - FLD	70w MH / HID-70	3	Replace fixture with LED Wall Pack (15w / 2160lm)	3
General Services Complex	924	1	23	Field Operations Bay	Warehouse	4' Wrap	F34T12 / FL Magnetic ES	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
General Services Complex	925	1	24	101 Control Room	Conference Room	LED - Recessed Can 6" (Retro)	LED (Screw In / Plug In) / N/A	10	DND - Existing LED fixture	10
General Services Complex	926	1	25	101 Control Room	Conference Room	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
General Services Complex	927	1	26	101 Control Room	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
General Services Complex	928	1	27	103 Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	929	1	28	104 Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	930	1	29	102 Conference	Conference Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	7	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	7
General Services Complex	931	1	33	102 Conference	Conference Room	Exit Sign w/battery & lights	I20T / N/A	1	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	1
General Services Complex	932	1	30	102A Mechanical	Mechanical Room	2' Wall Bracket	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	933	1	31	106 IT	Server / Com Room	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
General Services Complex	934	1	32	105 Restroom	Restroom - Public	Ceiling Mount	60w Incandescent / N/A	1	Relamp fixture with A19 LED	1
General Services Complex	935	1	34	Exterior	Exterior	Wall Pack	CFL 26w PL / CFL	2	Replace fixture with LED Wall Pack (25w / 3525lm)	2
General Services Complex	936	1	41	Restroom	Restroom - Public	2x2 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	937	1	42	Plumbing Workshop	Workroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
General Services Complex	938	1	43	HVAC Workroom	Workroom	4' Strip (20w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	939	1	44	HVAC Workroom	Workroom	8' Strip	F96T8 / 2L Electronic	2	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	2
General Services Complex	940	1	45	Electrical Workshop	Workroom	2x4 Surf. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	941	1	46	Electrical Workshop	Workroom	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	942	1	47	Electrical Workshop	Workroom	8' Strip	F96T8 / 2L Electronic	2	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	2
General Services Complex	943	1	48	Carpentry Workshop	Workroom	8' Strip	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
General Services Complex	944	1	49	Carpentry Workshop	Workroom	8' Strip	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	945	1	50	Carpentry Workshop	Workroom	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	7	DND - Existing LED fixture	7
General Services Complex	946	1	51	Keymaster Workshop	Workroom	4' Strip (20w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	947	1	52	Keymaster Workshop	Workroom	8' Strip	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	948	1	53	Building Maintenance Bay	Warehouse	8' Strip	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
General Services Complex	949	1	54	Corridor	Vestible / Foyer	8' Strip	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	950	1	55	Hallway	Corridor / Hallway	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	951	1	56	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	952	1	57	Restroom	Restroom - Public	LED - Fan Combo (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
General Services Complex	953	1	58	Breakroom	Break / Lounge	2x2 Troffer	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
General Services Complex	954	1	59	Open Office	Office - Admin Area	2x2 Troffer	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
General Services Complex	955	1	60	Office	Office - Private	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
General Services Complex	956	1	61	Office	Office - Private	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4



General Services Complex	957	1	62	Office	Office - Private	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
General Services Complex	958	1	63	Office	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	959	1	64	Office	Office - Private	2x2 Troffer	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
General Services Complex	960	1	65	Mechanical	Mechanical Room	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	961	1	66	Painter Workshop	Workroom	4' Strip	F32T8 / 2L Electronic	5	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
General Services Complex	962	1	67	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	963	1	68	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	964	1	90	2nd Floor Workroom	Workroom	1x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	965	1	91	2nd Floor Workroom	Workroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
General Services Complex	966	1	92	2nd Floor Office	Office - Private	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	967	1	93	2nd Floor Office	Office - Private	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	968	1	94	2nd Floor Mechanical	Mechanical Room	Decorative Suspended	60w Incandescent / N/A	1	Relamp fixture with A19 LED	1
General Services Complex	969	1	95	2nd Floor Foyer	Vestible / Foyer	2x2 Surf. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
General Services Complex	970	1	96	2nd Floor Office	Office - Private	4' Wrap	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	971	1	97	2nd Floor Office	Office - Private	Recessed Can 6"	I100A / N/A	1	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	1
General Services Complex	972	1	98	2nd Floor Copy	Copy Room	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	973	1	99	Lobby	Lobby Area - Main	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	974	1	100	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
General Services Complex	975	1	101	Foyer	Vestible / Foyer	LED - Recessed Can 8"	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	976	1	102	Conference	Conference Room	LED - Recessed Can 8"	Integral LED / Integral LED Driver	9	DND - Existing LED fixture	9
General Services Complex	977	1	103	Storage	Storage - General	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	978	1	104	Office	Office - Private	4' Wrap	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
General Services Complex	979	1	105	Kitchen	Kitchen	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear	2

									Tube and Normal Power LED Driver	
General Services Complex	980	1	106	Restroom	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	981	1	107	Restroom	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	982	1	108	Office	Office - Private	4' Wrap	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
General Services Complex	983	1	109	Office	Office - Private	4' Wrap	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	984	1	110	Office	Office - Private	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	985	1	111	Office	Office - Private	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	986	1	112	Office	Office - Private	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	987	1	113	Open Office	Office - Open Cubicals	4' Wrap	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	988	1	114	Breakroom	Break / Lounge	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	989	1	115	Workroom	Office - Private	4' Wrap	F32T8 / 4L Electronic	5	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	5
General Services Complex	990	1	116	Restroom	Restroom - Public	4' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	991	1	117	Office	Office - Private	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	992	1	118	2nd Floor Office	Office - Private	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	993	1	119	2nd Floor Open Office	Office - Open Cubicals	4' Wrap	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	994	1	120	2nd Floor Open Office	Office - Open Cubicals	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
General Services Complex	995	1	121	2nd Floor Open Office	Office - Open Cubicals	4' Wrap	F32T8 / 4L Electronic	6	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	6
General Services Complex	996	1	122	2nd Floor Foyer	Vestible / Foyer	2x2 Surf. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
General Services Complex	997	1	123	Open Office	Office - Admin Area	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	998	1	124	Hallway	Corridor / Hallway	2x2 Troffer	Integral LED / Integral LED Driver	7	DND - Existing LED fixture	7
General Services Complex	999	1	125	Hallway	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2

General Services Complex	1000	1	126	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
General Services Complex	1001	1	127	Exterior	Exterior	LED - Recessed Can 4"	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	1002	1	128	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	1003	1	129	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	1004	1	35	Bay	Truck Bay	LED - High Bay (100w)	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
General Services Complex	1005	1	36	Troff	Storage - Equipment	8' Strip	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	1006	1	37	Restroom	Restroom - Public	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
General Services Complex	1007	1	38	Lab	Lab Area	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
General Services Complex	1008	1	39	Storage	Storage - General	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	1009	1	40	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
General Services Complex	1010	1	69	Parts Storage	Storage - Equipment	4' Industrial	F32T8 / 2L Electronic	10	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10
General Services Complex	1011	1	70	Parts Storage	Storage - Equipment	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
General Services Complex	1012	1	71	Office	Office - Private	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
General Services Complex	1013	1	72	Restroom	Restroom - Public	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
General Services Complex	1014	1	73	Lobby	Lobby Area - Main	4' Industrial	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
General Services Complex	1015	1	74	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
General Services Complex	1016	1	75	Breakroom	Break / Lounge	LED - Recessed Can 6"	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
General Services Complex	1017	1	76	Breakroom	Break / Lounge	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
General Services Complex	1018	1	77	Breakroom	Break / Lounge	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
General Services Complex	1019	1	78	Restroom	Restroom - Public	LED - Recessed Can 6"	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	1020	1	79	Restroom	Restroom - Public	LED - Recessed Can 6"	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
General Services Complex	1021	1	80	Training	Training Room	LED - Recessed Can 8"	Integral LED / Integral LED Driver	15	DND - Existing LED fixture	15
General Services Complex	1022	1	81	Training	Training Room	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2

General Services Complex	1023	1	82	Stairway	Stairwell - Interior	LED - Recessed Can 6"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
General Services Complex	1024	1	83	Maintenance Bay	Maintenance Shop	LED - High Bay (100w)	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
General Services Complex	1025	1	84	Maintenance Bay	Maintenance Shop	LED - High Bay (100w)	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
General Services Complex	1026	1	85	Maintenance Bay	Maintenance Shop	8' Strip	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
General Services Complex	1027	1	86	Tire Storage	Storage - Equipment	4' Strip (20w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
General Services Complex	1028	1	87	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	1029	1	88	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
General Services Complex	1030	1	89	Exterior	Exterior	Wall Pack	175w MH / HID-175	1	Replace fixture with LED Wall Pack (25w / 3525lm)	1
Historical Courthouse	1031	1	1	26	Break / Lounge	Ceiling Drum	CFL 13w PL / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1032	1	2	27	Storage - General	Decorative Surface	CFL 32w / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1033	1	3	25	Conference Room	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Historical Courthouse	1034	1	4	25	Conference Room	LED - Track (Retro)	LED (Screw In / Plug In) / Integral LED Driver	4	DND - Existing LED fixture	4
Historical Courthouse	1035	1	5	27	Storage - General	Decorative Surface	CFL 32w / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1036	1	6	23	Office - Private	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Historical Courthouse	1037	1	7	23	Office - Private	LED - Track (Retro)	LED (Screw In / Plug In) / Integral LED Driver	7	DND - Existing LED fixture	7
Historical Courthouse	1038	1	8	22	Office - Private	Decorative Suspended	60w Incandescent / N/A	1	DND - Specialty/Decorative Lighting	1
Historical Courthouse	1039	1	9	17	Restroom - Public	Ceiling Drum	CFL 13w PL / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1040	1	10	16A	Office - Private	Decorative Suspended	60w Incandescent / N/A	1	DND - Specialty/Decorative Lighting	1
Historical Courthouse	1041	1	11	16	Office - Private	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Historical Courthouse	1042	1	12	15	Copy Room	Decorative Suspended	60w Incandescent / N/A	1	DND - Specialty/Decorative Lighting	1
Historical Courthouse	1043	1	13	19	Storage - General	Decorative Surface	CFL 32w / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1044	1	14	14	Office - Private	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Historical Courthouse	1045	1	15	13	Storage - General	Decorative Surface	CFL 32w / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1046	1	16	20	Custodial Closet	Decorative Surface	CFL 32w / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1047	1	17	21	Corridor / Hallway	Ceiling Drum	CFL 13w PL / CFL	1	Replace fixture with LED Flush Mount	1
Historical Courthouse	1048	1	18	21	Corridor / Hallway	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Historical Courthouse	1049	1	19	21	Corridor / Hallway	LED - Track (Retro)	LED (Screw In / Plug In) / Integral LED Driver	5	DND - Existing LED fixture	5

Historical Courthouse	1050	1	20	21	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Historical Courthouse	1051	1	21	21	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Hobe Sound Civic Center - Community Center	1052	1	1	Banquet Room	Café / Dining Area	4' Wrap	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Hobe Sound Civic Center - Community Center	1053	1	2	Banquet Room	Café / Dining Area	Exit Sign w/battery & lights	I20T / N/A	2	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	2
Hobe Sound Civic Center - Community Center	1054	1	3	Banquet Room	Café / Dining Area	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Hobe Sound Civic Center - Community Center	1055	1	4	Office	Office - Private	4' Wrap	F34T12 / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hobe Sound Civic Center - Community Center	1056	1	5	Office	Office - Private	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hobe Sound Civic Center - Community Center	1057	1	6	Office	Office - Private	4' Wrap	F34T12 / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hobe Sound Civic Center - Community Center	1058	1	7	Office	Office - Private	4' Wrap	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Hobe Sound Civic Center - Community Center	1059	1	8	Storage	Storage - General	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hobe Sound Civic Center - Community Center	1060	1	9	Kitchen	Kitchen	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Hobe Sound Civic Center - Community Center	1061	1	10	Kitchen	Kitchen	Exit Sign w/battery & lights	I20T / N/A	1	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	1
Hobe Sound Civic Center - Community Center	1062	1	11	Restroom	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Hobe Sound Civic Center - Community Center	1063	1	12	Restroom	Restroom - Public	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Hobe Sound Civic Center - Community Center	1064	1	13	Restroom	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Hobe Sound Civic Center - Community Center	1065	1	14	Restroom	Restroom - Public	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Hobe Sound Civic Center - Community Center - Exterior	1066	1	15	Exterior	Exterior - Parking / Grounds	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Hobe Sound Civic Center - Community Center	1067	1	16	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Hobe Sound Civic Center - Community Center	1068	1	17	Exterior	Exterior	LED - Wall Sconce (SCPS)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1

Hobe Sound Civic Center - Community Center	1069	1	18	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Hoke Library	1070	1	1	Room	Vestible / Foyer	Wall UpLight	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Hoke Library	1071	1	5	Room	Vestible / Foyer	Recessed Can 8" - Vert	CFL 26w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Hoke Library	1072	1	7	Room	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Hoke Library	1073	1	2	Room	Restroom - Public	LED - Surface Drum	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Hoke Library	1074	1	3	Room	Restroom - Public	4' Strip Cove / Soffit	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hoke Library	1075	1	4	Room	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Hoke Library	1076	1	6	Room	Custodial Closet	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hoke Library	1077	1	8	Room	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Hoke Library	1078	1	9	Room	Vestible / Foyer	Recessed Can 8" - Vert	CFL 18w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Hoke Library	1079	1	10	Room	Vestible / Foyer	LED - Surface Drum	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Hoke Library	1080	1	11	Room	Restroom - Public	LED - Surface Drum	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Hoke Library	1081	1	12	Room	Restroom - Public	4' Strip Cove / Soffit	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hoke Library	1082	1	13	Room	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Hoke Library	1083	1	14	Community Room	Conference Room	2x4 Rec. Parabolic	F32T8 / 3L Electronic	14	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	14
Hoke Library	1084	1	15	Community Room	Conference Room	2x4 Rec. Parabolic w/Battery	4' TLED T8 / N/A	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Hoke Library	1085	1	16	Community Room	Conference Room	2x4 Rec. Parabolic	4' TLED T8 / N/A	5	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	5
Hoke Library	1086	1	17	Community Room	Conference Room	Modular Track	MR16 / N/A	12	Relamp fixture with LED MR16 (Verify base & optics)	12
Hoke Library	1087	1	18	Community Room	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Hoke Library	1088	1	19	Community Room	Conference Room	Recessed Can 8" - Vert	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Hoke Library	1089	1	20	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	3
Hoke Library	1090	1	21	Children's	Library	2x4 Rec. Parabolic	F32T8 / 3L Electronic	28	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	28
Hoke Library	1091	1	22	Children's	Library	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency	1

									Battery (30w / 4110lm)	
Hoke Library	1092	1	23	Children's	Library	2x4 Rec. Parabolic	4' TLED T8 / N/A	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Hoke Library	1093	1	24	Room	Workroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	9	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	9
Hoke Library	1094	1	25	Room	Workroom	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Hoke Library	1095	1	26	Room	Workroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Hoke Library	1096	1	27	Room	Break / Lounge	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Hoke Library	1097	1	28	Room	Restroom - Public	LED - Recessed Can 6"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Hoke Library	1098	1	29	Room	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Hoke Library	1099	1	30	Room	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Hoke Library	1100	1	32	Room	Library	2x4 Rec. Parabolic	F32T8 / 3L Electronic	3	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	3
Hoke Library	1101	1	33	Room	Classroom - Study Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Hoke Library	1102	1	34	Room	Classroom - Study Room	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Hoke Library	1103	1	35	Room	Library	Wall UpLight	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Hoke Library	1104	1	36	Room	Library	Wall Pack - FCT - UpLight	175w MH / HID-175	4	Relamp fixture with LED CornCob lamp (45w / 6300lm) - remove existing ballast and direct wire socket	4
Hoke Library	1105	1	37	Room	Library	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	4
Hoke Library	1106	1	38	Room	Library	LED - Recessed Can 10"	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Hoke Library	1107	1	39	Room	Library	LED - Recessed Can 10" w/Battery	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Hoke Library	1108	1	40	Room	Library	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Hoke Library	1109	1	41	Room	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Hoke Library	1110	1	42	Room	Library	Wall UpLight	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
Hoke Library	1111	1	43	Room	Library	LED - Recessed Can 10"	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Hoke Library	1112	1	44	Room	Library	LED - Recessed Can 10" w/Battery	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Hoke Library	1113	1	51	Room	Library	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1



Hoke Library	1114	1	45	Room	Library	2x4 Rec. Parabolic	F32T8 / 3L Electronic	30	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	30
Hoke Library	1115	1	46	Room	Library	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	2
Hoke Library	1116	1	47	Room	Library	2x4 Rec. Parabolic	4' TLED T8 / N/A	3	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	3
Hoke Library	1117	1	48	Room	Library	Decorative Globe	25w Incandescent / N/A	4	DND - Specialty/Decorative Lighting	4
Hoke Library	1118	1	49	Room	Library	LED - Recessed Can 10"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Hoke Library	1119	1	50	Room	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Hoke Library	1120	1	52	Room	Library	2x4 Rec. Parabolic	F32T8 / 3L Electronic	28	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	28
Hoke Library	1121	1	53	Room	Library	2x4 Rec. Parabolic w/Battery	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	2
Hoke Library	1122	1	54	Room	Library	2x4 Rec. Parabolic	4' TLED T8 / N/A	5	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	5
Hoke Library	1123	1	56	Room	Library	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Hoke Library	1124	1	57	Room	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Hoke Library	1125	1	58	Room	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Hoke Library	1126	1	59	Room	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Hoke Library	1127	1	60	Room	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Hoke Library	1128	1	61	Exterior	Exterior	Recessed Can 6" - Vert	CFL 26w PL / CFL	6	Retrofit fixture with 6" LED Recessed Can Kit (13w / 1250lm)	6
Hoke Library	1129	1	62	Exterior	Exterior	Recessed Can 6" - Vert	CFL 18w PL / CFL	6	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	6
Hoke Library	1130	1	63	Exterior	Exterior	Recessed Can 8" - Vert	CFL 32w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Hoke Library	1131	1	64	Exterior	Exterior	Surface Mount	CFL 13w PL / CFL	3	Replace fixture with LED Wall Brick (20w / 2700lm) - White	3
Hoke Library	1132	1	65	Exterior	Exterior	Wall Pack	175w MH / HID-175	3	Replace fixture with LED Wall Pack (25w / 3525lm)	3
Hoke Library	1133	1	66	Flagpole	Exterior	Sconce	I100A / N/A	2	Relamp fixture with (2) A19 LED	2
Hoke Library - Exterior	1134	1	67	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1

Hoke Library - Exterior	1135	1	68	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Hoke Library - Exterior	1136	1	69	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Hoke Library - Exterior	1137	1	70	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Hoke Library - Exterior	1138	1	71	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Hoke Library - Exterior	1139	1	72	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Hoke Library - Exterior	1140	1	73	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Hoke Library - Exterior	1141	1	74	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Hoke Library - Exterior	1142	1	75	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Indian Riverside Park - Children's Museum	1143	1	2	Ship Area	Warehouse	4' Strip	4' TLED T8 / 2L Electronic	16	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	16
Indian Riverside Park - Children's Museum	1144	1	6	Ship Area	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Indian Riverside Park - Children's Museum	1145	1	7	Ship Area	Warehouse	Emergency Egress WP	Incandescent / N/A	3	DND - Existing Emergency Egress	3
Indian Riverside Park - Children's Museum	1146	1	8	Ship Area	Warehouse	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Indian Riverside Park - Children's Museum	1147	1	3	Pirate Ship-2nd Level	Multi Purpose	LED - Track (Retro)	LED (Screw In / Plug In) / Integral LED Driver	19	DND - Existing LED fixture	19
Indian Riverside Park -	1148	1	4	Pirate Ship-2nd Level	Multi Purpose	LED - Decorative	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1

Children's Museum										
Indian Riverside Park - Children's Museum	1149	1	5	Pirate Ship-2nd Level	Multi Purpose	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indian Riverside Park - Children's Museum	1150	1	9	Pirate Ship-1st Level	Multi Purpose	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	24	DND - Existing LED fixture	24
Indian Riverside Park - Children's Museum	1151	1	10	Pirate Ship-1st Level	Multi Purpose	Exit Sign w/battery & lights	I20T / N/A	2	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	2
Indian Riverside Park - Children's Museum	1152	1	11	Storage	Storage - General	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Indian Riverside Park - Children's Museum	1153	1	12	Multipurpose	Multi Purpose	4' Wrap	4' TLED T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Indian Riverside Park - Children's Museum	1154	1	13	Multipurpose	Multi Purpose	Exit Sign w/battery	Integral LED / Integral LED Driver	4	DND - Existing LED Exit	4
Indian Riverside Park - Children's Museum	1155	1	14	Storage	Storage - General	2x2 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Indian Riverside Park - Children's Museum	1156	1	15	Storage	Storage - General	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Indian Riverside Park - Children's Museum	1157	1	16	Storage	Storage - General	2' Wrap	2' TLED / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Indian Riverside Park - Children's Museum	1158	1	17	Storage	Storage - General	2' Wrap	2' TLED / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Indian Riverside Park - Children's Museum	1159	1	18	Storage	Storage - General	2' Wrap	2' TLED / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Indian Riverside Park - Children's Museum	1160	1	19	Lobby	Lobby Area - Main	4' Direct/Indirect	4' TLED T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Indian Riverside Park - Children's Museum	1161	1	20	Lobby	Lobby Area - Main	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Indian Riverside Park - Children's Museum	1162	1	21	Lobby	Lobby Area - Main	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	3	DND - Existing LED fixture	3
Indian Riverside Park -	1163	1	22	Lobby	Lobby Area - Main	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2

Children's Museum										
Indian Riverside Park - Children's Museum	1164	1	23	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Indian Riverside Park - Children's Museum	1165	1	24	City Area	Warehouse	4' Direct/Indirect	4' TLED T8 / 2L Electronic	31	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	31
Indian Riverside Park - Children's Museum	1166	1	25	City Area	Warehouse	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indian Riverside Park - Children's Museum	1167	1	26	City Area	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Indian Riverside Park - Children's Museum	1168	1	27	City Area	Warehouse	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Indian Riverside Park - Children's Museum	1169	1	28	Vestibule	Vestible / Foyer	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Indian Riverside Park - Children's Museum	1170	1	29	Vestibule	Vestible / Foyer	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Indian Riverside Park - Children's Museum	1171	1	30	Restroom	Restroom - Public	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	5	DND - Existing LED fixture	5
Indian Riverside Park - Children's Museum	1172	1	31	Restroom	Restroom - Public	2' Vanity	F17T8 / 2L Electronic	2	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	2
Indian Riverside Park - Children's Museum	1173	1	32	Restroom	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indian Riverside Park - Children's Museum	1174	1	33	Restroom	Restroom - Public	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	10	DND - Existing LED fixture	10
Indian Riverside Park - Children's Museum	1175	1	34	Restroom	Restroom - Public	2' Vanity	F17T8 / 2L Electronic	2	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	2
Indian Riverside Park - Children's Museum	1176	1	35	Restroom	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indian Riverside Park - Children's Museum	1177	1	36	Electrical	Electrical / Mech	4' Wrap	4' TLED T8 / 2L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indian Riverside Park -	1178	1	37	Electrical Room-Mezzanine	Electrical / Mech	4' Wrap	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2

Children's Museum										
Indian Riverside Park - Children's Museum	1179	1	38	Laundry	Laundry - Small	4' Wrap	4' TLED T8 / 2L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indian Riverside Park - Children's Museum	1180	1	39	Simulation Room	Multi Purpose	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indian Riverside Park - Children's Museum	1181	1	40	Storage	Storage - General	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
Indian Riverside Park - Children's Museum	1182	1	41	Storage	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indian Riverside Park - Children's Museum	1183	1	42	Open Office	Office - Open Cubicals	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	10	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Indian Riverside Park - Children's Museum	1184	1	43	Office	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indian Riverside Park - Children's Museum	1185	1	44	Office	Office - Private	LED - Ceiling Drum	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Indian Riverside Park - Children's Museum	1186	1	45	Hallway	Corridor / Hallway - Suite / Dept	2' Wrap	2' TLED / 2L Electronic	5	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	5
Indian Riverside Park - Children's Museum	1187	1	46	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indian Riverside Park - Children's Museum	1188	1	47	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indian Riverside Park - Children's Museum	1189	1	48	Hallway	Corridor / Hallway - Suite / Dept	2' Wrap	2' TLED / 2L Electronic	5	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	5
Indian Riverside Park - Children's Museum	1190	1	49	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indian Riverside Park - Children's Museum	1191	1	50	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indian Riverside Park - Children's Museum	1192	1	51	Exterior	Exterior	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Indian Riverside Park -	1193	1	52	Exterior	Exterior	Wall Pack	150w MH / HID-150	6	Replace fixture with LED Wall Pack (35w / 4655lm)	6

Children's Museum										
Indian Riverside Park - Children's Museum	1194	1	53	Exterior	Exterior	LED - Wall Pack (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1
Indiantown Health Department	1195	1	1	36	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1196	1	2	36	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1197	1	3	38A	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1198	1	4	38B	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1199	1	5	39	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	5	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Indiantown Health Department	1200	1	6	Lobby	Lobby Area - Main	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Indiantown Health Department	1201	1	7	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indiantown Health Department	1202	1	8	2	Waiting Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1203	1	9	3	Waiting Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1204	1	10	Office	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1205	1	11	4	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1206	1	12	4	Exam / Treatment	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1207	1	13	38B	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1208	1	14	9	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Indiantown Health Department	1209	1	15	9	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Indiantown Health Department	1210	1	16	9	Office - Admin Area	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1211	1	36	9	Office - Admin Area	2x2 Rec. Acrylic	F34T12/U / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and	1

									Normal Power LED Driver	
Indiantown Health Department	1212	1	17	44	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1213	1	18	44	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1214	1	19	Entrance	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1215	1	20	Entrance	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indiantown Health Department	1216	1	21	Lobby	Lobby Area - Main	4' Wall Bracket	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1217	1	22	Lobby	Lobby Area - Main	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1218	1	23	2	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1219	1	24	2	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1220	1	25	Workroom	Workroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Indiantown Health Department	1221	1	26	Workroom	Workroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indiantown Health Department	1222	1	27	4	Custodial Closet	2x4 Rec. Acrylic	F34T12 / FL Magnetic ES	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1223	1	28	5	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1224	1	29	6	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1225	1	30	7	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1226	1	31	13	Restroom - Public	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1227	1	32	13	Restroom - Public	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1228	1	33	11	Custodial Closet	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Indiantown Health Department	1229	1	34	Laboratory	Lab Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Indiantown Health Department	1230	1	35	Laboratory	Lab Area	2x4 Rec. Acrylic	F34T12 / FL Magnetic ES	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1



Indiantown Health Department	1231	1	37	Lobby	Lobby Area - Main	2x4 Rec. Acrylic	F32T8 / 4L Electronic	5	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Indiantown Health Department	1232	1	38	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Indiantown Health Department	1233	1	39	Lobby	Lobby Area - Main	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1234	1	40	18	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Indiantown Health Department	1235	1	41	19	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1236	1	42	20	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1237	1	43	21	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1238	1	44	22	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1239	1	45	23	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1240	1	46	24	Exam / Treatment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1241	1	47	31	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Indiantown Health Department	1242	1	48	34	Electrical / Mech	Sconce	CFL 13w Screw in / Integral CFL	1	Relamp fixture with A19 LED	1
Indiantown Health Department	1243	1	49	32	Mechanical Room	4' Wrap	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Indiantown Health Department	1244	1	50	30	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1245	1	51	26	Mechanical Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1246	1	52	27	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1247	1	53	29	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1248	1	54	Room	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 4L Electronic	5	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Indiantown Health Department	1249	1	55	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Indiantown Health Department	1250	1	56	Room	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Indiantown Health Department	1251	1	57	Room	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indiantown Health Department	1252	1	58	Room	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1253	1	59	Room	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Indiantown Health Department	1254	1	60	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1255	1	61	Room	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Indiantown Health Department	1256	1	63	Room	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1257	1	64	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F34T12/U / FL Magnetic ES	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1258	1	65	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Indiantown Health Department	1259	1	66	Room	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Indiantown Health Department	1260	1	67	Room	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1261	1	68	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F34T12/U / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1262	1	69	Room	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1263	1	70	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1264	1	71	Room	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Indiantown Health Department	1265	1	72	Room	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1266	1	73	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F34T12/U / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1267	1	91	Exterior	Exterior	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Indiantown Health Department	1268	1	92	Exterior	Exterior	LED - Flood (20w)	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Indiantown Health Department	1269	1	93	Exterior	Exterior	LED - Flood (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Indiantown Health Department	1270	1	74	Storage	Storage - General	4' Wrap	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5

Indiantown Health Department	1271	1	75	Storage	Storage - General	4' Wrap	F34T12 / FL Magnetic ES	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1272	1	76	Storage	Storage - General	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Indiantown Health Department	1273	1	77	Storage	Storage - General	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indiantown Health Department	1274	1	78	33	Storage - General	4' Wrap	F34T12 / FL Magnetic ES	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1275	1	79	49	Office - Private	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1277	1	81	47	Office - Private	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1279	1	83	45	Office - Private	4' Wrap	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1280	1	84	Hallway	Corridor / Hallway - Suite / Dept	4' Wrap	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Indiantown Health Department	1281	1	85	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1282	1	86	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indiantown Health Department	1283	1	87	Stairway	Stairwell - Interior	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1284	1	88	Stairway	Stairwell - Interior	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Indiantown Health Department	1285	1	89	Stairway	Stairwell - Interior	2x2 Surf. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Indiantown Health Department	1286	1	90	Stairway	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Indiantown Health Department - Exterior	1287	1	94	Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Indiantown Health Department - Exterior	1288	1	95	Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Indiantown Health Department - Exterior	1289	1	96	Parking	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Jensen Beach Community Center	1290	1	2	Lobby	Lobby Area - Main	Recessed Can 8" - Vert	CFL 26w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Jensen Beach Community Center	1291	1	3	Lobby	Lobby Area - Main	Recessed Can 8" - Vert w/Battery	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed	4

									Can Kit (17w / 872lm) w/battery	
Jensen Beach Community Center	1292	1	4	Lobby	Lobby Area - Main	Decorative Chandelier	CFL 26w PL / CFL	2	DND - Specialty/Decorative Lighting	2
Jensen Beach Community Center	1293	1	5	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Jensen Beach Community Center	1294	1	6	Auditorium	Auditorium	Decorative Chandelier	CFL 26w PL / CFL	10	DND - Specialty/Decorative Lighting	10
Jensen Beach Community Center	1295	1	7	Auditorium	Auditorium	Deco Sconce	CFL 26w PL / CFL	14	DND - Specialty/Decorative Lighting	14
Jensen Beach Community Center	1296	1	8	Auditorium	Auditorium	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Jensen Beach Community Center	1297	1	11	Storage	Storage - General	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Jensen Beach Community Center	1298	1	12	Vestibule	Vestible / Foyer	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Jensen Beach Community Center	1299	1	13	Vestibule	Vestible / Foyer	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Jensen Beach Community Center	1300	1	14	Vestibule	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Jensen Beach Community Center	1301	1	15	Vestibule	Vestible / Foyer	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Jensen Beach Community Center	1302	1	16	Vestibule	Vestible / Foyer	Recessed Can 8" - Vert w/Battery	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	1
Jensen Beach Community Center	1303	1	17	Restroom	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Jensen Beach Community Center	1304	1	18	Restroom	Restroom - Public	Recessed Can 8" - Vert	CFL 26w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Jensen Beach Community Center	1305	1	19	Restroom	Restroom - Public	Recessed Can 8" - Vert w/Battery	CFL 26w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	2
Jensen Beach Community Center	1306	1	20	Hallway	Corridor / Hallway	2x2 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Jensen Beach Community Center	1307	1	21	Hallway	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Jensen Beach Community Center	1308	1	22	Office	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Jensen Beach Community Center	1309	1	23	Office	Office - Private	2x2 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Jensen Beach Community Center	1310	1	24	Office	Office - Private	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Jensen Beach Community Center	1311	1	25	109B	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Jensen Beach Community Center	1312	1	26	109A	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1

Jensen Beach Community Center	1313	1	27	111	Custodial Closet	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Jensen Beach Community Center	1314	1	28	108	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Jensen Beach Community Center	1315	1	29	Open Office	Office - Admin Area	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Jensen Beach Community Center	1316	1	30	Mechanical	Mechanical Room	Keyless	CFL 55w / N/A	1	Relamp fixture with A19 LED	1
Jensen Beach Community Center	1317	1	31	Mechanical	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Jensen Beach Community Center	1318	1	1	Exterior	Exterior	LED - Canopy (20w)	Integral LED / Integral LED Driver	18	DND - Existing LED fixture	18
Jensen Beach Community Center	1319	1	9	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	18	DND - Existing LED fixture	18
Jensen Beach Community Center	1320	1	10	Exterior	Exterior	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Jensen Beach Community Center	1321	1	32	Exterior	Exterior	3' Decorative Sconce	F25T8 / 2L Electronic	9	Retrofit fixture with (2) 3' T8 LED Linear Tube and Normal Power LED Driver	9
Lahti Library	1322	1	11	102	Lobby Area - Main	4' Strip	Integral LED / Integral LED Driver	9	DND - Existing LED fixture	9
Lahti Library	1323	1	12	102	Lobby Area - Main	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	10	DND - Existing LED fixture	10
Lahti Library	1324	1	13	102	Lobby Area - Main	Recessed Can 4"	MR16 / N/A	3	Relamp fixture with LED MR16 (Verify base & optics)	3
Lahti Library	1325	1	14	102	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Lahti Library	1326	1	15	130	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	14	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	14
Lahti Library	1327	1	16	130	Library	2x2 Rec. Parabolic w/Battery	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit w/Emergency Battery (24w / 3168lm)	2
Lahti Library	1328	1	17	122	Workroom	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	12	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	12
Lahti Library	1329	1	18	122	Workroom	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Lahti Library	1330	1	19	122	Workroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Lahti Library	1331	1	20	129	Custodial Closet	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Lahti Library	1332	1	21	128	Mechanical Room	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Lahti Library	1333	1	22	127	Mechanical Room	4' Wall Bracket	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Lahti Library	1334	1	23	126	Storage - General	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	5	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	5

Lahti Library	1335	1	24	126	Storage - General	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Lahti Library	1336	1	25	126	Storage - General	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Lahti Library	1337	1	26	125	Server / Com Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Lahti Library	1338	1	27	124	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Lahti Library	1339	1	28	124	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Lahti Library	1340	1	29	123	Break / Lounge	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	4	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	4
Lahti Library	1341	1	30	117	Storage - General	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Lahti Library	1342	1	31	120	Storage - General	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	1	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	1
Lahti Library	1343	1	32	121	Office - Private	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Lahti Library	1344	1	33	114	Library	2x2 Troffer	Integral LED / Integral LED Driver	23	DND - Existing LED fixture	23
Lahti Library	1345	1	34	114	Library	2x2 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Lahti Library	1346	1	35	114	Library	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Lahti Library	1347	1	36	114	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Lahti Library	1348	1	37	119	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Lahti Library	1349	1	38	112	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	4
Lahti Library	1350	1	39	113	Conference Room	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Lahti Library	1351	1	40	111	Conference Room	2x2 Troffer	Integral LED / Integral LED Driver	34	DND - Existing LED fixture	34
Lahti Library	1352	1	41	111	Conference Room	Emergency Egress WP	Incandescent / N/A	3	DND - Existing Emergency Egress	3
Lahti Library	1353	1	42	111	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Lahti Library	1354	1	43	111	Conference Room	2x2 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Lahti Library	1355	1	44	110	Kitchen	2x2 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Lahti Library	1356	1	45	109A	Vestible / Foyer	2x2 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Lahti Library	1357	1	46	109A	Vestible / Foyer	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Lahti Library	1358	1	47	107	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Lahti Library	1359	1	48	107	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2

Lahti Library	1360	1	49	106	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Lahti Library	1361	1	50	106	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Lahti Library	1362	1	51	103	Office - Admin Area	4' Strip	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Lahti Library	1363	1	52	103	Office - Admin Area	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Lahti Library	1364	1	53	103	Office - Admin Area	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	2	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	2
Lahti Library	1365	1	54	105	Conference Room	2x2 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Lahti Library	1366	1	55	104/108/109	Library	4' Direct/Indirect	F32T8 / 2L Electronic	20	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	20
Lahti Library	1367	1	56	104/108/109	Library	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Lahti Library	1368	1	57	104/108/109	Library	LED - Wall Sconce (SCPS)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Lahti Library - Exterior	1369	1	5	Exterior	Exterior - Parking / Grounds	LED - Bollard	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Lahti Library	1370	1	6	Exterior	Exterior	LED - Flood (60w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Lahti Library	1371	1	7	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Lahti Library	1372	1	8	Exterior	Exterior	LED - Flood (60w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Lahti Library	1373	1	9	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Lahti Library	1374	1	10	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Lahti Library - Exterior	1375	1	1	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Lahti Library - Exterior	1376	1	2	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Lahti Library - Exterior	1377	1	3	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Lahti Library - Exterior	1378	1	4	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Langford Park	1379	1	38	Concession	Food Services Areas	4' Wrap	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear	3



									Tube and Normal Power LED Driver	
Langford Park	1380	1	39	Storage	Storage - Equipment	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1381	1	40	Electrical	Electrical / Mech	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Langford Park	1382	1	41	Restroom	Restroom - Public	4' Vapor Tight (20w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Langford Park	1383	1	42	Mechanical	Mechanical Room	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Langford Park	1384	1	43	Restroom	Restroom - Public	4' Vapor Tight (20w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Langford Park	1385	1	44	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Langford Park	1386	1	1	Lobby	Lobby Area - Main	Recessed Can 10" - Horz w/battery	CFL 26w PL / CFL	14	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	14
Langford Park	1387	1	2	Lobby	Lobby Area - Main	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Langford Park	1388	1	3	Meeting Room	Conference Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	12	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Langford Park	1389	1	4	Meeting Room	Conference Room	Exit Sign w/battery & lights	I20T / N/A	1	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	1
Langford Park	1390	1	5	Storage	Storage - General	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Langford Park	1391	1	6	Storage	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Langford Park	1392	1	7	Restroom	Restroom - Public	1x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1393	1	8	Restroom	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1394	1	9	Janitor	Custodial Closet	2' Strip	F20T12 / FL Magnetic ES	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Langford Park	1395	1	10	Restroom	Restroom - Public	1x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1396	1	11	Restroom	Restroom - Public	4' Vanity	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1397	1	12	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1398	1	14	Office	Office - Private	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Langford Park	1399	1	13	Storage	Storage - General	4' Strip	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Langford Park	1400	1	15	Banquet	Café / Dining Area	2x4 Rec. Acrylic	F32T8 / 2L Electronic	62	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	62
Langford Park	1401	1	16	Banquet	Café / Dining Area	Recessed Can 6"	60w Incandescent / N/A	8	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	8
Langford Park	1402	1	17	Banquet	Café / Dining Area	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Langford Park	1403	1	18	Banquet	Café / Dining Area	Exit Sign w/battery & lights	I20T / N/A	1	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	1
Langford Park	1404	1	19	Banquet	Café / Dining Area	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Langford Park	1405	1	20	Storage	Storage - General	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1406	1	21	Storage	Storage - General	4' Strip	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1407	1	22	Vestibule	Vestible / Foyer	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1408	1	23	Vestibule	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Langford Park	1409	1	24	Office	Office - Private	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Langford Park	1410	1	25	Office	Office - Private	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Langford Park	1411	1	26	Mechanical	Mechanical Room	4' Strip	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Langford Park	1412	1	27	Mechanical	Mechanical Room	4' Strip	F34T12 / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Langford Park	1413	1	28	Kitchen	Kitchen	2x4 Rec. Acrylic	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Langford Park	1414	1	29	Serving	Food Services Areas	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Langford Park	1415	1	30	Storage	Storage - General	4' Strip	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Langford Park	1416	1	31	Storage	Storage - General	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Langford Park	1417	1	32	Meeting Room	Conference Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	12	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Langford Park	1418	1	33	Meeting Room	Conference Room	Exit Sign w/battery & lights	I20T / N/A	1	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	1
Langford Park	1419	1	34	Exterior	Exterior	Recessed Can 8" - Horz	CFL 26w PL / CFL	3	Retrofit fixture with 8" LED Recessed	3

									Can Kit (23w / 2300lm)	
Langford Park	1420	1	35	Exterior	Exterior	Recessed Can 8" - Vert	CFL 26w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Langford Park	1421	1	36	Exterior	Exterior	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	8	DND - Existing LED fixture	8
Langford Park	1422	1	37	Exterior	Exterior	Sconce	I100A / N/A	2	Relamp fixture with (2) A19 LED	2
Martin County Landfill	1423	1	4	Conference	Conference Room	4' Direct/Indirect	4' TLED T8 / 2L Electronic	18	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	18
Martin County Landfill	1424	1	5	Conference	Conference Room	Decorative Sconce	CFL 32w PL / CFL	2	DND - Specialty/Decorative Lighting	2
Martin County Landfill	1425	1	6	Conference	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Landfill	1426	1	7	Conference	Conference Room	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Martin County Landfill	1427	1	8	Kitchen	Kitchen	LED - Recessed Can 6" (Retro)	LED (Screw In / Plug In) / N/A	10	DND - Existing LED fixture	10
Martin County Landfill	1428	1	9	Kitchen	Kitchen	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Landfill	1429	1	10	Kitchen	Kitchen	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Landfill	1430	1	15	Kitchen	Kitchen	4' Wall Bracket	F32T8 / 2L Electronic	5	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Martin County Landfill	1431	1	11	Mechanical	Mechanical Room	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Landfill	1432	1	12	It	Server / Com Room	2' Wrap	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Landfill	1433	1	13	Restroom	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Landfill	1434	1	14	Restroom	Restroom - Public	Recessed Can 8"	I100A / N/A	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Martin County Landfill	1435	1	16	Janitor	Custodial Closet	2' Wrap	F17T8 / 2L Electronic	1	Retrofit fixture with (2) 2' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Landfill	1436	1	17	Restroom	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Landfill	1437	1	18	Restroom	Restroom - Public	Recessed Can 8"	I100A / N/A	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Martin County Landfill	1438	1	19	Corridor	Corridor / Hallway - Suite / Dept	2x4 Rec. Parabolic	4' TLED T8 / N/A	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Landfill	1439	1	20	Office	Office - Private	2x4 Rec. Parabolic	4' TLED T8 / N/A	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Landfill	1440	1	21	Open Office	Office - Admin Area	2x4 Rec. Parabolic	4' TLED T8 / N/A	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4

Martin County Landfill	1441	1	22	Stairway	Stairwell - Interior	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Landfill	1442	1	23	Stairway	Stairwell - Interior	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Landfill	1443	1	24	Stairway	Stairwell - Interior	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Landfill	1444	1	25	Stairway	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Landfill	1445	1	26	Fire Storage	Storage - Equipment	4' Vapor Tight	F32T8 / 2L Electronic	20	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	20
Martin County Landfill	1446	1	27	Fire Storage	Storage - Equipment	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Martin County Landfill	1447	1	28	Fire Storage	Storage - Equipment	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Martin County Landfill	1448	1	35	Exterior	Exterior	LED - Canopy (30w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Martin County Landfill	1449	1	1	Transfer Bay	Warehouse	LED - High Bay (100w)	Integral LED / Integral LED Driver	25	DND - Existing LED fixture	25
Martin County Landfill	1450	1	2	Transfer Bay	Warehouse	Emergency Egress WP	Incandescent / N/A	12	DND - Existing Emergency Egress	12
Martin County Landfill	1451	1	3	Transfer Bay	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Landfill	1452	1	29	Transfer Tunnel	Truck Bay	Wall Pack (55w)	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Martin County Landfill	1453	1	30	Transfer Tunnel	Truck Bay	4' Vapor Tight	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Martin County Landfill	1454	1	31	Transfer Tunnel	Truck Bay	Emergency Egress WP	Incandescent / N/A	4	DND - Existing Emergency Egress	4
Martin County Landfill	1455	1	32	Generator	Generator Room	4' Vapor Tight	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Landfill	1456	1	34	Generator	Generator Room	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Landfill	1457	1	33	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	13	DND - Existing LED fixture	13
Martin County Landfill	1458	1	36	Maintenance Bay 2	Maintenance Shop	8' Industrial	F96T8 / 2L Electronic	6	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	6
Martin County Landfill	1459	1	37	Maintenance Bay 2	Maintenance Shop	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Landfill	1460	1	38	Maintenance Bay 2B	Maintenance Shop	8' Industrial	F96T8 / 2L Electronic	18	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	18
Martin County Landfill	1461	1	39	Maintenance Bay 2B	Maintenance Shop	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Martin County Landfill	1462	1	40	Maintenance Bay 2C	Maintenance Shop	LED - Surface Mount	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Martin County Landfill	1463	1	41	Parts	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Landfill	1464	1	42	Loft	Storage - General	8' Industrial	F96T8 / 2L Electronic	2	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	2
Martin County Landfill - Exterior	1465	1	43	Maintenance Bay 2 Exterior	Exterior - Parking / Grounds	LED - High Bay (100w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2

Martin County Landfill	1466	1	44	Maintenance Bay 2 Exterior	Exterior	Wall Pack	150w MH / HID-150	1	Replace fixture with LED Wall Pack (35w / 4655lm)	1
Martin County Landfill	1467	1	45	Maintenance Bay 1	Warehouse	8' Strip	F96T12ES / F2em96	5	Retrofit fixture with 8' LED Strip Kit (35w / 4900lm)	5
Martin County Landfill	1468	1	46	Maintenance Bay 1	Warehouse	High Bay	400w MH / HID-400	1	Replace fixture with LED High Bay (150w / 24300lm) w/Clear Reflector & microwave motion sensor step dimming	1
Martin County Landfill	1469	1	47	Maintenance Carport	Warehouse	4' Wrap	F32T8 / 2L Electronic	8	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Martin County Landfill	1470	1	48	Maintenance Bay 3	Maintenance Shop	LED - High Bay (100w)	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
Martin County Landfill	1471	1	49	Office	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Landfill	1472	1	50	Office	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Landfill	1473	1	51	Mechanical	Mechanical Room	4' Vapor Tight	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Landfill	1474	1	52	Breakroom	Break / Lounge	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Landfill	1475	1	53	Breakroom	Break / Lounge	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Landfill	1476	1	54	Restroom	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Landfill	1477	1	55	Restroom	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Landfill	1478	1	56	IT	Server / Com Room	2x4 Rec. Parabolic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Landfill	1479	1	57	Office	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Landfill	1480	1	58	Control Room	Office - Private	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Landfill	1481	1	59	Control Room	Office - Private	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Landfill	1482	1	60	Hallway	Corridor / Hallway	2x4 Rec. Parabolic	F32T8 / 3L Electronic	7	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Martin County Landfill	1483	1	61	Hallway	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	5	DND - Existing Emergency Egress	5
Martin County Landfill	1484	1	62	Hallway	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Martin County Landfill	1485	1	63	Generator	Generator Room	4' Vapor Tight	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Landfill	1486	1	64	Generator	Generator Room	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1

Martin County Landfill	1487	1	65	Exterior	Exterior	Wall Pack (70w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Martin County Landfill	1488	1	66	Exterior	Exterior	Wall Pack (70w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Martin County Landfill	1489	1	67	Exterior	Exterior	LED - Flood (60w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Martin County Landfill	1490	1	68	Hazmat Transfer Bay	Warehouse	LED - High Bay (100w)	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
Martin County Landfill	1491	1	69	Hazmat Transfer Bay	Warehouse	4' Vapor Tight (20w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Martin County Landfill	1492	1	70	Hazmat Transfer Bay	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Landfill	1493	1	73	Hazmat Transfer Bay	Warehouse	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Martin County Landfill	1494	1	71	Hazardous Storage	Storage - General	4' Vapor Tight (20w)	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Martin County Landfill	1495	1	72	Hazardous Storage	Storage - General	4' Vapor Tight (20w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Martin County Landfill	1496	1	74	Office	Office - Private	4' Wrap	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Landfill	1497	1	75	Restroom	Restroom - Public	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Landfill	1498	1	76	Exterior	Exterior	Wall Pack	150w MH / HID-150	4	Replace fixture with LED Wall Pack (35w / 4655lm)	4
Martin County Landfill - Exterior	1499	1	77	Exterior	Exterior - Parking / Grounds	Flood	400w MH / HID-400	1	Replace fixture with LED Flood (90w / 13950lm)	1
Martin County Tax Collector	1500	1	1	105	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1501	1	2	104	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1502	1	3	103	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1503	1	4	101	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1504	1	5	101A	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Martin County Tax Collector	1505	1	6	102	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Martin County Tax Collector	1506	1	7	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Martin County Tax Collector	1507	1	8	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Martin County Tax Collector	1508	1	9	Open Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1509	1	10	Open Office	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Martin County Tax Collector	1510	1	11	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Martin County Tax Collector	1511	1	12	112	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1512	1	13	111	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Tax Collector	1513	1	14	110	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Martin County Tax Collector	1514	1	15	108	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1515	1	16	107	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1516	1	17	Conference	Conference Room	LED - Recessed Can 8"	Integral LED / Integral LED Driver	18	DND - Existing LED fixture	18
Martin County Tax Collector	1517	1	18	Conference	Conference Room	LED - Recessed Can 8"	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Martin County Tax Collector	1518	1	19	Conference	Conference Room	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1519	1	20	109	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1520	1	21	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1521	1	22	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Martin County Tax Collector	1522	1	23	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1523	1	24	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1524	1	25	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	7	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Martin County Tax Collector	1525	1	26	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1526	1	27	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1527	1	28	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	10	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Martin County Tax Collector	1528	1	29	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1529	1	30	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Martin County Tax Collector	1530	1	31	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3



Martin County Tax Collector	1531	1	32	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1532	1	33	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Martin County Tax Collector	1533	1	34	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1534	1	35	Janitor	Custodial Closet	Globe	60w Incandescent / N/A	1	Relamp fixture with A19 LED	1
Martin County Tax Collector	1535	1	36	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Martin County Tax Collector	1536	1	37	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Martin County Tax Collector	1537	1	38	Vestibule	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Tax Collector	1538	1	39	Janitor	Custodial Closet	Globe	60w Incandescent / N/A	1	Relamp fixture with A19 LED	1
Martin County Tax Collector	1539	1	40	124	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1540	1	41	123	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1541	1	42	122	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1542	1	43	121	Workroom	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1543	1	44	120	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Martin County Tax Collector	1544	1	45	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Martin County Tax Collector	1545	1	46	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1546	1	47	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1547	1	48	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Martin County Tax Collector	1548	1	49	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1549	1	50	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1550	1	51	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1551	1	52	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1552	1	53	Vestibule	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear	2

									Tube and Normal Power LED Driver	
Martin County Tax Collector	1553	1	54	Lobby/Open Office	Office - Admin Area	LED - Recessed Can 8"	Integral LED / Integral LED Driver	56	DND - Existing LED fixture	56
Martin County Tax Collector	1554	1	55	Lobby/Open Office	Office - Admin Area	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1555	1	56	Lobby/Open Office	Office - Admin Area	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1556	1	57	Lobby/Open Office	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Martin County Tax Collector	1557	1	58	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Martin County Tax Collector	1558	1	59	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Martin County Tax Collector	1559	1	60	Vestibule	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1560	1	61	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Martin County Tax Collector	1561	1	62	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1562	1	63	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1563	1	64	Vestibule	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1564	1	65	Vestibule	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1565	1	66	145	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1566	1	67	144	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1567	1	68	143	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1568	1	69	Vestibule	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Martin County Tax Collector	1569	1	70	Vestibule	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1570	1	71	Open Office/Lobby	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	12	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Martin County Tax Collector	1571	1	72	Open Office/Lobby	Office - Private	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1572	1	73	Open Office/Lobby	Office - Private	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1573	1	74	Vestibule	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1574	1	75	Vestibule	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1

Martin County Tax Collector	1575	1	76	Restroom	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Martin County Tax Collector	1576	1	77	Restroom	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Martin County Tax Collector	1577	1	78	139	Classroom - Computer Lab	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Martin County Tax Collector	1578	1	79	138	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Martin County Tax Collector	1579	1	80	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	7	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Martin County Tax Collector	1580	1	81	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1581	1	82	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1582	1	83	Hallway	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Martin County Tax Collector	1583	1	84	Hallway	Corridor / Hallway - Suite / Dept	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Martin County Tax Collector	1584	1	85	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1585	1	86	147	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	8	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Martin County Tax Collector	1586	1	87	Restroom	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Martin County Tax Collector	1587	1	88	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	8	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Martin County Tax Collector	1588	1	89	Open Office	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	10	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Martin County Tax Collector	1589	1	90	Open Office	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Martin County Tax Collector	1590	1	91	Open Office	Office - Admin Area	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Martin County Tax Collector	1591	1	92	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	20	DND - Existing LED fixture	20
Martin County Tax Collector	1592	1	93	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	32	DND - Existing LED fixture	32
Mc DRC (Old EOC)	1593	1	1	Control Room	Office - Private	1x4 Rec. Parabolic	F32T8 / 2L Electronic	9	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	9
Mc DRC (Old EOC)	1594	1	2	Control Room	Office - Private	LED - Decorative	Integral LED / Integral LED Driver	14	DND - Existing LED fixture	14
Mc DRC (Old EOC)	1595	1	3	Restroom	Restroom - Public	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
Mc DRC (Old EOC)	1596	1	4	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1

Mc DRC (Old EOC)	1597	1	5	Restroom	Restroom - Public	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Mc DRC (Old EOC)	1598	1	6	Restroom	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
MCSO Aviation Hanger	1599	1	1	Entrance	Vestible / Foyer	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
MCSO Aviation Hanger	1600	1	2	Entrance	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
MCSO Aviation Hanger	1601	1	5	Entrance	Vestible / Foyer	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
MCSO Aviation Hanger	1602	1	3	Kitchen	Kitchen	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
MCSO Aviation Hanger	1603	1	4	Dayroom	Dayroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	6	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	6
MCSO Aviation Hanger	1604	1	6	Dayroom	Dayroom	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
MCSO Aviation Hanger	1605	1	7	Dayroom	Dayroom	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
MCSO Aviation Hanger	1606	1	8	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
MCSO Aviation Hanger	1607	1	9	Workroom	Workroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
MCSO Aviation Hanger	1608	1	10	Restroom	Restroom - Public	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
MCSO Aviation Hanger	1609	1	11	Restroom	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
MCSO Aviation Hanger	1610	1	12	Hallway	Corridor / Hallway	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
MCSO Aviation Hanger	1611	1	13	Hallway	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
MCSO Aviation Hanger	1612	1	14	Locker Room	Locker Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
MCSO Aviation Hanger	1613	1	15	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
MCSO Aviation Hanger	1614	1	16	Parts Room	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
MCSO Aviation Hanger	1616	1	18	Parts Room	Storage - Equipment	4' Wrap	F32T8 / 2L Electronic	7	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	7
MCSO Aviation Hanger	1617	1	19	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2

MCSO Aviation Hanger	1618	1	20	Hanger	Warehouse	LED - High Bay (100w)	Integral LED / Integral LED Driver	9	DND - Existing LED fixture	9
MCSO Aviation Hanger	1619	1	21	Hanger	Warehouse	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
MCSO Aviation Hanger	1620	1	22	Hanger	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
MCSO Aviation Hanger	1621	1	23	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
MCSO Aviation Hanger - Exterior	1622	1	24	Exterior	Exterior - Parking / Grounds	Flood	250w MH / HID-250	2	Replace fixture with LED Flood (90w / 13950lm)	2
MCSO Aviation Hanger	1623	1	25	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Morgade Library	1624	1	1	Room	Lobby Area - Main	Recessed Can 8" - Vert	CFL 18w PL / CFL	10	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	10
Morgade Library	1625	1	2	Room	Lobby Area - Main	4' Strip Cove / Soffit	F32T8 / 2L Electronic	18	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	18
Morgade Library	1626	1	3	Room	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Morgade Library	1627	1	23	Room	Lobby Area - Main	Recessed Can 4"	MR16 / N/A	4	Relamp fixture with LED MR16 (Verify base & optics)	4
Morgade Library	1628	1	4	Room	Vestible / Foyer	LED - Ceiling Drum	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Morgade Library	1629	1	5	Room	Restroom - Public	LED - Ceiling Drum	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Morgade Library	1630	1	6	Room	Restroom - Public	4' Strip Cove / Soffit	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Morgade Library	1631	1	7	Room	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Morgade Library	1632	1	8	Room	Custodial Closet	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Morgade Library	1633	1	9	Room	Vestible / Foyer	Recessed Can 8" - Vert	CFL 18w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Morgade Library	1634	1	10	Room	Conference Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	16	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	16
Morgade Library	1635	1	11	Room	Conference Room	Recessed Can 8" - Vert	CFL 18w PL / CFL	15	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	15
Morgade Library	1636	1	12	Room	Conference Room	Recessed Can 8" - Vert	CFL 18w PL / CFL	3	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	3
Morgade Library	1637	1	13	Room	Conference Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1638	1	14	Room	Conference Room	Recessed Can 8" - Vert	CFL 18w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Morgade Library	1639	1	15	Room	Conference Room	Track	I100A / N/A	4	Relamp fixture with PAR30 LED	4
Morgade Library	1640	1	16	Room	Conference Room	Exit Sign w/battery & lights	I20T / N/A	1	Replace fixture with LED Exit Sign COMBO w/Battery	1

									Back Up & Egress Lights (White/Red)	
Morgade Library	1641	1	17	Room	Conference Room	Exit Sign w/battery & lights	I20T / N/A	2	Replace fixture with LED Exit Sign COMBO w/Battery Back Up & Egress Lights (White/Red)	2
Morgade Library	1642	1	18	Room	Kitchen	2x4 Rec. Parabolic	F32T8 / 4L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Morgade Library	1643	1	19	Room	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1644	1	20	Room	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1645	1	21	Room	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Morgade Library	1646	1	22	Room	Server / Com Room	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1647	1	24	Room	Vestible / Foyer	LED - Ceiling Drum	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Morgade Library	1648	1	25	Room	Restroom - Public	LED - Ceiling Drum	Integral LED / Integral LED Driver	7	DND - Existing LED fixture	7
Morgade Library	1649	1	26	Room	Restroom - Public	4' Strip Cove / Soffit	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Morgade Library	1650	1	27	Room	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Morgade Library	1651	1	28	Room	Office - Private	2x4 Rec. Parabolic	F32T8 / 4L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1652	1	29	Room	Workroom	2x4 Rec. Parabolic	F32T8 / 4L Electronic	8	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	8
Morgade Library	1653	1	30	Room	Workroom	2x4 Rec. Parabolic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1654	1	31	Room	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1655	1	32	Room	Restroom - Public	LED - Surface Drum	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Morgade Library	1656	1	33	Room	Break / Lounge	2x4 Rec. Parabolic	F32T8 / 4L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1657	1	34	Room	Office - Private	2x4 Rec. Parabolic	F32T8 / 4L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Morgade Library	1658	1	35	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	12	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	12
Morgade Library	1659	1	36	Room	Library	Recessed Can 8" - Vert	CFL 18w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
Morgade Library	1660	1	37	Room	Storage - General	Recessed Can 8" - Vert	CFL 18w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Morgade Library	1661	1	38	Room	Training Room	2x4 Rec. Parabolic	F32T8 / 4L Electronic	2	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	2
Morgade Library	1662	1	39	Room	Training Room	Recessed Can 8" - Vert	CFL 18w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Morgade Library	1663	1	40	Room	Classroom - Study Room	2x4 Rec. Parabolic	F32T8 / 4L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1



Morgade Library	1664	1	41	Room	Classroom - Study Room	2x4 Rec. Parabolic	F32T8 / 4L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Morgade Library	1665	1	42	Room	Conference Room	2x4 Rec. Parabolic	F32T8 / 4L Electronic	6	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	6
Morgade Library	1666	1	43	Room	Conference Room	Recessed Can 8" - Vert	CFL 18w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Morgade Library	1667	1	44	Room	Library	1x4 Rec. Parabolic	F32T8 / 2L Electronic	10	Retrofit fixture with 1x4 LED Door Kit (24w / 3168lm)	10
Morgade Library	1668	1	45	Room	Library	2x4 Rec. Parabolic - Emergency Battery	F32T8 / 4L Electronic	2	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	2
Morgade Library	1669	1	46	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	4	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	4
Morgade Library	1670	1	47	Room	Library	2x4 Rec. Parabolic - Emergency Battery	F32T8 / 4L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Morgade Library	1671	1	48	Room	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Morgade Library	1672	1	49	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	62	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	62
Morgade Library	1673	1	50	Room	Library	2x4 Rec. Parabolic - Emergency Battery	F32T8 / 4L Electronic	2	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	2
Morgade Library	1674	1	51	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	5	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	5
Morgade Library	1675	1	52	Room	Library	2x4 Rec. Parabolic - Emergency Battery	F32T8 / 4L Electronic	1	Retrofit fixture with 2x4 LED Door Kit w/Emergency Battery (30w / 4110lm)	1
Morgade Library	1676	1	53	Room	Library	2x2 Rec. Parabolic	F32T8/U / 2L Electronic	22	Retrofit fixture with 2x2 LED Door Kit (24w / 3168lm)	22
Morgade Library	1677	1	54	Room	Library	LED - Decorative	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Morgade Library	1678	1	55	Room	Library	4' Strip Cove / Soffit	F32T8 / 2L Electronic	28	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	28
Morgade Library	1679	1	56	Room	Library	Decorative Chandelier	CFL 42w PL / CFL	14	Retrofit fixture with (6) 16w LED Direct Drive lamp - remove ballast & direct wire socket	14
Morgade Library	1680	1	57	Room	Library	LED - Decorative	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Morgade Library	1681	1	58	Room	Library	Recessed Can 8" - Vert	CFL 18w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Morgade Library	1682	1	59	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	1	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	1
Morgade Library	1683	1	60	Room	Library	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Morgade Library	1684	1	61	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	6	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	6



Morgade Library	1685	1	62	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	3	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	3
Morgade Library	1686	1	63	Room	Library	2x4 Rec. Parabolic	F32T8 / 4L Electronic	8	Retrofit fixture with 2x4 LED Door Kit (30w / 4110lm)	8
Morgade Library	1687	1	64	Room	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Morgade Library	1688	1	65	Room	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Morgade Library	1689	1	66	Room	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Morgade Library	1690	1	67	Room	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Morgade Library	1691	1	68	Room	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Morgade Library	1692	1	69	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Morgade Library	1693	1	70	Exterior	Exterior	Recessed Can 8" - Vert	CFL 26w PL / CFL	18	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	18
Morgade Library	1694	1	71	Exterior	Exterior	Wall Mount UpLight	100w MH / HID-100	8	Relamp fixture with LED CornCob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	8
Morgade Library - Exterior	1695	1	72	Flagpole	Exterior - Parking / Grounds	LED - Flood (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1
Morgade Library - Exterior	1696	1	73	Flagpole	Exterior - Parking / Grounds	LED - Flood (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1
Morgade Library - Exterior	1697	1	74	Parking Lot	Exterior - Parking / Grounds	LED - Area (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1
Morgade Library - Exterior	1698	1	75	Parking Lot	Exterior - Parking / Grounds	LED - Area (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1
Morgade Library - Exterior	1699	1	76	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1700	1	77	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1701	1	78	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1702	1	79	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1

Morgade Library - Exterior	1703	1	80	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1704	1	81	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1705	1	82	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1706	1	83	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixture with LED Area Luminaire (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1707	1	84	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1708	1	85	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1709	1	86	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
Morgade Library - Exterior	1710	1	87	Parking Lot	Exterior - Parking / Grounds	Shoebox	250w MH / HID-250	1	Replace fixtures with (2) LED Area Luminaires (71w / 10992lm - Optics TBD) - Slipfit w/Tenon Direct Arm	1
New Monrovia Park Community Center	1711	1	1	Lobby	Lobby Area - Main	2x4 Rec. Parabolic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
New Monrovia Park Community Center	1712	1	2	Lobby	Lobby Area - Main	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
New Monrovia Park Community Center	1713	1	3	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
New Monrovia Park Community Center	1714	1	4	Restroom	Restroom - Public	Recessed Can 8" - Horz	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
New Monrovia Park Community Center	1715	1	5	Mechanical	Mechanical Room	Jelly Jar	60w Incandescent / N/A	1	Relamp fixture with A19 LED	1
New Monrovia Park	1716	1	6	Multipurpose	Multi Purpose	2x4 Rec. Parabolic	F32T8 / 3L Electronic	18	Retrofit fixture with (3) 4' T8 LED Linear	18

Community Center									Tube and Normal Power LED Driver	
New Monrovia Park Community Center	1717	1	7	Multipurpose	Multi Purpose	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
New Monrovia Park Community Center	1718	1	8	Multipurpose	Multi Purpose	Exit Sign w/battery	Integral LED / Integral LED Driver	4	DND - Existing LED Exit	4
New Monrovia Park Community Center	1719	1	9	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
New Monrovia Park Community Center	1720	1	10	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
New Monrovia Park Community Center	1721	1	11	Kitchen	Kitchen	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
New Monrovia Park Community Center	1722	1	12	Restroom	Restroom - Public	Recessed Can 8" - Horz	CFL 13w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	4
New Monrovia Park Community Center	1723	1	13	Janitor	Custodial Closet	Recessed Can 8" - Horz	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
New Monrovia Park Community Center	1724	1	15	Mechanical	Mechanical Room	4' Wall Bracket	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
New Monrovia Park Community Center	1725	1	14	Exterior	Exterior	Wall Pack (25w)	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
New Monrovia Park Community Center	1726	1	16	Exterior	Exterior	LED - Canopy (30w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
New Monrovia Park Community Center	1727	1	17	Exterior	Exterior	LED - Flood (20w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
New Monrovia Sheriff Substation	1728	1	4	Open Office	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
New Monrovia Sheriff Substation	1729	1	5	Open Office	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
New Monrovia Sheriff Substation	1730	1	6	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
New Monrovia Sheriff Substation	1731	1	7	Office	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
New Monrovia	1732	1	8	Storage	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear	1

Sheriff Substation									Tube and Normal Power LED Driver	
New Monrovia Sheriff Substation	1733	1	9	Janitor	Custodial Closet	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
New Monrovia Sheriff Substation	1734	1	10	Restroom	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
New Monrovia Sheriff Substation	1735	1	11	Restroom	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
New Monrovia Sheriff Substation	1736	1	12	Open Office	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
New Monrovia Sheriff Substation	1737	1	13	Restroom	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
New Monrovia Sheriff Substation	1738	1	14	Restroom	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
New Monrovia Sheriff Substation	1739	1	15	Dayroom	Dayroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	6	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	6
New Monrovia Sheriff Substation	1740	1	16	Hallway	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
New Monrovia Sheriff Substation	1741	1	17	Hallway	Corridor / Hallway	Exit Sign w/battery & lights	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
New Monrovia Sheriff Substation	1742	1	1	Exterior	Exterior	LED - Canopy (30w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
New Monrovia Sheriff Substation	1743	1	2	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
New Monrovia Sheriff Substation	1744	1	3	Exterior	Exterior	Wall Pack	150w MH / HID-150	3	Replace fixture with LED Wall Pack (35w / 4655lm)	3
Public Safety Complex	1745	1	133	102	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1746	1	134	104	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1747	1	135	105	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1748	1	136	101	Vestible / Foyer	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Public Safety Complex	1749	1	137	101	Vestible / Foyer	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	5	DND - Existing LED fixture	5
Public Safety Complex	1750	1	139	101	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1751	1	269	101	Vestible / Foyer	LED - Recessed	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1

						Can 4" (Retro)				
Public Safety Complex	1752	1	138	101A	Corridor / Hallway	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Public Safety Complex	1753	1	140	197	Classroom - General	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	12	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Public Safety Complex	1754	1	141	193	Storage - General	4' Industrial	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1755	1	142	196	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1756	1	143	194A	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1757	1	144	194B	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1758	1	145	191	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1759	1	146	192	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1760	1	147	189	Office - Private	8' Louvered Up/Down	4' TLED T8 / N/A	1	Retrofit fixture with (6) 4' T8 LED Linear Tube and (3) Normal Power LED Driver	1
Public Safety Complex	1761	1	148	189	Office - Private	Recessed Can 8" - Vert w/Battery	CFL 32w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	4
Public Safety Complex	1762	1	149	104	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1763	1	150	104	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1764	1	151	184	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1765	1	152	182	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1766	1	153	183	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	1767	1	154	181	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1768	1	155	180	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1769	1	156	178	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4

Public Safety Complex	1770	1	157	177	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Public Safety Complex	1771	1	158	176	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1772	1	159	174	Office - Open Cubicals	8' Louvered Up/Down	4' TLED T8 / N/A	17	Retrofit fixture with (6) 4' T8 LED Linear Tube and (3) Normal Power LED Driver	17
Public Safety Complex	1773	1	160	174	Office - Open Cubicals	8' Indirect Up	4' TLED T8 / N/A	10	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Public Safety Complex	1774	1	161	172	Lobby Area - Main	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1775	1	162	172	Lobby Area - Main	Recessed Can 4"	MR16 / N/A	5	Relamp fixture with LED MR16 (Verify base & optics)	5
Public Safety Complex	1776	1	164	172	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1777	1	163	172A	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1778	1	165	190	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1779	1	166	187	Office - Private	LED - Recessed Can 8"	Integral LED / Integral LED Driver	38	DND - Existing LED fixture	38
Public Safety Complex	1780	1	167	187	Office - Private	LED - Recessed Can 8" w/battery	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Public Safety Complex	1781	1	168	187	Office - Private	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Public Safety Complex	1782	1	169	188	Conference Room	LED - Recessed Can 8"	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Public Safety Complex	1783	1	170	188	Conference Room	LED - Recessed Can 8" w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Public Safety Complex	1784	1	171	187A	Office - Private	LED - Recessed Can 8"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Public Safety Complex	1785	1	172	187A	Office - Private	LED - Recessed Can 8" w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	1786	1	173	187B	Office - Private	LED - Recessed Can 8"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Public Safety Complex	1787	1	174	187B	Office - Private	LED - Recessed Can 8" w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	1788	1	175	175	Office - Admin Area	LED - Recessed Can 8"	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Public Safety Complex	1789	1	176	175	Office - Admin Area	LED - Recessed Can 8" w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Public Safety Complex	1790	1	177	175	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Public Safety Complex	1791	1	178	107	Conference Room	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1792	1	179	106A	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1793	1	180	106	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1794	1	181	108	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1795	1	182	109A	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1796	1	183	109A	Office - Admin Area	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1797	1	184	130	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1798	1	185	123	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1799	1	186	135	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1800	1	187	132	Office - Open Cubicals	2x4 Rec. Acrylic	4' TLED T8 / N/A	12	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Public Safety Complex	1801	1	188	132A	Office - Open Cubicals	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1802	1	189	139	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1803	1	190	140	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1804	1	191	138	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1805	1	192	137	Office - Open Cubicals	2x4 Rec. Acrylic	4' TLED T8 / N/A	5	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Public Safety Complex	1806	1	193	137A	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	7	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	1807	1	194	137A	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	1808	1	195	132A	Office - Open Cubicals	2x4 Rec. Volumetric	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1809	1	196	152A	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2



Public Safety Complex	1810	1	197	152	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1811	1	198	143A	Custodial Closet	2x4 Rec. Volumetric	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1812	1	199	143A	Custodial Closet	2x4 Rec. Volumetric	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1813	1	200	134	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1814	1	201	133	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1815	1	202	142	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1816	1	203	145	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1817	1	204	151	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1818	1	205	150	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1819	1	206	148	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1820	1	207	148	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1821	1	208	144A	Workroom	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1822	1	209	149	Conference Room	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1823	1	210	153B	Break / Lounge	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1824	1	211	153A	Storage - Records	2x4 Rec. Acrylic	4' TLED T8 / N/A	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1825	1	212	146	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1826	1	213	146	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1827	1	214	144B	Storage - Records	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1828	1	215	155	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2

Public Safety Complex	1829	1	216	154	Vestible / Foyer	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1830	1	217	154	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	1831	1	218	161A	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1832	1	219	161A	Restroom - Public	Recessed Can 8" - Vert	CFL 13w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Public Safety Complex	1833	1	220	161A	Restroom - Public	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1834	1	221	161D	Storage - General	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1835	1	222	161C	Vestible / Foyer	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1836	1	230	161C	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1837	1	223	161	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	1838	1	224	160	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1839	1	225	159	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1840	1	226	159	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1841	1	227	157	Workroom	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1842	1	228	158A	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1843	1	229	158	Waiting Room	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1844	1	231	162	Conference Room	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1845	1	232	162	Conference Room	Recessed Can 8" - Horz	CFL 32w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	6
Public Safety Complex	1846	1	233	163	Copy Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1847	1	234	167	Lobby Area - Main	2x4 Rec. Volumetric	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear	4

									Tube and Normal Power LED Driver	
Public Safety Complex	1848	1	235	167	Lobby Area - Main	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1849	1	236	167	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	1850	1	237	167A	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1851	1	238	163	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1852	1	239	165	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1853	1	240	163	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1854	1	241	168	Office - Admin Area	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1855	1	242	144	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	7	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	1856	1	243	144	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1857	1	244	144	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	5	DND - Existing LED Exit	5
Public Safety Complex	1858	1	245	143	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	12	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	12
Public Safety Complex	1859	1	246	143	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	6	DND - Existing LED Exit	6
Public Safety Complex	1860	1	247	109	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1861	1	248	103	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	8	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	8
Public Safety Complex	1862	1	249	103	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Public Safety Complex	1863	1	250	195	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	6	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	1864	1	251	195	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Public Safety Complex	1865	1	252	198	Office - Admin Area	2x4 Rec. Acrylic	4' TLED T8 / N/A	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6

Public Safety Complex	1866	1	253	199	Workroom	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1867	1	254	194A	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1868	1	255	194B	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1869	1	256	194B	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1870	1	257	194C	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1871	1	258	194C	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	4	DND - Existing LED Exit	4
Public Safety Complex	1872	1	259	174B	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1873	1	260	174C	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1874	1	261	167A	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1875	1	262	167A	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1876	1	263	171	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1877	1	264	169/170	Vestible / Foyer	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	7	DND - Existing LED fixture	7
Public Safety Complex	1878	1	265	169/170	Vestible / Foyer	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Public Safety Complex	1879	1	266	169/170	Vestible / Foyer	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	1880	1	267	169/170	Vestible / Foyer	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1881	1	268	169/170	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1882	1	270	169/170	Vestible / Foyer	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1883	1	438	125	Storage - Equipment	2x4 Rec. Acrylic	4' TLED T8 / N/A	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3

Public Safety Complex	1884	1	439	117	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	10	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Public Safety Complex	1885	1	440	117	Office - Private	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1886	1	441	126	Storage - Equipment	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1887	1	442	118	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1888	1	443	117	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1889	1	444	116	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1890	1	445	114	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1891	1	446	113	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1892	1	447	112	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1893	1	448	111	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1894	1	449	128	Conference Room	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1895	1	450	127	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1896	1	451	127A	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1897	1	452	110	Office - Open Cubicals	12' Direct/Indirect	F32T8 / 2L Electronic	8	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	8
Public Safety Complex	1898	1	453	110	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Public Safety Complex	1899	1	454	110A	Vestible / Foyer	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1900	1	455	110A	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1901	1	456	174A	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1

Public Safety Complex	1902	1	457	179	Stairwell - Interior	4' Wall Bracket w/Battery	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	3
Public Safety Complex	1903	1	458	179	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1904	1	459	156	Stairwell - Interior	4' Wall Bracket w/Battery	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	3
Public Safety Complex	1905	1	460	156	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1906	1	461	119	Stairwell - Interior	4' Wall Bracket w/Battery	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	4
Public Safety Complex	1907	1	462	119	Stairwell - Interior	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1908	1	497	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	1909	1	498	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	1910	1	499	Exterior	Exterior	LED - Sconce	Integral LED / Integral LED Driver	15	DND - Existing LED fixture	15
Public Safety Complex	1911	1	500	Exterior	Exterior	LED - Flood (100w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Public Safety Complex	1912	1	501	Exterior	Exterior	Wall Pack	70w HPS / HID-70	1	Replace fixture with LED Wall Pack (15w / 2160lm)	1
Public Safety Complex	1913	1	502	Exterior	Exterior	LED - Flood (100w)	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Public Safety Complex	1914	1	3	276	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 3L Electronic	12	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Public Safety Complex	1915	1	4	276	Break / Lounge	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1916	1	5	276A	Kitchen	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Public Safety Complex	1917	1	7	276A	Kitchen	1x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1918	1	6	276B	Kitchen - Storage	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1919	1	8	283	Kitchen - Storage	2x4 Rec. Acrylic	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	1920	1	9	Cooler	Storage - General	LED - Jelly Jar (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	1921	1	11	280	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2

Public Safety Complex	1922	1	12	278	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / N/A	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1923	1	13	279	Server / Com Room	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1924	1	14	273	Vestible / Foyer	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1925	1	23	273	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1926	1	15	284	Conference Room	2x4 Rec. Volumetric	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1927	1	16	285	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1928	1	17	285	Office - Admin Area	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1929	1	18	236	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1930	1	19	277	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1931	1	22	277	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1934	1	24	235	Workroom	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1935	1	25	234	Office - Open Cubicals	2x4 Rec. Volumetric	F32T8 / 2L Electronic	7	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	1936	1	26	232	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / N/A	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	1937	1	27	231	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	5	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Public Safety Complex	1938	1	28	230	Office - Admin Area	4' Industrial	F32T8 / 2L Electronic	8	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Public Safety Complex	1939	1	29	229	Workroom	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1940	1	30	228	Conference Room	12' Direct/Indirect	F32T8 / 2L Electronic	9	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	9
Public Safety Complex	1941	1	116	228	Conference Room	4' Direct/Indirect	F32T8 / 2L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3



Public Safety Complex	1942	1	117	228	Conference Room	Recessed Can 8" - Vert w/Battery	CFL 32w PL / CFL	4	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	4
Public Safety Complex	1943	1	118	228	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Public Safety Complex	1944	1	31	222	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1945	1	32	221	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1946	1	33	220	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1947	1	34	219	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1948	1	35	218	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1949	1	36	218	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1950	1	37	216	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1951	1	38	216A	Office - Private	2x2 Rec. Parabolic	FB31T8/U / 3L Electronic	4	Retrofit fixture with (3) 2' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1952	1	39	215	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1953	1	40	212	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1954	1	41	211	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1955	1	42	210	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1956	1	43	211	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1957	1	44	208	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1958	1	45	207	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1959	1	46	206	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1960	1	47	205A	Office - Admin Area	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2

Public Safety Complex	1961	1	48	205	Office - Open Cubicals	2x4 Rec. Volumetric	F32T8 / 2L Electronic	10	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Public Safety Complex	1962	1	49	213A	Workroom	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1963	1	50	213	Office - Open Cubicals	2x4 Rec. Volumetric	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	1964	1	51	225/225A	Classroom - General	12' Direct/Indirect	F32T8 / 2L Electronic	8	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	8
Public Safety Complex	1965	1	119	225/225A	Classroom - General	Recessed Can 8" - Horz	CFL 32w PL / CFL	16	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	16
Public Safety Complex	1966	1	120	225/225A	Classroom - General	Recessed Can 8"	60w Incandescent / N/A	12	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	12
Public Safety Complex	1967	1	121	225/225A	Classroom - General	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	1968	1	52	227	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1969	1	53	269	Server / Com Room	2x4 Rec. Acrylic	4' TLED T8 / N/A	9	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	9
Public Safety Complex	1970	1	54	269	Server / Com Room	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	5	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	5
Public Safety Complex	1971	1	55	226	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1972	1	56	226	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	1973	1	57	202	Custodial Closet	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1974	1	58	203	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / N/A	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1975	1	59	204	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / N/A	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1976	1	1	201	Lobby Area - Main	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	10	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	10
Public Safety Complex	1977	1	2	201	Lobby Area - Main	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	12	DND - Existing LED fixture	12
Public Safety Complex	1978	1	122	201	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Public Safety Complex	1979	1	60	286	Conference Room	2x4 Rec. Acrylic	4' TLED T8 / N/A	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	1980	1	61	286	Conference Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1981	1	62	286	Conference Room	Recessed Can 8" - Horz	CFL 32w PL / CFL	8	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	8
Public Safety Complex	1982	1	63	286A	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1983	1	64	272C	Vestible / Foyer	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1984	1	65	272	Locker Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1985	1	66	272A	Locker Room - Showers	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1986	1	67	272A	Locker Room - Showers	Recessed Can 8" - Vert	CFL 13w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Public Safety Complex	1987	1	68	271C	Vestible / Foyer	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	1988	1	69	271	Locker Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	1989	1	70	271A	Locker Room - Showers	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1990	1	71	271A	Locker Room - Showers	Recessed Can 8" - Vert	CFL 13w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Public Safety Complex	1991	1	72	264	Exterior	Bulkhead	CFL 26w PL / CFL	2	Relamp fixture with LED CornCob lamp (18w / 2520lm) - remove existing ballast and direct wire socket	2
Public Safety Complex	1992	1	73	263	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1993	1	74	262	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1994	1	75	280	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1995	1	76	261	Break / Lounge	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1996	1	77	260	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2

Public Safety Complex	1997	1	78	259	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1998	1	79	258	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	1999	1	80	257	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2000	1	81	266	Office - Open Cubicals	12' Direct/Indirect	F32T8 / 2L Electronic	12	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	12
Public Safety Complex	2001	1	82	266	Office - Open Cubicals	4' Direct/Indirect	F32T8 / 2L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2002	1	83	266	Office - Open Cubicals	Recessed Can 8" - Vert w/Battery	CFL 32w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (17w / 872lm) w/battery	6
Public Safety Complex	2003	1	84	266	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2004	1	85	265	Server / Com Room	2x4 Rec. Acrylic	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2005	1	86	265	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2006	1	87	265	Server / Com Room	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2007	1	88	267	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2008	1	89	267	Break / Lounge	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2009	1	90	268	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2010	1	91	268A	Mechanical Room	4' Wrap	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2011	1	92	256A	Office - Open Cubicals	2x4 Rec. Volumetric	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2012	1	93	255	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2013	1	94	254	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2014	1	95	254	Office - Private	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2015	1	96	246	Classroom - General	12' Direct/Indirect	F32T8 / 2L Electronic	8	Retrofit fixture with (4) 4' T8 LED Linear	8

									Tube and Normal Power LED Driver - Emergency Battery Back Up	
Public Safety Complex	2016	1	97	246	Classroom - General	4' Direct/Indirect	F32T8 / 2L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2017	1	98	246	Classroom - General	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Public Safety Complex	2018	1	99	252	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2019	1	100	251	Mechanical Room	4' Industrial	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2020	1	101	249	Office - Private	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2021	1	102	247	Classroom - Shop / Vocational	2x4 Rec. Acrylic	4' TLED T8 / N/A	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	2022	1	103	242A	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2023	1	104	242	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2024	1	105	244	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2025	1	106	244	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2026	1	107	243	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2027	1	108	239	Conference Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	2028	1	109	238	Conference Room	2x4 Rec. Acrylic	4' TLED T8 / N/A	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	2029	1	110	237	Conference Room	2x4 Rec. Volumetric	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	2030	1	111	241/240	Classroom - Shop / Vocational	2x4 Rec. Acrylic	F32T8 / 2L Electronic	7	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	2031	1	112	241/240	Classroom - Shop / Vocational	2x4 Rec. Acrylic	4' TLED T8 / N/A	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2032	1	113	233	Restroom - Public	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2033	1	114	285	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	13	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	13

Public Safety Complex	2034	1	115	285	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Public Safety Complex	2035	1	123	201A	Waiting Room	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Public Safety Complex	2036	1	124	201A	Waiting Room	LED - Recessed Can 4" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Public Safety Complex	2037	1	125	201A	Waiting Room	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2038	1	126	223	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2039	1	127	224	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	15	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	15
Public Safety Complex	2040	1	128	224	Corridor / Hallway	2x2 Troffer	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Public Safety Complex	2041	1	129	224	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	5	DND - Existing LED Exit	5
Public Safety Complex	2042	1	130	224	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2043	1	131	248/256	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	22	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	22
Public Safety Complex	2044	1	132	248/256	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2045	1	463	120	Maintenance Shop	4' Vapor Tight	4' TLED T8 / N/A	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2046	1	464	121	Maintenance Shop	4' Vapor Tight	F32T8 / 3L Electronic	10	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	10
Public Safety Complex	2047	1	465	121	Workroom	4' Vapor Tight	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	2048	1	466	121	Workroom	4' Vapor Tight	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2049	1	468	121	Workroom	4' Vapor Tight	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2050	1	467	122	Maintenance Shop	4' Vapor Tight	4' TLED T8 / N/A	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2051	1	469	122	Maintenance Shop	High Bay	1000w MH / HID-1000	1	Replace fixture with LED High Bay (320w / 50550lm) w/wireguard & microwave motion sensor step dimming	1
Public Safety Complex	2052	1	470	122	Maintenance Shop	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Public Safety Complex	2053	1	471	124B	Chiller Plant Area	Wall Pack	150w MH / HID-150	12	Replace fixture with LED Wall Pack (35w / 4655lm)	12
Public Safety Complex	2054	1	472	124B	Chiller Plant Area	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Public Safety Complex	2055	1	473	124B	Chiller Plant Area	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2056	1	474	124	Electrical / Mech	4' Industrial	F32T8 / 2L Electronic	3	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2057	1	475	124	Electrical / Mech	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2058	1	476	124	Electrical / Mech	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Public Safety Complex	2059	1	477	Room	Locker Room	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2060	1	478	Room	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2061	1	479	Room	Locker Room - Showers	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2062	1	480	Room	Locker Room - Showers	Recessed Can 8" - Vert	CFL 13w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Public Safety Complex	2063	1	481	Room	Locker Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2064	1	482	Room	Restroom - Public	2x4 Rec. Acrylic	4' TLED T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2065	1	483	Room	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2066	1	484	Room	Locker Room - Showers	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2067	1	485	Room	Locker Room - Showers	Recessed Can 8" - Vert	CFL 13w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	2
Public Safety Complex	2069	1	487	Room	Storage - General	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2070	1	488	Room	Storage - General	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2071	1	489	Exterior-Locker Area	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Public Safety Complex	2072	1	490	Exterior-Crime Scene Garage	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Public Safety Complex	2073	1	491	Exterior-Chiller Yard	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Public Safety Complex	2074	1	271	Room	Restroom - Public	1x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2



Public Safety Complex	2075	1	272	Room	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	2076	1	273	Room	Restroom - Public	1x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Public Safety Complex	2077	1	274	Room	Restroom - Public	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	2078	1	275	Room	Classroom - Study Room	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2079	1	276	Room	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2080	1	277	Room	Storage - General	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	2	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2081	1	278	307	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2082	1	279	308	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2083	1	280	309	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2084	1	281	310	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2085	1	282	311	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2086	1	283	312	Storage - General	Recessed Can 8" - Vert	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Public Safety Complex	2087	1	284	313	Restroom - Public	1x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	2088	1	285	313	Restroom - Public	Recessed Can 8" - Vert	CFL 13w PL / CFL	1	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	1
Public Safety Complex	2089	1	286	314	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2090	1	287	315	Storage - Records	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2091	1	288	316	Storage - General	2x2 Rec. Acrylic	F34T12/U / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2092	1	289	317	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2093	1	290	318	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2094	1	291	318	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Public Safety Complex	2095	1	292	Room	Copy Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2096	1	293	Room	Lobby Area - Main	2x4 Rec. Acrylic	F32T8 / 4L Electronic	7	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	2097	1	294	Room	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2098	1	295	335A	Conference Room	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	12	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	12
Public Safety Complex	2099	1	296	335A	Conference Room	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2100	1	297	335B	Vestible / Foyer	Recessed Can 10" - Horz	CFL 13w PL / CFL	2	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	2
Public Safety Complex	2101	1	298	335B	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2102	1	299	331	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2103	1	300	331	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2104	1	301	332	Storage - Records	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2105	1	302	333	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2106	1	303	333	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2107	1	304	325A	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2108	1	305	325A	Office - Admin Area	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2109	1	306	325A	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2110	1	307	326	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2111	1	308	327	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2112	1	309	328	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2113	1	310	329	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear	1

									Tube and Normal Power LED Driver	
Public Safety Complex	2114	1	311	329	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2115	1	312	330	Storage - General	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2116	1	313	324	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	2117	1	314	323	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	2118	1	315	322A	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	12	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Public Safety Complex	2119	1	316	322A	Office - Admin Area	Recessed Can 8"	60w Incandescent / N/A	9	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	9
Public Safety Complex	2120	1	317	322A	Office - Admin Area	Track	I100A / N/A	3	Relamp fixture with PAR30 LED	3
Public Safety Complex	2121	1	318	322A	Office - Admin Area	Recessed Can 6"	60w Incandescent / N/A	2	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	2
Public Safety Complex	2122	1	319	322A	Office - Admin Area	Recessed Can 6"	I100A / N/A	2	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	2
Public Safety Complex	2123	1	320	322A	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2124	1	321	321	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2125	1	322	321	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2127	1	324	Room	Mechanical Room	Surface Mount	CFL 13w PL / CFL	1	Retrofit fixture with LED Circular Kit (13.5w / 2150lm)	1
Public Safety Complex	2128	1	325	339	Mail Room / Distribution Center	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2129	1	326	340	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2130	1	327	341	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2132	1	329	343	Workroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2133	1	330	344	Vestible / Foyer	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	2134	1	331	Room	Locker Room	1x4 Troffer	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Public Safety Complex	2135	1	332	Room	Locker Room	LED - Recessed Can 8"	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Public Safety Complex	2136	1	333	346	Custodial Closet	LED - Canopy (Retro)	LED Corn Cob / N/A	1	DND - Existing LED fixture	1

Public Safety Complex	2137	1	334	344	Vestible / Foyer	LED - Recessed Can 8"	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	2138	1	335	Room	Locker Room	1x4 Troffer	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Public Safety Complex	2139	1	336	Room	Locker Room	LED - Recessed Can 8"	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Public Safety Complex	2140	1	337	351A	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2141	1	338	351A	Storage - General	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2142	1	339	352	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2143	1	340	353	Storage - General	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2144	1	341	353	Storage - General	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2145	1	342	350A	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	11	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	11
Public Safety Complex	2146	1	343	350A	Office - Admin Area	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2147	1	344	350A	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2148	1	345	355	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	2149	1	346	356	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	2150	1	347	357	Office - Open Cubicals	2x4 Rec. Acrylic	F32T8 / 4L Electronic	4	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2151	1	351	357	Office - Open Cubicals	1x4 Rec. Parabolic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2152	1	348	358	Office - Private	1x4 Rec. Parabolic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2153	1	349	359	Server / Com Room	1x4 Rec. Parabolic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2154	1	350	359	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2155	1	352	Room	Corridor / Hallway	LED - Decorative (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Public Safety Complex	2156	1	353	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2157	1	354	35	Office - Private	1x4 Rec. Parabolic	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4

Public Safety Complex	2158	1	355	365	Office - Open Cubicals	1x4 Rec. Parabolic	F32T8 / 2L Electronic	18	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	18
Public Safety Complex	2159	1	356	365	Office - Open Cubicals	Recessed Can 8"	60w Incandescent / N/A	21	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	21
Public Safety Complex	2160	1	357	365	Office - Open Cubicals	Recessed Can 6"	I100A / N/A	8	Retrofit fixture with 6" LED Recessed Can Kit (9w / 850lm)	8
Public Safety Complex	2161	1	358	365	Office - Open Cubicals	4' Wall Bracket	F32T8 / 2L Electronic	16	Retrofit fixture with (1) 4' T8 LED Linear Tube and Normal Power LED Driver	16
Public Safety Complex	2162	1	359	365	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2163	1	360	367	Storage - Equipment	1x4 Rec. Acrylic	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2164	1	361	367	Storage - Equipment	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2165	1	362	369	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2166	1	363	363	Mechanical Room	Surface Mount	CFL 13w PL / CFL	1	Retrofit fixture with LED Circular Kit (13.5w / 2150lm)	1
Public Safety Complex	2167	1	364	364	Storage - General	2x2 Rec. Acrylic	F34T12/U / FL Magnetic ES	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2168	1	365	370C	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2169	1	366	370C	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2170	1	367	368A	Electrical / Mech	1x4 Rec. Acrylic	4' TLED T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2171	1	368	371	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2172	1	369	Room	Office - Admin Area	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	9	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	9
Public Safety Complex	2173	1	370	372A	Storage - Equipment	8' Industrial	4' TLED T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2174	1	374	372A	Storage - Equipment	8' Industrial	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2175	1	375	372A	Storage - Equipment	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2176	1	371	Room	Storage - General	8' Industrial	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2177	1	372	Room	Storage - General	8' Industrial	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3

Public Safety Complex	2178	1	373	Room	Storage - General	4' Wrap	F32T8 / 2L Electronic	8	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Public Safety Complex	2179	1	376	373	Workroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2180	1	377	380	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2181	1	378	372B	Workroom	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2182	1	379	381	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2183	1	380	382	Storage - General	1x4 Rec. Acrylic	F32T8 / 2L Electronic	12	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	12
Public Safety Complex	2184	1	381	382	Storage - General	1x4 Rec. Acrylic	4' TLED T8 / 2L Electronic	5	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Public Safety Complex	2185	1	385	Room	Generator Room	Wall Pack (25w)	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Public Safety Complex	2186	1	386	Room	Generator Room	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Public Safety Complex	2187	1	387	364	Storage - General	4' Industrial	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2188	1	388	Room	Electrical / Mech	1x4 Rec. Acrylic	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2189	1	389	383	Mechanical Room	Surface Mount	CFL 13w PL / CFL	1	Retrofit fixture with LED Circular Kit (13.5w / 2150lm)	1
Public Safety Complex	2190	1	390	384	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	2191	1	391	385	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Public Safety Complex	2192	1	392	386	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	6	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Public Safety Complex	2193	1	397	386	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2194	1	398	378	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2195	1	399	379	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2196	1	400	Room	Office - Private	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2197	1	401	398	Storage - Records	2x4 Rec. Acrylic	F32T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2198	1	402	396	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1

Public Safety Complex	2199	1	403	395	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2200	1	404	394	Office - Private	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2201	1	405	393	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2202	1	406	392	Storage - General	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2203	1	407	Room	Corridor / Hallway - Suite / Dept	Recessed Can 10" - Horz	CFL 13w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (17w / 1380lm) w/10" Goof Ring & Battery	6
Public Safety Complex	2204	1	408	39	Office - Admin Area	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2205	1	409	390	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	7	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	2206	1	411	390	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2207	1	412	Room	Copy Room	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2208	1	413	Room	Lobby Area - Main	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2209	1	414	Room	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2210	1	415	Room	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2211	1	416	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2212	1	417	402	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2213	1	418	401	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2214	1	419	400	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	7	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	2215	1	420	400	Office - Admin Area	2x4 Rec. Acrylic	4' TLED T8 / 4L Electronic	3	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2216	1	421	3	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 4L Electronic	13	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	13
Public Safety Complex	2217	1	422	3	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2



Public Safety Complex	2218	1	423	Room	Corridor / Hallway - Suite / Dept	2x4 Rec. Acrylic	F32T8 / 4L Electronic	1	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2219	1	424	Room	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 4L Electronic	2	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2220	1	425	Room	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	3	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	3
Public Safety Complex	2221	1	426	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2222	1	427	Room	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	4	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2223	1	428	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2224	1	429	Room	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	10	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	10
Public Safety Complex	2225	1	430	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	5	DND - Existing LED Exit	5
Public Safety Complex	2226	1	431	Room	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	7	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	2227	1	432	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2228	1	433	Room	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	9	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	9
Public Safety Complex	2229	1	434	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2230	1	435	Room	Corridor / Hallway	2x2 Rec. Acrylic	4' TLED - T8U / 2L Electronic	7	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	7
Public Safety Complex	2231	1	436	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Public Safety Complex	2232	1	437	Room	Corridor / Hallway - Suite / Dept	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2233	1	492	Room	Mechanical Room	Surface Mount	CFL 13w PL / CFL	1	Retrofit fixture with LED Circular Kit (13.5w / 2150lm)	1
Public Safety Complex	2234	1	493	Room	Mechanical Room	Surface Mount	CFL 13w PL / CFL	1	Retrofit fixture with LED Circular Kit (13.5w / 2150lm)	1
Public Safety Complex	2235	1	494	Exterior	Exterior	Recessed Square	70w HPS / HID-70	39	Retrofit fixture with LED Rectangular Kit (12w / 1600lm)	39
Public Safety Complex	2236	1	495	Exterior	Exterior	Wall Pack	150w MH / HID-150	5	Replace fixture with LED Wall Pack (35w / 4655lm)	5
Public Safety Complex	2237	1	496	Exterior	Exterior	Wall Pack (70w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1

Public Safety Complex	2238	1	382	Evidence Warehouse	Warehouse	LED - High Bay	Integral LED / Integral LED Driver	36	DND - Existing LED fixture	36
Public Safety Complex	2239	1	384	Evidence Warehouse	Warehouse	4' Wrap	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	2240	1	383	It Room	Server / Com Room	4' Strip (20w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Public Safety Complex	2241	1	513	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Public Safety Complex	2242	1	514	Exterior	Exterior	LED - Canopy (30w)	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Public Safety Complex	2243	1	503	Room	Maintenance Shop	LED - High Bay (100w)	Integral LED / Integral LED Driver	17	DND - Existing LED fixture	17
Public Safety Complex	2244	1	504	Room	Maintenance Shop	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Public Safety Complex	2245	1	505	Exterior	Exterior	Wall Pack	150w MH / HID-150	10	Replace fixture with LED Wall Pack (35w / 4655lm)	10
Public Safety Complex	2246	1	506	100	Warehouse	2x4 High Bay	FP54T5HO / 4L Electronic	34	Replace fixture with LED High Bay (100w / 16500lm) w/Clear Reflector & microwave motion sensor step dimming	34
Public Safety Complex	2247	1	507	100	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	4	DND - Existing LED Exit	4
Public Safety Complex	2248	1	508	100	Warehouse	Emergency Egress WP	Incandescent / N/A	5	DND - Existing Emergency Egress	5
Public Safety Complex	2249	1	509	101	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Public Safety Complex	2250	1	510	102	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Public Safety Complex	2251	1	511	103	Storage - Equipment	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Public Safety Complex	2252	1	512	Exterior	Exterior	Wall Pack	150w MH / HID-150	11	Replace fixture with LED Wall Pack (35w / 4655lm)	11
Supervisor of Elections	2253	1	1	Room	Lobby Area - Main	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Supervisor of Elections	2254	1	2	Room	Lobby Area - Main	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Supervisor of Elections	2255	1	3	Room	Lobby Area - Main	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2256	1	4	Room	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Supervisor of Elections	2257	1	5	Room	Workroom	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Supervisor of Elections	2258	1	6	Room	Workroom	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2259	1	7	Room	Training Room	2x4 Troffer	Integral LED / Integral LED Driver	12	DND - Existing LED fixture	12
Supervisor of Elections	2260	1	8	Room	Training Room	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2261	1	9	Room	Training Room	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Supervisor of Elections	2262	1	10	Room	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Supervisor of Elections	2263	1	11	Room	Waiting Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	8	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	8
Supervisor of Elections	2264	1	12	Room	Waiting Room	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Supervisor of Elections	2265	1	13	Room	Waiting Room	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2266	1	14	Room	Waiting Room	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Supervisor of Elections	2267	1	15	Room	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Supervisor of Elections	2268	1	16	Room	Office - Admin Area	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2269	1	17	Room	Office - Admin Area	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Supervisor of Elections	2270	1	18	Room	Warehouse	8' Strip	F32T8 / 4L Electronic	13	Retrofit fixture with (4) 4' T8 LED Linear Tube and Normal Power LED Driver	13
Supervisor of Elections	2271	1	19	Room	Warehouse	Emergency Egress WP	Incandescent / N/A	2	DND - Existing Emergency Egress	2
Supervisor of Elections	2272	1	20	Room	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Supervisor of Elections	2273	1	21	Room	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Supervisor of Elections	2274	1	22	Room	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Supervisor of Elections	2275	1	23	Room	Storage - General	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Supervisor of Elections	2276	1	24	Room	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Supervisor of Elections	2277	1	25	Room	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Supervisor of Elections	2278	1	27	Room	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Supervisor of Elections	2279	1	28	Room	Corridor / Hallway	2x2 Rec. Acrylic	F32T8/U / 2L Electronic	1	Retrofit fixture with (2) 4' T8U LED Linear Tube and Normal Power LED Driver	1
Supervisor of Elections	2280	1	29	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Supervisor of Elections	2281	1	30	Room	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2282	1	31	Room	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Supervisor of Elections	2283	1	32	Room	Conference Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3

Supervisor of Elections	2284	1	33	Room	Office - Private	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Supervisor of Elections	2285	1	34	Room	Workroom	2x4 Rec. Acrylic	F32T8 / 3L Electronic	6	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Supervisor of Elections	2286	1	35	Room	Workroom	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Supervisor of Elections	2287	1	36	Room	Break / Lounge	2x4 Rec. Acrylic	F32T8 / 3L Electronic	4	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Supervisor of Elections	2288	1	37	Room	Electrical / Mech	4' Wrap	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Supervisor of Elections	2289	1	38	Room	Custodial Closet	2x4 Rec. Acrylic	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Supervisor of Elections	2290	1	39	Room	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Supervisor of Elections	2291	1	40	Room	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Supervisor of Elections	2292	1	41	Room	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Supervisor of Elections	2293	1	42	Room	Storage - Records	8' Strip	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Supervisor of Elections	2294	1	43	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Supervisor of Elections	2295	1	44	Room	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Supervisor of Elections	2296	1	45	Room	Office - Admin Area	2x4 Rec. Acrylic	F32T8 / 3L Electronic	7	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	7
Supervisor of Elections	2297	1	46	Room	Office - Admin Area	Recessed Can 8"	75w Incandescent / N/A	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Supervisor of Elections	2298	1	47	Room	Office - Admin Area	Recessed Can 8"	75w Incandescent / N/A	5	Retrofit fixture with 8" LED Recessed Can Kit (16w / 1600lm)	5
Supervisor of Elections	2299	1	48	Room	Vestible / Foyer	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Supervisor of Elections	2300	1	50	Room	Vestible / Foyer	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Supervisor of Elections	2301	1	51	Room	Vestible / Foyer	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2302	1	52	Room	Corridor / Hallway	2x4 Rec. Acrylic	F32T8 / 3L Electronic	3	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	3
Supervisor of Elections	2303	1	53	Room	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Supervisor of Elections	2304	1	54	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3

Supervisor of Elections	2305	1	55	Room	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Supervisor of Elections	2306	1	56	Room	Corridor / Hallway	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Supervisor of Elections	2307	1	57	Room	Mechanical Room	Keyless	CFL 23w Screw In / Integral CFL	1	Relamp fixture with A19 LED	1
Supervisor of Elections	2308	1	58	Exterior	Exterior	Wall Pack (55w)	Integral LED / Integral LED Driver	10	DND - Existing LED fixture	10
Supervisor of Elections	2309	1	59	Exterior	Exterior	LED - Flood (50w)	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2310	1	1	Lobby	Lobby Area - Main	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	15	DND - Existing LED fixture	15
Willoughby Property Appraiser's Office	2311	1	2	Lobby	Lobby Area - Main	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	11	DND - Existing LED fixture	11
Willoughby Property Appraiser's Office	2312	1	3	Lobby	Lobby Area - Main	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Willoughby Property Appraiser's Office	2313	1	4	154	Conference Room	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	10	DND - Existing LED fixture	10
Willoughby Property Appraiser's Office	2314	1	5	154	Conference Room	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	7	DND - Existing LED fixture	7
Willoughby Property Appraiser's Office	2315	1	6	131	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2316	1	7	130	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2317	1	8	129	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2318	1	9	128	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2319	1	10	127	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2320	1	11	125	Server / Com Room	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2321	1	12	126	Workroom	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2322	1	13	155	Storage - General	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2323	1	14	124	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2324	1	15	123	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2

Willoughby Property Appraiser's Office	2325	1	16	122	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2326	1	17	121	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2327	1	18	120	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2328	1	19	119	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2329	1	20	118	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2330	1	21	117	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2331	1	22	116	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2332	1	23	115	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2333	1	24	114	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2334	1	25	113	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2335	1	26	111	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2336	1	27	110	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2337	1	28	112	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2338	1	29	RR5	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2339	1	30	RR4	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2340	1	31	152	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2341	1	32	Storage	Storage - General	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Willoughby Property Appraiser's Office	2342	1	33	Open Office	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	20	DND - Existing LED fixture	20
Willoughby Property Appraiser's Office	2343	1	38	Open Office	Office - Open Cubicals	2x4 Troffer w/battery	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4

Willoughby Property Appraiser's Office	2344	1	34	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer	Integral LED / Integral LED Driver	6	DND - Existing LED fixture	6
Willoughby Property Appraiser's Office	2345	1	35	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer w/battery	Integral LED / Integral LED Driver	7	DND - Existing LED fixture	7
Willoughby Property Appraiser's Office	2346	1	36	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Willoughby Property Appraiser's Office	2347	1	37	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Willoughby Property Appraiser's Office	2348	1	39	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer	Integral LED / Integral LED Driver	8	DND - Existing LED fixture	8
Willoughby Property Appraiser's Office	2349	1	40	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2350	1	41	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Willoughby Property Appraiser's Office	2351	1	42	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	2	DND - Existing LED Exit	2
Willoughby Property Appraiser's Office	2352	1	43	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2353	1	44	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2354	1	45	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Willoughby Property Appraiser's Office	2355	1	46	Hallway	Corridor / Hallway - Suite / Dept	2x4 Troffer w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2356	1	47	Hallway	Corridor / Hallway - Suite / Dept	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Willoughby Property Appraiser's Office	2357	1	48	RR1	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2358	1	49	RR1	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2359	1	50	RR2	Restroom - Public	4' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2360	1	51	RR2	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Willoughby Property Appraiser's Office	2361	1	52	RR3	Restroom - Public	4' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2362	1	53	RR3	Restroom - Public	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	5	DND - Existing LED fixture	5



Willoughby Property Appraiser's Office	2363	1	54	RR3	Restroom - Public	2' Vanity	Integral LED / Integral LED Driver	1	DND - Existing LED fixture	1
Willoughby Property Appraiser's Office	2364	1	55	RR3	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Willoughby Property Appraiser's Office	2365	1	56	109	Office - Private	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	8	DND - Existing LED fixture	8
Willoughby Property Appraiser's Office	2366	1	57	109	Office - Private	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	4	DND - Existing LED fixture	4
Willoughby Property Appraiser's Office	2367	1	58	108	Conference Room	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Willoughby Property Appraiser's Office	2368	1	59	108	Conference Room	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	5	DND - Existing LED fixture	5
Willoughby Property Appraiser's Office	2369	1	60	107	Office - Private	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	6	DND - Existing LED fixture	6
Willoughby Property Appraiser's Office	2370	1	61	107	Office - Private	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	5	DND - Existing LED fixture	5
Willoughby Property Appraiser's Office	2371	1	62	Open Office	Office - Open Cubicals	LED - Recessed Can 10" (Retro)	LED (Screw In / Plug In) / N/A	12	DND - Existing LED fixture	12
Willoughby Property Appraiser's Office	2372	1	63	Open Office	Office - Open Cubicals	LED - Recessed Can 8" (Retro)	LED (Screw In / Plug In) / N/A	12	DND - Existing LED fixture	12
Willoughby Property Appraiser's Office	2373	1	64	Open Office	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby Property Appraiser's Office	2374	1	65	Hallway	Corridor / Hallway	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Willoughby Property Appraiser's Office	2375	1	66	Hallway	Corridor / Hallway	2x4 Troffer w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED fixture	3
Willoughby Property Appraiser's Office	2376	1	67	Hallway	Corridor / Hallway	Exit Sign w/battery	Integral LED / Integral LED Driver	3	DND - Existing LED Exit	3
Willoughby Property Appraiser's Office	2377	1	68	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	13	DND - Existing LED fixture	13
Willoughby Property Appraiser's Office	2378	1	69	Exterior	Exterior	LED - Recessed Can 10"	Integral LED / Integral LED Driver	7	DND - Existing LED fixture	7
Willoughby Property Appraiser's Office	2379	1	70	Exterior	Exterior	LED - Wall Sconce (SCPS)	LED (Screw In / Plug In) / N/A	2	DND - Existing LED fixture	2
Willoughby MPO Office	2380	1	1	Open Office/Lobby	Office - Open Cubicals	2x4 Troffer	Integral LED / Integral LED Driver	9	DND - Existing LED fixture	9
Willoughby MPO Office	2381	1	2	Open Office/Lobby	Office - Open Cubicals	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1

Willoughby MPO Office	2382	1	3	Open Office/Lobby	Office - Open Cubicals	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Willoughby MPO Office	2383	1	4	Office	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby MPO Office	2384	1	5	Office	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby MPO Office	2385	1	6	Restroom	Restroom - Public	LED - Vanity (Retro)	LED (Screw In / Plug In) / N/A	1	DND - Existing LED fixture	1
Willoughby MPO Office	2386	1	7	Vestibule	Vestible / Foyer	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby MPO Office	2387	1	8	Office	Office - Private	2x4 Troffer	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Willoughby MPO Office	2388	1	9	Breakroom	Break / Lounge	2x4 Troffer	Integral LED / Integral LED Driver	2	DND - Existing LED fixture	2
Willoughby MPO Office	2389	1	10	Breakroom	Break / Lounge	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Willoughby MPO Office	2390	1	11	Breakroom	Break / Lounge	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Willoughby MPO Office	2391	1	12	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	5	DND - Existing LED fixture	5
Willoughby MPO Office	2392	1	13	Exterior	Exterior	LED - Recessed Can 8"	Integral LED / Integral LED Driver	4	DND - Existing LED fixture	4
Witham Field Customs Building	2393	1	1	Customs processing	Warehouse	2x4 Rec. Volumetric	F32T8 / 2L Electronic	6	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	6
Witham Field Customs Building	2394	1	2	Customs processing	Warehouse	Recessed Can 10" - Horz	CFL 26w PL / CFL	10	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm) w/10" Goof Ring	10
Witham Field Customs Building	2395	1	3	Customs processing	Warehouse	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Witham Field Customs Building	2396	1	6	Customs processing	Warehouse	2x4 Rec. Volumetric w/Battery	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	2
Witham Field Customs Building	2397	1	4	106	Custodial Closet	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2398	1	5	104	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Witham Field Customs Building	2399	1	7	103	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	4	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	4
Witham Field Customs Building	2400	1	8	103	Office - Admin Area	2x4 Rec. Volumetric w/Battery	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Witham Field Customs Building	2401	1	9	103A	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2402	1	10	103A	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1

Witham Field Customs Building	2403	1	11	Room	Waiting Room	2x4 Rec. Volumetric	F32T8 / 2L Electronic	2	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Witham Field Customs Building	2404	1	12	Room	Waiting Room	2x4 Rec. Volumetric w/Battery	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Witham Field Customs Building	2405	1	13	Room	Waiting Room	Recessed Can 10" - Horz	CFL 26w PL / CFL	6	Retrofit fixture with 8" LED Recessed Can Kit (23w / 2300lm) w/10" Goof Ring	6
Witham Field Customs Building	2406	1	14	Room	Waiting Room	Exit Sign w/battery	Integral LED / Integral LED Driver	1	DND - Existing LED Exit	1
Witham Field Customs Building	2407	1	15	A	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2408	1	16	A	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Witham Field Customs Building	2409	1	17	B	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2410	1	18	B	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Witham Field Customs Building	2411	1	19	111	Vestible / Foyer	4' Tamper Proof	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Witham Field Customs Building	2412	1	20	112	Holding Cell	4' Tamper Proof	F32T8 / 3L Electronic	2	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	2
Witham Field Customs Building	2413	1	21	110	Holding Cell	4' Tamper Proof	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2414	1	22	109	Holding Cell	4' Tamper Proof	F32T8 / 3L Electronic	1	Retrofit fixture with (3) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2415	1	23	107	Storage - General	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2416	1	25	105	Waiting Room	2x4 Rec. Volumetric	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2417	1	26	105	Waiting Room	2x4 Rec. Volumetric w/Battery	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver - Emergency Battery Back Up	1
Witham Field Customs Building	2418	1	27	105	Office - Admin Area	2x4 Rec. Volumetric	F32T8 / 2L Electronic	5	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	5
Witham Field Customs Building	2419	1	28	105B	Server / Com Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
Witham Field Customs Building	2420	1	29	105A	Restroom - Public	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1

Witham Field Customs Building	2421	1	30	105A	Restroom - Public	Emergency Egress WP	Incandescent / N/A	1	DND - Existing Emergency Egress	1
Witham Field Customs Building	2422	1	31	Mechanical	Mechanical Room	2x4 Rec. Acrylic	F32T8 / 2L Electronic	1	Retrofit fixture with (2) 4' T8 LED Linear Tube and Normal Power LED Driver	1
100% Savings								8168		8168

## Appendix E Water Line by Line

Project	Building	Floor	Location	Type	QTY	Pre Retrofit CODE	Pre-Retrofit	Post Retrofit Code	Retrofit Description
Martin County	Administrative Center	4	Men Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	4	Men Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	4	Men Gang Across from elevator	URINAL	2	WMU TS c1.0F/v.5F SS	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Administrative Center	4	Men Gang Across from elevator	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	4	Women Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	4	Women Gang Across from elevator	WATER CLOSET	2	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	4	Women Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	4	Women Gang Across from elevator	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit

Martin County	Administrative Center	4	Kitchen	FAUCET	1	AER 1.25F	1.25 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	4	Workshop Room	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Administrative Center	4	City Attorney Breakroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	3	Men Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	3	Men Gang Across from elevator	WATER CLOSET	2	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	3	Men Gang Across from elevator	URINAL	2	WMU TS c1.0F/v.5F SS	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Administrative Center	3	Men Gang Across from elevator	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Administrative Center	3	Women Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Administrative Center	3	Women Gang Across from elevator	WATER CLOSET	3	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	3	Women Gang Across from elevator	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit

Martin County	Administrative Center	3	Kitchen	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	2	Men Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	2	Men Gang Across from elevator	WATER CLOSET	2	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	2	Men Gang Across from elevator	URINAL	2	WMU TS c1.0F/v.5F SS	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Administrative Center	2	Men Gang Across from elevator	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	2	Women Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	2	Women Gang Across from elevator	WATER CLOSET	3	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	2	Women Gang Across from elevator	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	2	Kitchen	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	2	Back Office Kitchen	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	1	Men Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top	NR	No Retrofit



							Spud - Exposed Side Mount 9vBt Diaphragm		
Martin County	Administrative Center	1	Men Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	1	Men Gang Across from elevator	URINAL	2	WMU TS c1.0F/v.125F SS	1.0 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Administrative Center	1	Men Gang Across from elevator	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Administrative Center	1	Women Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	1	Women Gang Across from elevator	WATER CLOSET	2	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	1	Women Gang Across from elevator	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Administrative Center	1	Women Gang Across from elevator	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Administrative Center	1	Kitchen	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Administrative Center	1	Parks n Rec Kitchen	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit

Martin County	Blake Library	2	Restrooms near back stairwell door	WATER CLOSET	2	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Blake Library	2	Restrooms near back stairwell door	FAUCET	2	AER 2.5F	2.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	2	Staff Kitchen	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	2	Learning Room	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	2	Restroom back hallway	WATER CLOSET	2	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Blake Library	2	Restroom back hallway	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	2	Staff Office Sink	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	2	Library Restroom	WATER CLOSET	1	FM TS c1.6F/v3.5F <6vBt D	1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Blake Library	2	Library Restroom	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Blake Library	2	Library Restroom	FAUCET	2	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	1	Restrooms in staff area	WATER CLOSET	2	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side	NR	No Retrofit

							Mount 9vBt Diaphragm		
Martin County	Blake Library	1	Restrooms in staff area	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	1	Staff Office Sink	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Blake Library	1	Men Gang	WATER CLOSET	2	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Blake Library	1	Men Gang	URINAL	2	WMU TS c1.0F/v.5F SS	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Blake Library	1	Men Gang	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	1	Men Gang	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Blake Library	1	Women Gang	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Blake Library	1	Women Gang	WATER CLOSET	3	WM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Blake Library	1	Women Gang	FAUCET	3	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Blake Library	1	Women Gang	FAUCET	1	AER 0.5F	0.5 GPM Faucet	NR	No Retrofit

							Aerator Female		
Martin County	Building Department	1	Staff Restrooms outside 116	WATER CLOSET	2	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	Building Department	1	Staff Restrooms outside 116	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Building Department	1	Women Gang at Entry	WATER CLOSET	3	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Building Department	1	Women Gang at Entry	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Building Department	1	Men Gang at Entry	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Building Department	1	Men Gang at Entry	URINAL	2	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Building Department	1	Men Gang at Entry	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Building Department	1	116	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Building Department	1	Back Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Building Maintenance Shop	2	Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water	NR	No Retrofit

							Closet Top Spud - Exposed		
Martin County	Building Maintenance Shop	2	Restroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Building Maintenance Shop	1	Shop Restroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Building Maintenance Shop	1	Shop Restroom	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Building Maintenance Shop	2	Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Citrus Grove Park	1	Concession Men	WATER CLOSET	2	WM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Citrus Grove Park	1	Concession Men	URINAL	1	WMU TS .125F/v.125F	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Citrus Grove Park	1	Concession Men	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Citrus Grove Park	1	Concession women	WATER CLOSET	3	WM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Citrus Grove Park	1	Concession women	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Citrus Grove Park	1	Concession	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Citrus Grove Park	1	Concession	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Citrus Grove Park	1	103	FAUCET	1	AER 4.0F	4.0 GPM Faucet	RFAK1.5	1.5 GPM Kitchen

							Aerator Female		Faucet Aerator
Martin County	Citrus Grove Park	1	104	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Citrus Grove Park	1	104	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cob Building	1	113	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Cob Building	1	Kitchen in Jury Room	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Cob Building	1	B117	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Cob Building	1	B117	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	1	B120	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Cob Building	1	B120	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	1	Staff East Wing Office	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Cob Building	1	Staff East Wing Office	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cob Building	1	Staff East Wing Entry	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Cob Building	1	Staff East Wing Entry	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cob Building	2	B204	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud -	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit

							Exposed Side Mount 9vBt Diaphragm		
Martin County	Cob Building	2	B204	WATER CLOSET	1	FM TS c1.6F/v2.4F 21vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	2	B204	URINAL	1	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Cob Building	2	B204	FAUCET	2	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	1	B103	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	1	B103	WATER CLOSET	2	FM TS c1.6F/v1.6F SS 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 21vBt Diaphragm	NR	No Retrofit
Martin County	Cob Building	1	B103	FAUCET	3	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	1	B104	WATER CLOSET	1	FM TS c1.6F/v3.5F SS 9vBt D	1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	1	B104	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 21vBt Diaphragm	NR	No Retrofit
Martin County	Cob Building	1	B104	URINAL	1	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud -	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit



							Exposed Side Mount		
Martin County	Cob Building	1	B104	FAUCET	2	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	2	B202	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	2	B202	WATER CLOSET	2	FM TS c1.6F/v1.6F SS 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 21vBt Diaphragm	NR	No Retrofit
Martin County	Cob Building	2	B202	FAUCET	3	AER 1.25F	1.25 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	1	Kitchenette across from 216	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Cob Building	2	B214	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Cob Building	2	B214	FAUCET	1	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	2	B216	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Cob Building	2	B216	FAUCET	1	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	1	Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Cob Building	2	B234	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit

Martin County	Cob Building	2	B234	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	2	B233	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Cob Building	2	B233	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	1	Internal Auditor Office	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Cob Building	2	Internal Audit Office	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Cob Building	2	Internal Audit Office	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	3	B303	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Cob Building	3	B303	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 21vBt Diaphragm	NR	No Retrofit
Martin County	Cob Building	3	B303	URINAL	1	WMU TS c1.0F/v1.0F	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Cob Building	3	B303	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cob Building	3	B301	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	3	B301	WATER CLOSET	2	FM TS c1.6F/v2.4F 21vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit

							Spud - Exposed 21vBt Diaphragm		
Martin County	Cob Building	3	B301	FAUCET	3	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	3	B310	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cob Building	3	Financial Serv Entry	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Cob Building	3	Financial Serv Entry	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	4	B403	WATER CLOSET	1	FM TS c1.6F/v3.5F SS 9vBt D	1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	4	B403	WATER CLOSET	1	FM TS c1.6F/v2.4F 21vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	4	B403	URINAL	1	WMU TS c1.0F/v1.0F	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Cob Building	4	B403	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	4	B401	WATER CLOSET	1	FM TS c1.6F/v3.5F SS 9vBt D	1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cob Building	4	B401	WATER CLOSET	2	FM TS c1.6F/v2.4F 21vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit

Martin County	Cob Building	4	B401	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	4	Conference Room	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cob Building	4	Conference Room	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Cob Building	4	Conference Room	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cob Building	4	Attorneys Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	County Line Park - Community Center	1	Men	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	County Line Park - Community Center	1	Men	URINAL	1	WMU TS c1.0F/v1.0F TMI	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	County Line Park - Community Center	1	Men	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	County Line Park - Community Center	1	Women	WATER CLOSET	1	FMTT c3.5F/v3.5F	3.5 GPF/3.5 GPF Floor Mount Tank Type Water Closet	NFMTT1.28	1.28 GPF Floor Mount Tank Type Toilet with Gravity Tank and Bowl STD w/ Seat minus cover
Martin County	County Line Park - Community Center	1	Women	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Court Holding	1	Maintenance Shop	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Court Holding	1	Maintenance Shop	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Court Holding	1	Maintenance Shop	FAUCET	1	AER 2.0F	2.0 GPM Faucet	RFAK1.5	1.5 GPM Kitchen

							Aerator Female		Faucet Aerator
Martin County	Court Holding	1	Maintenance Shop	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Court Holding	1	Maintenance Shop Back Hall	WATER CLOSET	1	FM TS c3.5F/v3.5F 9vBt D	3.5 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NFMFT1.28	1.28 GPF Floor Mount Top Spud Toilet STD, Diaphragm Flush Valve w/Seat minus Cover
Martin County	Court Holding	1	Maintenance Shop Back Hall	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Court Holding	1	Staff Restroom in Prisoner holding	WATER CLOSET	1	FM TS c1.6F/v3.5F SS 9vBt D	1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Court Holding	1	Staff Restroom in Prisoner holding	FAUCET	1	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Court Holding	1	Holding Cells	WATER CLOSET	8	FMSS RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Floor Mount Stainless Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Courthouse	1	A127	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	1	A127	WATER CLOSET	1	FM TS c1.6F/v3.5F SS 9vBt D	1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Courthouse	1	A127	URINAL	1	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Courthouse	1	A127	FAUCET	3	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator

Martin County	Courthouse	1	A126	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	1	A126	WATER CLOSET	2	FM TS c1.6F/v2.4F 21vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Courthouse	1	A126	FAUCET	3	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	1	Sheriffs Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Courthouse	1	Sheriffs Restroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	1	Kitchenette	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Courthouse	1	A150	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Courthouse	1	A150	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	1	146	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Courthouse	1	146	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	1	146	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit

Martin County	Courthouse	1	146	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Courthouse	1	146	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	2	A212	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	2	A212	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Courthouse	2	A212	URINAL	1	WMU TS c1.0F/v.5F SS	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Courthouse	2	A212	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	2	A213	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	2	A213	WATER CLOSET	2	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Courthouse	2	A213	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A312	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top	NR	No Retrofit



							Spud - Exposed Side Mount 9vBt Diaphragm		
Martin County	Courthouse	3	A312	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Courthouse	3	A312	URINAL	1	WMU TS c1.0F/v.5F SS	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Courthouse	3	A312	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A313	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	3	A313	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Courthouse	3	A313	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	2	A218	WATER CLOSET	2	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	2	A218	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	1	Court 4 Jury Room	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Courthouse	2	A225	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud -	NR	No Retrofit

							Exposed 9vBt Diaphragm		
Martin County	Courthouse	2	A225	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	2	A225	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A320	WATER CLOSET	2	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	3	A320	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A320	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Courthouse	3	A343	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	3	A343	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A343	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Courthouse	3	A346	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Courthouse	3	A346	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A355	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Courthouse	3	A355	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A355	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator

Martin County	Courthouse	3	A362	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Courthouse	3	A362	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A362	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Courthouse	3	A365-367	WATER CLOSET	3	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Courthouse	3	A365-367	FAUCET	3	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A365-367	FAUCET	3	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Courthouse	3	A343	WATER CLOSET	1	FM TS c1.28F/v1.28F 9vBt	1.28 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt	NR	No Retrofit
Martin County	Courthouse	3	A343	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A343	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Courthouse	3	A346	WATER CLOSET	1	FM TS c1.28F/v1.28F 9vBt	1.28 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt	NR	No Retrofit
Martin County	Courthouse	3	A346	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	3	A346	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Courthouse	2	A249-A268	WATER CLOSET	4	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Courthouse	2	A249-A268	FAUCET	4	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	2	A249-A268	FAUCET	4	AER 4.0F	4.0 GPM Faucet	RFAK1.5	1.5 GPM Kitchen

							Aerator Female		Faucet Aerator
Martin County	Courthouse	2	A239	WATER CLOSET	1	FM TS c1.28F/v1.28F 9vBt	1.28 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt	NR	No Retrofit
Martin County	Courthouse	2	A239	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse	2	A241	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Courthouse	2	A241	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Courthouse Cultural Center (Historical Designation)	1	Closet Breakroom	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Courthouse Cultural Center (Historical Designation)	1	Entry Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Courthouse Cultural Center (Historical Designation)	1	Entry Restroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Courthouse Cultural Center (Historical Designation)	2	Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Courthouse Cultural Center (Historical Designation)	2	Gallery Women	WATER CLOSET	1	FMTT c3.5F/v3.5F	3.5 GPF/3.5 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Courthouse Cultural Center (Historical Designation)	2	Gallery Women	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Courthouse Cultural Center (Historical Designation)	2	Gallery Women	FAUCET	2	AER 4.0F	4.0 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cummings Library	1	Visitor Restrooms in library area	WATER CLOSET	2	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit

Martin County	Cummings Library	1	Visitor Restrooms in library area	FAUCET	2	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cummings Library	1	Staff restroom in library area	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Cummings Library	1	Staff restroom in library area	FAUCET	1	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Cummings Library	1	Visitor Restroom at Entry	WATER CLOSET	2	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cummings Library	1	Visitor Restroom at Entry	WATER CLOSET	4	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Cummings Library	1	Visitor Restroom at Entry	FAUCET	6	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cummings Library	1	Visitor Restrooms at Entry	WATER CLOSET	2	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cummings Library	1	Visitor Restrooms at Entry	WATER CLOSET	4	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Cummings Library	1	Visitor Restrooms at Entry	FAUCET	6	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cummings Library	1	107A	WATER CLOSET	1	FM TS c1.6F/v2.4F 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud -	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit

							Exposed 9vBt Diaphragm		
Martin County	Cummings Library	1	107A	WATER CLOSET	1	FM TS c1.6F/v2.4F 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cummings Library	1	107A	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Cummings Library	1	108B	WATER CLOSET	1	FM TS c1.6F/v2.4F 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Cummings Library	1	108B	URINAL	1	WMU TS c1.0F/v1.0F	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Cummings Library	1	108B	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Cummings Library	2	205B	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Cummings Library	2	205B	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Cummings Library	2	205B	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Cummings Library	2	206B	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit

Martin County	Cummings Library	2	206B	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Cummings Library	2	206B	URINAL	1	WMU TS c1.0F/v1.0F	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Cummings Library	2	206B	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Cummings Library	2	Exploration Lab	FAUCET	2	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Cummings Library	2	Exploration Lab	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Cummings Library	1	Staff Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Field Operations	1	Restroom 1	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Field Operations	1	Restroom 1	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Field Operations	1	Restroom 2	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Field Operations	1	Restroom 2	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Field Operations	1	Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Rescue Lifestar Hangar	1	Kitchen	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Rescue Lifestar Hangar	1	Restroom next to common area	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit



Martin County	Fire Rescue Lifestar Hangar	1	Restroom next to common area	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Rescue Lifestar Hangar	1	Restroom next to common area	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Rescue Lifestar Hangar	1	Restroom next to common area	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Rescue Lifestar Hangar	1	Hangar	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Rescue Lifestar Hangar	1	Restroom in Hangar	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Fire Rescue Lifestar Hangar	1	Restroom in Hangar	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Rescue Lifestar Hangar	1	Restroom in Hangar	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Rescue Lifestar Hangar	1	Restroom in Hangar	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 16 Kitchen	1	Kitchen	FAUCET	2	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Station 16 Kitchen	1	Kitchen	FAUCET	1	AER 1.0F	1.0 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Fire Station 16 Restroom	1	Restroom close to entry	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 16 Restroom	1	Restroom close to entry	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 16 Restroom	1	Restroom close to entry	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 16 Restrooms near gym	1	Restroom	WATER CLOSET	2	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 16 Restrooms near gym	1	Restroom	FAUCET	2	AER 2.0F	2.0 GPM Faucet	RFA0.5	0.5 GPM Faucet Aerator

							Aerator Female		
Martin County	Fire Station 16 Restrooms near gym	1	Restroom	SHOWER	2	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 16 Shop	1	Shop	FAUCET	1	AER 3.0F	3.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Station 21	1	Restroom next to 128	WATER CLOSET	1	WM TS c1.6F/v1.28F <6vBt D	1.6 GPF/1.28 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 21	1	Restroom next to 128	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 21	1	Restrooms next to kitchen	WATER CLOSET	3	WM TS c1.6F/v2.4F SS <6vBt D	1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Side Mount <6vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Fire Station 21	1	Restrooms next to kitchen	FAUCET	3	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 21	1	Restrooms next to kitchen	SHOWER	3	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 21	1	Kitchen	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Station 21	1	127	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Station 21	1	101	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Station 21	1	EMS Toilet	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Fire Station 21	1	EMS Toilet	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 21	1	EMS Toilet	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit

Martin County	Fire Station 22	1	1-114	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Fire Station 22	1	1-114	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 22	1	1-114	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 22	1	1-114	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 22	1	1-115	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Fire Station 22	1	1-115	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Fire Station 22	1	1-115	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 22	1	1-115	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 22	1	Kitchen	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 23	1	130	WATER CLOSET	1	WM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 23	1	130	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 23	1	130	SHOWER	1	SH 4.0F	4.0 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 23	1	123	WATER CLOSET	1	WM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit

Martin County	Fire Station 23	1	123	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 23	1	123	SHOWER	1	SH 4.0F	4.0 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 23	1	123	WATER CLOSET	1	FM TS c1.28F/v1.28F SS 9vBt D	1.28 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 23	1	123	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Fire Station 24	1	172	WATER CLOSET	2	WM TS c1.6F/v1.28F <6vBt D	1.6 GPF/1.28 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 24	1	172	URINAL	2	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Fire Station 24	1	172	FAUCET	3	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 24	1	172	SHOWER	2	SH 4.0F	4.0 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 24	1	172	WATER CLOSET	1	WM TS c1.6F/v1.28F <6vBt D	1.6 GPF/1.28 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 24	1	172	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 24	1	172	SHOWER	1	SH 4.0F	4.0 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 24	1	Kitchen	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Fire Station 30	1	Entry Lounge	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator

Martin County	Fire Station 30	1	Kitchen	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Fire Station 30	1	115	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 30	1	115	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 30	1	115	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Fire Station 30	1	115	SHOWER	1	SH 1.75F	1.75 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 30	1	114	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 30	1	114	URINAL	1	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Fire Station 30	1	114	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 30	1	114	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 30	1	114	SHOWER	1	SH 1.75F	1.75 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 30	1	114	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 30	1	119B	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 30	1	119B	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator

Martin County	Fire Station 32	1	Kitchen	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Station 32	1	Kitchen	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Fire Station 32	1	Restroom	WATER CLOSET	2	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Fire Station 32	1	Restroom	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 32	1	Restroom	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 32	1	Restroom	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 32	1	Lounge Restroom	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Fire Station 32	1	Lounge Restroom	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Fire Station 32	1	Lounge Restroom	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Fire Station 32	1	Lounge Restroom	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Halpatokee Regional Park	1	Women	WATER CLOSET	3	FM TS c1.6F/v2.4F TMI 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Halpatokee Regional Park	1	Women	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Halpatokee Regional Park	1	Men	WATER CLOSET	2	FM TS c1.6F/v2.4F TMI 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit

							(Integral) 9vBt Diaphragm		
Martin County	Halpatokee Regional Park	1	Men	URINAL	1	WMU TS c0.5F/v0.5F TMI 9vBt	0.5 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral) 9" Vacuum Breaker	NR	No Retrofit
Martin County	Halpatokee Regional Park	1	Men	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Hobe Sound Civic Center - Community Center	1	Men	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Hobe Sound Civic Center - Community Center	1	Men	WATER CLOSET	1	FMTT c3.5F/v3.5F	3.5 GPF/3.5 GPF Floor Mount Tank Type Water Closet	NFMTT1.28	1.28 GPF Floor Mount Tank Type Toilet with Gravity Tank and Bowl STD w/ Seat minus cover
Martin County	Hobe Sound Civic Center - Community Center	1	Men	URINAL	1	WMU TS c1.0F/v1.0F	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Hobe Sound Civic Center - Community Center	1	Men	FAUCET	1	AER 1.25F	1.25 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Hobe Sound Civic Center - Community Center	1	Men	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Hobe Sound Civic Center - Community Center	1	Women	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Hobe Sound Civic Center - Community Center	1	Women	WATER CLOSET	2	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Hobe Sound Civic Center - Community Center	1	Women	FAUCET	1	AER 1.25F	1.25 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Hobe Sound Civic Center - Community Center	1	Women	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit



Martin County	Hobe Sound Civic Center - Community Center	1	Kitchen	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Hoke Library	1	Men	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Hoke Library	1	Men	URINAL	1	WMU TS c1.0F/v1.5F SS	1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Hoke Library	1	Men	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Hoke Library	1	Men	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Hoke Library	1	Women	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Hoke Library	1	Women	WATER CLOSET	1	FM TS c1.6F/v1.28F SS <6vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount <6vBt Diaphragm	NR	No Retrofit
Martin County	Hoke Library	1	Women	WATER CLOSET	1	FM TS c1.28F/v1.28F SS 9vBt D	1.28 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Hoke Library	1	Women	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Hoke Library	1	Women	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Hoke Library	1	Breakroom	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator

Martin County	Hoke Library	1	Restroom	WATER CLOSET	1	FM TS c1.6F/v1.28F SS 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Hoke Library	1	Restroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	HOLT ADMINISTRATION	1	Breakroom	WATER CLOSET	1	FM TS c3.5F/v2.4F SS 21vBt D	3.5 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 21vBt Diaphragm	NFMFT1.28	1.28 GPF Floor Mount Top Spud Toilet STD, Diaphragm Flush Valve w/Seat minus Cover
Martin County	HOLT ADMINISTRATION	1	Breakroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	HOLT ADMINISTRATION	1	Breakroom	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	HOLT ADMINISTRATION	1	Lab Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	HOLT ADMINISTRATION	1	Lab Restroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	HOLT ADMINISTRATION	1	Back Office Restroom	WATER CLOSET	1	FM TS c1.6F/v1.6F SS <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount <6vBt Diaphragm	NR	No Retrofit
Martin County	HOLT ADMINISTRATION	1	Back Office Restroom	URINAL	1	WMU TS c1.0F/v.5F SS	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	HOLT ADMINISTRATION	1	Back Office Restroom	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	HOLT ADMINISTRATION	1	Back Office Restroom 2	WATER CLOSET	1	FM TS c1.6F/v1.6F SS <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud -	NR	No Retrofit

							Exposed Side Mount <6vBt Diaphragm		
Martin County	HOLT ADMINISTRATION	1	Back Office Restroom 2	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indian Riverside Park - Sailing Center Building	1	Exterior Restroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Indian Riverside Park - Sailing Center Building	1	Exterior Restroom	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indian Riverside Park - Sailing Center Building	2	Upstairs Bar	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Indian Riverside Park - Sailing Center Building	2	Exterior Restroom	WATER CLOSET	3	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Indian Riverside Park - Sailing Center Building	2	Exterior Restroom	FAUCET	3	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indian Riverside Park - Sailing Center Building	1	Exterior Shower	SHOWER	4	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Indian Riverside Park - Sailing Center Building	1	Out building Restroom Men	WATER CLOSET	1	WM RS-CN c1.6F/v2.4F D	1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Indian Riverside Park - Sailing Center Building	1	Out building Restroom Men	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indian Riverside Park - Sailing Center Building	1	Out building Restroom Women	WATER CLOSET	1	WM RS-CN c1.6F/v2.4F D	1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Indian Riverside Park - Sailing Center Building	1	Out building Restroom Women	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indian Riverside Park-Children'S Museum	1	Men Gang Entry	WATER CLOSET	2	FM TS c1.6F/v1.6F 9vBt PT	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Piston	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	1	Men Gang Entry	WATER CLOSET	2	FM TS c1.6F/v1.6F 9vBt PT	1.6 GPF/1.6 GPF Floor Mount Flush	NR	No Retrofit

							Valve Water Closet Top Spud - Exposed 9vBt Piston		
Martin County	Indian Riverside Park-Children'S Museum	1	Men Gang Entry	URINAL	2	WMU TS	0.0 GPF/0.0 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	1	Men Gang Entry	FAUCET	1	AER 1.5F FS	1.5 GPM Faucet Aerator Faucet Sensor Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indian Riverside Park-Children'S Museum	1	Men Gang Entry	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	1	Men Gang Entry	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	1	Women Gang Entry	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt PT	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Piston	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	1	Women Gang Entry	WATER CLOSET	7	FM TS c1.6F/v1.6F 9vBt PT	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Piston	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	1	Women Gang Entry	FAUCET	1	AER 1.5F FS	1.5 GPM Faucet Aerator Faucet Sensor Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indian Riverside Park-Children'S Museum	1	Women Gang Entry	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	1	Women Gang Entry	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Indian Riverside Park-Children'S Museum	2	Staff Area	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Indiantown Annex	1	Entry Women's	WATER CLOSET	1	FM TS c1.6F/v2.4F <6vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit

							<6vBt Diaphragm		
Martin County	Indiantown Annex	1	Entry Women's	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indiantown Annex	1	Entry men's	WATER CLOSET	1	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Indiantown Annex	1	Entry men's	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indiantown Annex	1	DMV Gang	WATER CLOSET	1	FM TS c1.6F/v2.4F <6vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Indiantown Annex	1	DMV Gang	URINAL	1	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Indiantown Annex	1	DMV Gang	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indiantown Annex	1	DMV Gang	WATER CLOSET	2	FM TS c1.6F/v2.4F <6vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Indiantown Annex	1	DMV Gang	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Indiantown Annex	1	DMV Breakroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	INDIANTOWN EDUCATION CENTER	1	102	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	INDIANTOWN EDUCATION CENTER	1	102	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	INDIANTOWN EDUCATION CENTER	1	104	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank	NR	No Retrofit

							Type Water Closet		
Martin County	INDIANTOWN EDUCATION CENTER	1	104	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	36	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Indiantown Health Department	1	36	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	37	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Indiantown Health Department	1	37	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	Breakroom	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Indiantown Health Department	1	Doc Office	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	Exam Rooms	FAUCET	3	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Indiantown Health Department	1	Exam Rooms	FAUCET	3	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	13	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Indiantown Health Department	1	13	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	12	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor	NR	No Retrofit

							Mount Tank Type Water Closet Top Spud - Exposed		
Martin County	Indiantown Health Department	1	12	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	44	WATER CLOSET	2	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Indiantown Health Department	1	44	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Indiantown Health Department	1	2	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Indiantown Health Department	1	2	URINAL	1	WMU TS c1.0F/v1.5F SS	1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Indiantown Health Department	1	2	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Jensen Beach Communtiy Center	1	Women	WATER CLOSET	2	FM TS c1.6F/v2.4F 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Jensen Beach Communtiy Center	1	Women	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Jensen Beach Communtiy Center	1	Men	WATER CLOSET	1	FM TS c1.28F/v1.28F 9vBt D	1.28 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud -	NR	No Retrofit



							Exposed 9vBt Diaphragm		
Martin County	Jensen Beach Communtiy Center	1	Men	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Sensor Female	NR	No Retrofit
Martin County	Jensen Beach Communtiy Center	1	Breakroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Jensen Beach Ocean Rescue	1	Garage Bathroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Jensen Beach Ocean Rescue	1	Garage Bathroom	FAUCET	1	AER 1.25F	1.25 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Jensen Beach Ocean Rescue	1	Garage Bathroom	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Jensen Beach Ocean Rescue	2	Men's Bathroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Jensen Beach Ocean Rescue	2	Men's Bathroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Jensen Beach Ocean Rescue	2	Women's Bathroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Jensen Beach Ocean Rescue	2	Women's Bathroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Jensen Beach Ocean Rescue	2	Office	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Jensen Beach Park	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) <6vBt Diaphragm	NR	No Retrofit
Martin County	Jensen Beach Park	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit

Martin County	Jensen Beach Park	1	Men Gang	URINAL	1	WMU TS .125F/v.125F TMI	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	NR	No Retrofit
Martin County	Jensen Beach Park	1	Men Gang	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Jensen Beach Park	1	Men Gang	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Jensen Beach Park	1	Men Gang	SHOWER	6	SH 1.75F	1.75 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Jensen Beach Park	1	Women Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) <6vBt Diaphragm	NR	No Retrofit
Martin County	Jensen Beach Park	1	Women Gang	WATER CLOSET	2	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Jensen Beach Park	1	Women Gang	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Jensen Beach Park	1	Women Gang	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Jimmy Graham Park	1	Men	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Jimmy Graham Park	1	Men	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Jimmy Graham Park	1	Women	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water	NR	No Retrofit

							Closet Rear Spud - Concealed Diaphragm		
Martin County	Jimmy Graham Park	1	Women	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Jock Leighton Park	1	Men	WATER CLOSET	2	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Jock Leighton Park	1	Men	URINAL	1	WMU TS c0.5F/v0.5F	0.5 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Jock Leighton Park	1	Men	FAUCET	1	AER 3.0F	3.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Jock Leighton Park	1	Men	FAUCET	2	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Jock Leighton Park	1	Women	WATER CLOSET	1	FM TS c1.6F/v2.4F 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Jock Leighton Park	1	Women	WATER CLOSET	2	FM TS c1.6F/v3.5F D	1.6 GPF/3.5 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Jock Leighton Park	1	Women	FAUCET	3	AER 1.0F	1.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Jock Leighton Park	1	Concession	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	JV Reed Park	1	Men near fire station	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	JV Reed Park	1	Men near fire station	URINAL	1	WMU TS c1.0F/v1.0F TMI	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud -	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit

							Exposed Top Mount (Integral)		
Martin County	JV Reed Park	1	Men near fire station	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	JV Reed Park	1	Concession near fire station	FAUCET	1	AER 2.5F	2.5 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	JV Reed Park	1	Women near fire station	WATER CLOSET	1	FM TS c3.5F/v2.4F 9vBt D	3.5 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NFMFT1.28	1.28 GPF Floor Mount Top Spud Toilet STD, Diaphragm Flush Valve w/Seat minus Cover
Martin County	JV Reed Park	1	Women near fire station	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	JV Reed Park	1	Women near fire station	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	JV Reed Park	1	Women main gate	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	JV Reed Park	1	Women main gate	WATER CLOSET	2	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	JV Reed Park	1	Women main gate	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	JV Reed Park	1	Concession main gate	FAUCET	1	AER 2.5F	2.5 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator

Martin County	JV Reed Park	1	Men main gate	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	JV Reed Park	1	Men main gate	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	JV Reed Park	1	Men main gate	URINAL	1	WMU TS c1.0F/v1.0F TMI	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	JV Reed Park	1	Men main gate	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Lahti Library	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Lahti Library	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Lahti Library	1	Men Gang	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Lahti Library	1	Women Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Lahti Library	1	Women Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush	NR	No Retrofit

							Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm		
Martin County	Lahti Library	1	Women Gang	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Lahti Library	1	Community Room	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Lahti Library	1	119	WATER CLOSET	1	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Lahti Library	1	119	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Lahti Library	1	Children's Area	FAUCET	1	AER 2.2F FS	2.2 GPM Faucet Aerator Faucet Sensor Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Lahti Library	1	124	WATER CLOSET	1	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Lahti Library	1	124	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Lahti Library	1	Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Lamar Howard Park	1	Men	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Lamar Howard Park	1	Men	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	REFT 0.5	0.5 GPM 4in Centerset, Deck Mount, Faucet

Martin County	Lamar Howard Park	1	Women	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Lamar Howard Park	1	Women	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Lamar Howard Park - Cassidy Community Center	1	Lounge	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Lamar Howard Park - Cassidy Community Center	1	Women	WATER CLOSET	2	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Lamar Howard Park - Cassidy Community Center	1	Women	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Lamar Howard Park - Cassidy Community Center	1	Men	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Lamar Howard Park - Cassidy Community Center	1	Men	URINAL	1	WMU TS .125F/v.5F TMI	0.125 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	NR	No Retrofit
Martin County	Lamar Howard Park - Cassidy Community Center	1	Men	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Landfill Breakroom Building	1	Breakroom	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Landfill Hazmat/Transfer Station	1	Women's Gang	WATER CLOSET	1	WM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Landfill Hazmat/Transfer Station	1	Women's Gang	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Landfill Hazmat/Transfer Station	1	Women's Gang	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator



Martin County	Landfill Hazmat/Transfer Station	1	Women's Gang	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Landfill Hazmat/Transfer Station	1	Men's Locker	WATER CLOSET	1	WM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Landfill Hazmat/Transfer Station	1	Men's Locker	FAUCET	3	AER 1.5F FS		RFA0.5	0.5 GPM Faucet Aerator
Martin County	Landfill Hazmat/Transfer Station	1	Men's Locker	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Landfill Hazmat/Transfer Station	1	Men's Locker	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Landfill Hazmat/Transfer Station	1	Restroom	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Landfill Hazmat/Transfer Station	1	Restroom	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Landfill Hazmat/Transfer Station	1	Restroom	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	NR	No Retrofit
Martin County	Landfill Hazmat/Transfer Station	1	Break Area	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Landfill Maintenance Shop	1	Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Landfill Maintenance Shop	1	Restroom	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Landfill Maintenance Shop	1	Bathrooms Near Fueling Station	WATER CLOSET	2	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Landfill Maintenance Shop	1	Bathrooms Near Fueling Station	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator

Martin County	Landfill Scalehouse	1	Kitchen	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Landfill Scalehouse	1	Men	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Landfill Scalehouse	1	Men	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Landfill Scalehouse	1	Women	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Landfill Scalehouse	1	Women	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Landfill Scalehouse	1	Women	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Langford Park	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 21vBt Diaphragm	NR	No Retrofit
Martin County	Langford Park	1	Men Gang	URINAL	1	WMU TS c1.0F/v1.0F TMI	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Langford Park	1	Men Gang	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Langford Park	1	Women Gang	WATER CLOSET	2	FM TS c1.6F/v1.6F TMI 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 21vBt Diaphragm	NR	No Retrofit

Martin County	Langford Park	1	Women Gang	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Langford Park	1	Kitchen	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang	WATER CLOSET	2	FMTT TS c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang	URINAL	2	WMU TS c1.0F/v1.0F TMI	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang	FAUCET	4	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang	WATER CLOSET	4	FMTT TS c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang	FAUCET	4	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Kitchen	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang	WATER CLOSET	4	FMTT TS c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang	FAUCET	4	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang Exterior near playground	WATER CLOSET	2	WM TS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator	NR	No Retrofit

			Exterior near playground				Faucet Sensor Female		
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang Exterior near playground	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang Exterior near playground	WATER CLOSET	1	WM TS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang Exterior near playground	URINAL	1	WMU TS .125F/v.125F	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang Exterior near playground	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang Exterior near baseball	WATER CLOSET	2	WM TS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang Exterior near baseball	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Women Gang Exterior near baseball	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang Exterior near baseball	WATER CLOSET	1	WM TS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang Exterior near baseball	URINAL	1	WMU TS .125F/v.125F	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Langford Park - Vince Bocchino Community Center	1	Men Gang Exterior near baseball	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	LCpl Justin Wilson Park	1	Baseball Womens	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28	NR	No Retrofit

							GPF Floor Mount Tank Type Water Closet Top Spud - Exposed		
Martin County	LCpl Justin Wilson Park	1	Baseball Womens	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	LCpl Justin Wilson Park	1	Baseball Womens	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	LCpl Justin Wilson Park	1	Baseball Womens	FAUCET	3	AER 2.0F	2.0 GPM Faucet Aerator Female	REFT 0.5	0.5 GPM 4in Centerset, Deck Mount, Faucet
Martin County	LCpl Justin Wilson Park	1	Baseball Mens	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	LCpl Justin Wilson Park	1	Baseball Mens	URINAL	2	WMU TS c0.5F/v0.5F	0.5 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	LCpl Justin Wilson Park	1	Baseball Mens	FAUCET	3	AER 2.0F	2.0 GPM Faucet Aerator Female	REFT 0.5	0.5 GPM 4in Centerset, Deck Mount, Faucet
Martin County	Martin County Tax Collector Offices	1	Restrooms in Lobby	WATER CLOSET	2	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Martin County Tax Collector Offices	1	Restrooms in Lobby	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Sensor Female	NR	No Retrofit
Martin County	Martin County Tax Collector Offices	1	Staff Bathroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Martin County Tax Collector Offices	1	Staff Bathroom	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Sensor Female	NR	No Retrofit
Martin County	Martin County Tax Collector Offices	1	Staff Bathroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Martin County Tax Collector Offices	1	Staff Bathroom	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator	NR	No Retrofit

							Faucet Sensor Female		
Martin County	Mary Brogan Park	1	Women	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Mary Brogan Park	1	Women	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Mary Brogan Park	1	Men	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Mary Brogan Park	1	Men	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Mc Drc (Old Eoc)	1	Kitchen	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Mc Drc (Old Eoc)	1	Hallway Restroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Mc Drc (Old Eoc)	1	Hallway Restroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Mc Drc (Old Eoc)	1	Women	WATER CLOSET	2	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Mc Drc (Old Eoc)	1	Women	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Mc Drc (Old Eoc)	1	Men	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Mc Drc (Old Eoc)	1	Men	URINAL	1	WMU TS .125F/v1.0F	0.125 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit

Martin County	Mc Drc (Old Eoc)	1	Men	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Mcso Aviation Hangar	1	Kitchen	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Mcso Aviation Hangar	1	Hangar	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Mcso Aviation Hangar	1	Restroom in common area	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Mcso Aviation Hangar	1	Restroom in common area	URINAL	1	WMU TS c1.0F/v.5F	1.0 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Mcso Aviation Hangar	1	Restroom in common area	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Mcso Aviation Hangar	1	Restroom in common area	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Mcso Aviation Hangar	1	Restroom in common area	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Morgade Library	1	Men Gang Entry	WATER CLOSET	1	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Morgade Library	1	Men Gang Entry	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Morgade Library	1	Men Gang Entry	URINAL	1	WMU TS c1.0F/v1.5F SS	1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Morgade Library	1	Men Gang Entry	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Morgade Library	1	Men Gang Entry	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Morgade Library	1	Women Gang Entry	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush	NR	No Retrofit



							Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm		
Martin County	Morgade Library	1	Women Gang Entry	WATER CLOSET	4	FM TS c1.6F/v2.4F SS 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Morgade Library	1	Women Gang Entry	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Morgade Library	1	Women Gang Entry	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Morgade Library	1	Office	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Morgade Library	1	Office Bathroom	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Morgade Library	1	Office Bathroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Morgade Library	1	Breakroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Mosquito Control Office	1	Shop Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Mosquito Control Office	1	Shop Restroom	URINAL	1	WMU TS .125F/v.125F	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Mosquito Control Office	1	Shop Restroom	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	New Fleet Maintenance	1	106	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top	NR	No Retrofit

							Spud - Exposed Side Mount 9vBt Diaphragm		
Martin County	New Fleet Maintenance	1	106	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	New Fleet Maintenance	1	110	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	New Fleet Maintenance	1	110	URINAL	1	WMU TS c1.0F/v1.0F SS	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	New Fleet Maintenance	1	110	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	New Fleet Maintenance	1	110	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	New Fleet Maintenance	1	116	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Women	WATER CLOSET	1	FM TS c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	NR	No Retrofit
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Women	WATER CLOSET	2	FM TS c1.6F/v2.4F TMI 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Women	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Men	WATER CLOSET	1	FM TS c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed	NR	No Retrofit

							21vBt Diaphragm		
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Men	WATER CLOSET	1	FM TS c1.6F/v2.4F TMI 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Men	URINAL	1	WMU TS c0.5F/v0.5F	0.5 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Men	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	New Monrovia Park - Costella Williams Learning Center/Community Center	1	Common Room	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	New Monrovia Sheriff Substation	1	Women	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	New Monrovia Sheriff Substation	1	Women	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	New Monrovia Sheriff Substation	1	Men	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	New Monrovia Sheriff Substation	1	Men	FAUCET	1	AER 1.25F	1.25 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	New Monrovia Sheriff Substation	1	Breakroom	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Park Operations Compound	1	Garage Bathroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Park Operations Compound	1	Garage Bathroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Park Operations Compound	1	Office Bathroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water	NR	No Retrofit

							Closet Top Spud - Exposed		
Martin County	Park Operations Compound	1	Office Bathroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Park Operations Compound	1	Breakroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Pineapple Park	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 21vBt Diaphragm	NR	No Retrofit
Martin County	Pineapple Park	1	Men Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 21vBt Diaphragm	NR	No Retrofit
Martin County	Pineapple Park	1	Men Gang	URINAL	1	WMU TS c0.5F/v0.5F	0.5 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Pineapple Park	1	Men Gang	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Pineapple Park	1	Women Gang	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 21vBt Diaphragm	NR	No Retrofit
Martin County	Pineapple Park	1	Women Gang	WATER CLOSET	2	FM TS c1.6F/v1.6F TMI 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 21vBt Diaphragm	NR	No Retrofit

Martin County	Pineapple Park	1	Women Gang	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Port Salerno Civic Center	1	Men	WATER CLOSET	1	FM TS c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	NR	No Retrofit
Martin County	Port Salerno Civic Center	1	Men	URINAL	1	WMU TS c1.0F/v1.0F TMI	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Port Salerno Civic Center	1	Men	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Port Salerno Civic Center	1	Women	WATER CLOSET	1	FM TS c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	NR	No Retrofit
Martin County	Port Salerno Civic Center	1	Women	WATER CLOSET	1	FM TS c1.6F/v1.6F TMI 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	NR	No Retrofit
Martin County	Port Salerno Civic Center	1	Women	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Port Salerno Civic Center	1	Kitchen	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Public Safety Complex	1	105 Fire Office	WATER CLOSET	2	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit

Martin County	Public Safety Complex	1	105 Fire Office	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Public Safety Complex	1	104 Fire Office	WATER CLOSET	1	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	1	104 Fire Office	URINAL	2	WMU TS c1.0F/v.125F TMI	1.0 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	NR	No Retrofit
Martin County	Public Safety Complex	1	104 Fire Office	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Public Safety Complex	2	204 Fire Office	WATER CLOSET	4	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	2	204 Fire Office	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Public Safety Complex	2	203 Fire Office	WATER CLOSET	2	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	2	203 Fire Office	URINAL	2	WMU TS c1.0F/v.125F TMI	1.0 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	NR	No Retrofit
Martin County	Public Safety Complex	2	203 Fire Office	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator	NR	No Retrofit

							Faucet Sensor Female		
Martin County	Public Safety Complex	2	271 Women Locker	WATER CLOSET	1	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	2	271 Women Locker	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Public Safety Complex	2	271 Women Locker	SHOWER	2	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Public Safety Complex	2	271 Women Locker	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Public Safety Complex	2	271 Men Locker	WATER CLOSET	1	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	2	271 Men Locker	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Public Safety Complex	2	271 Men Locker	SHOWER	2	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Public Safety Complex	2	271 Men Locker	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Public Safety Complex	2	244 Men	WATER CLOSET	1	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	2	244 Men	URINAL	1	WMU TS c1.0F/v.125F TMI	1.0 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral)	NR	No Retrofit
Martin County	Public Safety Complex	2	244 Men	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet	NR	No Retrofit



							Aerator Faucet Sensor Female		
Martin County	Public Safety Complex	2	243 Women	WATER CLOSET	1	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	2	243 Women	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Public Safety Complex	2	PSC	FAUCET	2	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Public Safety Complex	2	PSC	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Public Safety Complex	2	Fire Office Entry Kitchenette	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Public Safety Complex	1	189A	WATER CLOSET	1	FM TS c1.6F/v2.4F TMI 9vBt PT	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Piston	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Public Safety Complex	1	189A	FAUCET	1	AER 1.5F FS	1.5 GPM Faucet Aerator Faucet Sensor Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	185	WATER CLOSET	1	WM TS c1.6F/v2.4F TMI PT	1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Public Safety Complex	1	185	FAUCET	1	AER 1.5F FS		RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	185	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Public Safety Complex	1	PSC Real Time Crime	FAUCET	1	AER 1.8F	1.8 GPM Faucet	RFAK1.5	1.5 GPM Kitchen

							Aerator Female		Faucet Aerator
Martin County	Public Safety Complex	1	134	WATER CLOSET	1	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	1	134	FAUCET	1	AER 1.5F FS		RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	133	WATER CLOSET	1	WM TS c1.6F/v2.4F TMI PT	1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Public Safety Complex	1	133	FAUCET	1	AER 1.5F FS		RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	Sheriffs Office	WATER CLOSET	1	WM TS c1.6F/v1.6F TMI PT	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) Piston	NR	No Retrofit
Martin County	Public Safety Complex	1	Sheriffs Office	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	Sheriffs Office	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Public Safety Complex	1	Sheriffs Office	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Public Safety Complex	1	PSC 162A	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Public Safety Complex	1	PSC Human Resources Men	WATER CLOSET	1	WM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Public Safety Complex	1	PSC Human Resources Men	URINAL	2	WMU TS .125F/v.25F	0.125 GPF/0.25 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit

Martin County	Public Safety Complex	1	PSC Human Resources Men	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	PSC Human Resources Women	WATER CLOSET	1	WM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Public Safety Complex	1	PSC Human Resources Women	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	PSC Human Resources Hallway Men	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Public Safety Complex	1	PSC Human Resources Hallway Men	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	PSC Human Resources Hallway Women	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Public Safety Complex	1	PSC Human Resources Hallway Women	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	PSC Human Resources Breakroom	FAUCET	1	AER 1.8F	1.8 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Public Safety Complex	1	Women next to Staff Inspections	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Public Safety Complex	1	Women next to Staff Inspections	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	Men next to Staff Inspections	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Public Safety Complex	1	Men next to Staff Inspections	FAUCET	1	AER 2.0F	2.0 GPM Faucet	RFA0.5	0.5 GPM Faucet Aerator

							Aerator Female		
Martin County	Public Safety Complex	1	PSC Human Resources Conference Room	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Public Safety Complex	1	Men next to Back Hallway HR	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Public Safety Complex	1	Men next to Back Hallway HR	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Public Safety Complex	1	Women in Back Hallway HR	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Public Safety Complex	1	Women in Back Hallway HR	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Rio Civic Center	1	Kitchen	FAUCET	1	AER 3.0F	3.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Rio Civic Center	1	Women	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Rio Civic Center	1	Women	WATER CLOSET	2	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Rio Civic Center	1	Women	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Rio Civic Center	1	Men	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Rio Civic Center	1	Men	URINAL	1	WMU TS c1.0F/v1.0F	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Rio Civic Center	1	Men	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Kitchen	FAUCET	1	AER 1.5F	1.5 GPM Faucet	NR	No Retrofit

							Aerator Female		
Martin County	Sailfish Splash Water Park	1	Kitchen	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Sailfish Splash Water Park	1	Kitchen	FAUCET	2	AER 2.5F	2.5 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Sailfish Splash Water Park	1	Gift Shop	WATER CLOSET	1	FM TS c1.6F/v1.28F 21vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 21vBt Diaphragm	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Gift Shop	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Sailfish Splash Water Park	1	Men Locker	WATER CLOSET	6	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Men Locker	URINAL	3	WMU TS .125F/v.125F	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Men Locker	URINAL	3	WMU TS .125F/v.125F	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Men Locker	FAUCET	5	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Men Locker	SHOWER	2	SH 1.75F	1.75 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Sailfish Splash Water Park	1	Men Locker	SHOWER	1	SH 1.75F	1.75 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Sailfish Splash Water Park	1	Women Locker	WATER CLOSET	18	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Women Locker	FAUCET	5	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet	NR	No Retrofit

							Sensor Female		
Martin County	Sailfish Splash Water Park	1	Women Locker	SHOWER	4	SH 1.75F	1.75 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Sailfish Splash Water Park	1	Women Locker	SHOWER	1	SH 1.75F	1.75 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Sailfish Splash Water Park	1	Family Bathrooms in pool area	WATER CLOSET	5	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Family Bathrooms in pool area	FAUCET	5	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Sailfish Splash Water Park	1	Kitchen	FAUCET	1	AER 2.5F	2.5 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Stuart Beach Park	1	Beach Cafe Kitchen	FAUCET	3	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Stuart Beach Park	1	Men Near Cafe	WATER CLOSET	2	WM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Stuart Beach Park	1	Men Near Cafe	URINAL	2	WMU TS c0.5F/v0.5F	0.5 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Stuart Beach Park	1	Men Near Cafe	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Stuart Beach Park	1	Women Standalone Bldg	WATER CLOSET	3	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Stuart Beach Park	1	Women Standalone Bldg	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Stuart Beach Park	1	Outdoor Showers near Cafe	SHOWER	6	SH 2.0F	2.0 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead

Martin County	Stuart Beach Park	1	Women near Cafe	WATER CLOSET	4	WM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Stuart Beach Park	1	Women near Cafe	FAUCET	3	AER 0.5F FS	0.5 GPM Faucet Aerator Sensor Female	NR	No Retrofit
Martin County	Stuart Beach Park	1	Men Standalone Bldg	WATER CLOSET	2	FM TS c1.6F/v1.6F <6vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed <6vBt Diaphragm	NR	No Retrofit
Martin County	Stuart Beach Park	1	Men Standalone Bldg	URINAL	1	WMU TS .125F/v.125F	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed	NR	No Retrofit
Martin County	Stuart Beach Park	1	Men Standalone Bldg	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Stuart Beach Park	1	Outdoor Showers Standalone Bldg	SHOWER	6	SH 2.0F	2.0 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Supervisor Of Elections Office	1	Kitchen	FAUCET	1	AER 2.0F	2.0 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Supervisor Of Elections Office	1	Restroom	WATER CLOSET	2	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Supervisor Of Elections Office	1	Restroom	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Supervisor Of Elections Office	1	Public Restroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Supervisor Of Elections Office	1	Public Restroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Supervisor Of Elections Office	1	Public Restroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Supervisor Of Elections Office	1	Public Restroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet	RFA0.5	0.5 GPM Faucet Aerator



							Aerator Female		
Martin County	Supervisor Of Elections Office	1	Staff Restroom Storage	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Supervisor Of Elections Office	1	Staff Restroom Storage	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Timer Powers Park	1	Women's in open field	WATER CLOSET	2	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Timer Powers Park	1	Women's in open field	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Timer Powers Park	1	Men's in open field	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Timer Powers Park	1	Men's in open field	URINAL	1	WMU TS c1.0F/v1.5F	1.0 GPF/1.5 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Timer Powers Park	1	Men's in open field	FAUCET	2	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Timer Powers Park	1	Men's at Arena	WATER CLOSET	1	WM RS-CN c1.6F/v2.4F 21vBt D	1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed 21vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Timer Powers Park	1	Men's at Arena	URINAL	2	WMU TS .125F/v1.0F	0.125 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Timer Powers Park	1	Men's at Arena	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Timer Powers Park	1	Women's at Arena	WATER CLOSET	3	WM RS-CN c1.6F/v2.4F 21vBt D	1.6 GPF/2.4 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit

							21vBt Diaphragm		
Martin County	Timer Powers Park	1	Women's at Arena	FAUCET	2	AER 2.0F	2.0 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Timer Powers Park	1	Fish cleaning	FAUCET	1	AER 4.0F	4.0 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Traffic Management Center	1	Restroom	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Traffic Management Center	1	Restroom	FAUCET	1	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Vehicle Maintenance Shop	1	Shop Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Vehicle Maintenance Shop	1	Shop Restroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Vehicle Maintenance Shop	1	Office Restroom	WATER CLOSET	1	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Vehicle Maintenance Shop	1	Office Restroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Vehicle Maintenance Shop	1	Breakroom	FAUCET	1	AER 2.2F	2.2 GPM Faucet Aerator Female	RFAK1.5	1.5 GPM Kitchen Faucet Aerator
Martin County	Vehicle Maintenance Shop	2	Upstairs Office Restrooms	WATER CLOSET	2	FMTT TS c1.28F/v1.28F	1.28 GPF/1.28 GPF Floor Mount Tank Type Water Closet Top Spud - Exposed	NR	No Retrofit
Martin County	Vehicle Maintenance Shop	2	Upstairs Office Restrooms	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Vehicle Maintenance Shop	2	Lounge	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit

Martin County	William Doc Myers Park	1	Women	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed 21vBt Diaphragm	NR	No Retrofit
Martin County	William Doc Myers Park	1	Women	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	William Doc Myers Park	1	Men	WATER CLOSET	1	WM RS-CN c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Rear Spud - Concealed 21vBt Diaphragm	NR	No Retrofit
Martin County	William Doc Myers Park	1	Men	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Men	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Men	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Unisex Restroom by Bookeeping	WATER CLOSET	1	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Unisex Restroom by Bookeeping	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Restrooms in back office	WATER CLOSET	2	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Restrooms in back office	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit

Martin County	Willoughby Commons Usd Office	1	Women's Restroom by Bookeeping	WATER CLOSET	1	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Women's Restroom by Bookeeping	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Restroom in back hall by exit door	WATER CLOSET	1	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Restroom in back hall by exit door	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Men's Restroom by Bookeeping	WATER CLOSET	1	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Men's Restroom by Bookeeping	URINAL	1	WMU TS c1.0F/v1.0F	1.0 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Willoughby Commons Usd Office	1	Men's Restroom by Bookeeping	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Women	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Women	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Lounge	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Willoughby Commons Usd Office	1	Restrooms in back office	WATER CLOSET	2	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit

Martin County	Willoughby Commons Usd Office	1	Restrooms in back office	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Mpo Office	1	Staff Bathroom	WATER CLOSET	1	FMTT c1.6F/v1.6F	1.6 GPF/1.6 GPF Floor Mount Tank Type Water Closet	NR	No Retrofit
Martin County	Willoughby Mpo Office	1	Staff Bathroom	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Mpo Office	1	Breakroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Breakroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Men's in Entry office area	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Men's in Entry office area	URINAL	1	WMU TS .125F/v1.0F SS	0.125 GPF/1.0 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	RUDVK0.5	0.5 GPF Diaphragm Urinal Valve Kit
Martin County	Willoughby Property Appraiser's Office	1	Men's in Entry office area	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Unisex in Entry office area	WATER CLOSET	1	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Unisex in Entry office area	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Women's in Entry office area	WATER CLOSET	2	FM TS c1.6F/v1.6F SS 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top	NR	No Retrofit

							Spud - Exposed Side Mount 9vBt Diaphragm		
Martin County	Willoughby Property Appraiser's Office	1	Women's in Entry office area	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Break Room	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Men's in Break Room	WATER CLOSET	1	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Men's in Break Room	URINAL	2	WMU TS .125F/v.125F SS	0.125 GPF/0.125 GPF Wall Mount Urinal Top Spud - Exposed Side Mount	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Men's in Break Room	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Women's in Break Room	WATER CLOSET	2	FM TS c1.6F/v1.6F 9vBt D	1.6 GPF/1.6 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Women's in Break Room	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Women's in office area	WATER CLOSET	1	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Women's in office area	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Unisex in utilities bldg	WATER CLOSET	1	FM TS c1.28F/v1.28F SS 9vBt D	1.28 GPF/1.28 GPF Floor Mount Flush	NR	No Retrofit

							Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm		
Martin County	Willoughby Property Appraiser's Office	1	Unisex in utilities bldg	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Unisex in utilities bldg	WATER CLOSET	1	FM TS c1.28F/v1.28F SS 9vBt D	1.28 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Side Mount 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Unisex in utilities bldg	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Men's in office area	WATER CLOSET	1	FM TS c1.6F/v1.28F 9vBt D	1.6 GPF/1.28 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed 9vBt Diaphragm	NR	No Retrofit
Martin County	Willoughby Property Appraiser's Office	1	Men's in office area	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Restroom	WATER CLOSET	1	WM TS 4B c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 4 Bolt China 21vBt Diaphragm	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Restroom	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Witham Field Customs Building	1	Restroom in Customs	WATER CLOSET	2	WM TS 4B c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 4 Bolt China 21vBt Diaphragm	NR	No Retrofit



Martin County	Witham Field Customs Building	1	Restroom in Customs	FAUCET	2	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Witham Field Customs Building	1	Restroom in Customs	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Witham Field Customs Building	1	Men's Restroom in CBP Processing	WATER CLOSET	1	WM TS 4B c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 4 Bolt China 21vBt Diaphragm	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Men's Restroom in CBP Processing	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Women's Restroom in CBP Processing	WATER CLOSET	1	WM TS 4B c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 4 Bolt China 21vBt Diaphragm	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Women's Restroom in CBP Processing	FAUCET	2	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Restroom in CBP Office	WATER CLOSET	1	WM TS 4B c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 4 Bolt China 21vBt Diaphragm	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Restroom in CBP Office	FAUCET	1	AER 0.5F FS	0.5 GPM Faucet Aerator Faucet Sensor Female	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Restroom in CBP Office	SHOWER	1	SH 2.5F	2.5 GPM Standard Showerhead	RSHS1.5	1.5 GPM Standard Showerhead
Martin County	Witham Field Customs Building	1	Restroom on County Side	WATER CLOSET	1	WM TS 4B c1.6F/v1.6F 21vBt D	1.6 GPF/1.6 GPF Wall Mount Flush Valve Water Closet Top Spud - Exposed 4 Bolt China	NR	No Retrofit

							21vBt Diaphragm		
Martin County	Witham Field Customs Building	1	Restroom on County Side	FAUCET	1	AER 1.5F	1.5 GPM Faucet Aerator Female	RFA0.5	0.5 GPM Faucet Aerator
Martin County	Witham Field Customs Building	1	Holding Cell	WATER CLOSET	1	FM RS-CN c1.6F/v2.4F D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Rear Spud - Concealed Diaphragm	NR	No Retrofit
Martin County	Witham Field Customs Building	1	Holding Cell	FAUCET	1	AER 1.0F	1.0 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Wojcieszak Park	1	Men	WATER CLOSET	2	FM TS c1.6F/v2.4F TMI 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Wojcieszak Park	1	Men	URINAL	1	WMU TS c0.5F/v0.5F TMI 9vBt	0.5 GPF/0.5 GPF Wall Mount Urinal Top Spud - Exposed Top Mount (Integral) 9" Vacuum Breaker	NR	No Retrofit
Martin County	Wojcieszak Park	1	Men	FAUCET	3	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit
Martin County	Wojcieszak Park	1	Women	WATER CLOSET	3	FM TS c1.6F/v2.4F TMI 9vBt D	1.6 GPF/2.4 GPF Floor Mount Flush Valve Water Closet Top Spud - Exposed Top Mount (Integral) 9vBt Diaphragm	RTDVK1.6	1.6 GPF Diaphragm Toilet Valve Kit
Martin County	Wojcieszak Park	1	Women	FAUCET	3	AER 0.5F	0.5 GPM Faucet Aerator Female	NR	No Retrofit