



NOTE: EXISTING VEGETATION WITHIN THE EAST AND NORTH BUFFERS CANNOT BE REMOVED.

SAW PALMETTO PROPOSED ON THE EAST BUFFER ARE TO BE ENHANCED WITH THE EXISTING SAW PALMETTO.

NOTE: SUBMITTAL OF A PERFORMANCE BOND EQUAL TO 100% OF COST FOR THE LANDSCAPE RESTORATION MATERIALS AND INSTALLATION TO BE EXECUTED DURING THE POST DEVELOPMENT PROCESS.

GENERAL LANDSCAPE MAINTENANCE NOTES:
 REQUIRE MAINTENANCE IN ACCORDANCE UTILIZING SOUND HORTICULTURAL PRACTICES. NO SPECIAL ALLOWANCE FOR INCREASED TRIMMING IS TO BE ALLOWED.

MATERIAL SCHEDULE							
Project Number: 010900-01-002 FIFTH THIRD BANK - JENSEN BEACH							
Date: 10/22/2024							
TREES (Florida No. 1)							
QTY	SYM	NATIVE BOTANICAL	COMMON	SPECS	SPACING	ZONE	
5	PE20	YES	<i>Pinus elliotii</i> var. <i>densa</i>	South Florida Slash Pine	20'-22"H x 12"-13", 6" DBH, 300G	AS SHOWN	9a-11a
5	QV20	YES	<i>Quercus virginiana</i>	Live Oak	20'-22"H x 12"-13", 6" DBH, 300G	AS SHOWN	7a-10b
SHRUBS (Florida No. 1)							
QTY	SYM	NATIVE BOTANICAL	COMMON	SPECIFICATIONS	SPACING	ZONE	
95	SES25	YES	<i>Serenoa repens</i> 'Silver'	Silver Saw Palmetto	42"H x 36" S, 25G	36" OC	8a-10b
GENERAL NOTES							
1 Plant materials must be installed in soil conditions that are conducive to the proper growth of the plant material. Limerock located within planting areas must be removed and replaced with native or growing quality soil before planting.							
2 The Use of Alternative Species must also be approved by County Staff.							

RESTORATION PLAN - Enlargement:

