

LEGAL DESCRIPTION

PARCEL 1:

TRACTS 2. 6 AND 7. BLOCK 43, ST. LUCIE INLET FARMS, ACCORDING TO THE MAP OR PLAT THEREOF AS RECORDED IN PLAT BOOK 1, PAGE 98, PALM BEACH COUNTY, FLORIDA (NOW MARTIN) PUBLIC RECORDS, LESS RIGHT-OF-WAY FOR S.E. COVE ROAD.

PARCEL 2:

TRACTS 2 AND 7, BLOCK 44, ST. LUCIE INLET FARMS, ACCORDING TO THE MAP OR PLAT THEREOF AS RECORDED IN PLAT BOOK 1, PAGE 98, PALM BEACH COUNTY, FLORIDA (NOW MARTIN) PUBLIC RECORDS, LESS RIGHT-OF-WAY FOR S.E. SALERNO ROAD.

LESS THE FOLLOWING:

BEING KNOWN AS A PORTION OF TRACT 2, BLOCK 44, "ST. LUCIE INLET FARMS SUBDIVISION" AS RECORDED IN PLAT BOOK 1, PAGE 98, PUBLIC RECORDS OF PALM BEACH, (NOW MARTIN) COUNTY, FLORIDA AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCING AT THE NORTHWEST CORNER OF SAID TRACT 2, ALSO BEING THE CENTERLINE OF A 30 FOOT WIDE PLATTED ROAD RIGHT-OF-WAY; THENCE RUN SOUTH 23"16'57" EAST ALONG THE WEST LINE OF SAID TRACT 2 A DISTANCE OF 40 FEET TO THE POINT AND PLACE OF BEGINNING; THENCE RUN NORTH 66°09'54" EAST ALONG THE NEW RIGHT-OF-WAY OF WAY LINE OF SALERNO ROAD AND A LINE BEING SOUTH AND PARALLEL TO THE ORIGINAL CENTER LINE AND NORTH LINE OF SAID TRACT 2 A DISTANCE OF 237.81 FEET TO A POINT; THENCE RUN SOUTH 23"16'57" EAST A DISTANCE OF 120.01 FEET TO A POINT: THENCE RUN SOUTH 66°09'54" WEST A DISTANCE OF 237.81 FEET TO A POINT ON THE WEST LINE OF SAID TRACT 2; THENCE RUN NORTH 23"16'57" WEST ALONG SAID WEST LINE A DISTANCE OF 120.01 FEET TO THE POINT AND PLACE OF BEGINNING. CONTAINING: 28,537 S/F, 0.66 ACRES +\-

PHASE I PHASE II

90,282 90,282

1.0

0.54 AC.

.21

2.0 YEARS

180,564 C.Y.

2,028,154 SF 98%

.7%

23,522 SF

9,148 SF

3,485 SF

1.0

A-1A/R-3A

RURAL DENSITY

AGRICULTURAL

47.39 ACRES

0.04 UPA

INCLUDED AREA = 2,052,500 SQUARE FEET, 47.12 ACRES +/-.

PHASING PLAN & DATA:

DURATION OF PROJECT

CIVIL/SITE WORK - FILLING

PARCEL CONTROL NUMBERS:

GROSS RESIDENTIAL DENSITY:

WETLAND BUFFER

BUILDING COVERAGE:

ROADS/DRIVEWAYS:

OPEN SPACE:

FUTURE LAND USE DESIGNATION:

ITEM/DESCRIPTION

SITE DATA:

EXISTING ZONING:

TOTAL SITE AREA:

EXISTING USE:

TOTAL UNITS:

PERVIOUS AREA:

IMPERVIOUS AREA:

OPERATIONAL SPECIFICATIONS

- 1. ALL MINING ACTIVITIES SHALL BE IN ACCORDANCE WITH ALL APPLICABLE MARTIN COUNTY STANDARDS AND CONDITIONS FOR EXCAVATION, FILL AND
- 2. HOURS OF OPERATION FOR ALL MINING PROJECTS SHALL BE LIMITED TO BETWEEN THE HOURS OF 7:00 A.M. AND 4:00 P.M. MONDAY THROUGH FRIDAY, AND SATURDAY 9:00 A.M. TO 4:00 P.M.
- 3. ALL DRAINAGE RELATED TO THE PROJECT SHALL BE IN ACCORDANCE WITH SFWMD PERMIT NO. 43-02237-P.
- 4. ALL CLEARING AND GRUBBING MUST BE PHASED CONCURRENTLY WITH CONSTRUCTION ACTIVITIES TO MINIMIZE SOIL EROSION AND THE GENERATION OF AIRBORNE DUST.
- 5. SEEDING, WETTING AND/OR MULCHING PROCEDURES WILL BE IMPLEMENTED FOR ANY DISTURBED AREAS WITHIN THIRTY (30) DAYS OF COMPLETION TO MINIMIZE AIRBORNE DUST AND PARTICULATE EMISSIONS.
- 3. THERE ARE TWO EXISTING HOMES LOCATED IN THE NORTHWEST CORNER OF THE PROPERTY SERVED BY A POTABLE WELL AND A SEPTIC SYSTEM FOR UTILITIES. THERE ARE NO NEW UTILITY SERVICES PROPOSED FOR THIS
- 7. SILT FENCE SHALL BE INSTALLED AND MAINTAINED ADJACENT TO ALL DISTURBED AREAS AS NECESSARY.
- 8. PROPERTY CORNERS SHALL BE LOCATED BY A LICENSED LAND SURVEYOR AND CLEARLY MARKED IN THE FIELD PRIOR TO THE ENGINEERING DEPARTMENT'S PRE-CONSTRUCTION MEETING FOR SITE DEVELOPMENT.
- 9. ALL CONSTRUCTION BARRICADES AND SILT FENCES WILL REMAIN IN PLACE AND BE MONITORED FOR COMPLIANCE BY THE PERMIT HOLDER DURING THE PERMITTED DEVELOPMENT ACTIVITIES.
- 10. SOIL STABILIZATION SHALL BE COMPLETED WITHIN 30 DAYS OF VEGETATION REMOVAL.
- 11. ALL BARRICADES AND EROSION CONTROL DEVICES SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR FOLLOWING CERTIFICATION OF THE


ସର୍ବାବାବାବାବାବା

INSHINE STATE ONE CALL OF FLORIDA, INC.

CALL 48 HOURS

IT'S THE LAW! 1-800-432-4770

BEFORE YOU DIG



ENGINEERING