


Land Planner / Landscape Architect:
Lucido & Associates
701 E. Ocean Blvd
Stuart, Florida 34994

Surveyor:
Betsy Lindsay Surveying & Mapping
7997 SW Jack James Drive
Stuart, Florida 34997

Martin County, Florida

Date	By	Description
03.11.19	SAW	Initial Submittal
09.24.19	SAW	Resubmittal 1
12.16.19	SAW	Resubmittal 2



© Copyright Lucido & Associates. These documents and their contents are the property of Lucido & Associates. Any reproductions, revisions, modifications or use of these documents without the express written consent of Lucido & Associates is prohibited by law.

Required Xeriscape Points:	
Design options used:	
51% or more of drought tolerant grasses used	10 pts.
51% or more of drought tolerant shrubs used	10 pts.
51% or more of drought tolerant trees used	10 pts.
25% more than the required shade trees planted in vehicular use area	5 pts.
Utilization of compacted mulch other than cypress mulch	5 pts.
Utilization of compacted mulch beds at least three inches deep in all planted areas, excepting groundcovers	10 pts.
Total Xeriscape Points	50 pts.

Alternative plant species for required landscape may be permitted subject to review and approval by the Martin County Growth Management Department prior to installation.

All prohibited exotic or invasive species shall be removed from the entire site prior to the issuance of a Certificate of Occupancy.

All required landscaping shall be installed prior to the issuance of a Certificate of Occupancy.

No Cypress Mulch is to be used on site. Eucalyptus or Melaleuca Mulch is to be used in a 3" consistent layer in all plant beds.

Enhanced landscaping beyond minimum requirements will conform to all applicable sections of the Martin County Landscape Development Regulations. As-built drawings will be submitted to Martin County Growth Management with Certification of Landscaping installation and Maintenance.

This plan has been designed to meet the tree planting requirements contained within the FPL document entitled "Plant the Right Tree in the Right Place".

- For existing or proposed utilities, no tree shall be planted where it could, at mature height conflict with overhead power lines.
- Large trees (height at maturity of more than 30') shall be planted no closer than a horizontal distance of 30' from the nearest overhead power line.
- Medium height trees (height at maturity between 20' and 30') shall be offset at least 20' and small trees (height at maturity of less than 20') require no offset.
- No tree shrubs, hedges or vines shall be planted within 5' of an existing or proposed utility pole, guy wire or pad-mounted transformer.
- Palms should be planted at a distance equal to or greater than the average frond length plus two (2) feet from power lines.
- Tree species shall be selected as to minimize conflicts with existing or proposed utilities.

Encroachments into required bufferyards and landscape areas by vehicles, boats, mobile homes or trailers shall not be permitted, and required landscape areas shall not be used for the storage or sale of materials or products or the parking of vehicles and equipment.

The property owner, or successors in interest, or agent, if any, shall be jointly and severally responsible for the following:

- a. Regular maintenance of all landscaping to be kept alive and in good condition and in a way that presents a healthy, neat, and orderly appearance. All landscaping shall be maintained free from disease, pests, weeds, and litter. Maintenance shall include weeding, watering, fertilizing, pruning, mowing, edging, mulching and other maintenance, as needed and in accordance with acceptable horticultural practices;
- b. Repair or replacement of required walls, fences, or structures to a structurally sound condition;
- c. Regular maintenance, repair or replacement, where necessary, of any screening or buffering required by the division;
- d. Perpetual maintenance to prohibit the re-establishment of harmful exotic species within landscaping and preservation areas; and
- e. Replacement of any required landscaping in easement areas that may be disturbed by future maintenance.

Landscape Plan, Plant Schedule	COVER
Landscape Plan	LA-1
Landscape Plan-SPZ Detail	LA-2
Shoreline Protection Zone Landscape	LA-3
Tree Mitigation Plan	LA-4
Landscape Details	LA-4
Landscape Specifications	LA-5

[illegible]

USES	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	CALIPER
BS	25	Bursera simaruba	Gumbo Limbo	65G	14'-16" HT	10" SPR		Native	3" Caliper
BS2	3	Bursera simaruba	Gumbo Limbo	FG	22-24" HT	16" Sprd	6 CT, STD, SP	Native	8" Caliper
CU	10	Coccoloba uvifera	Sea Grape	45G	14' HT	8" SPR	Standard, Specimen	Native	
COE	9	Coccoloba uvifera	Sea Grape	Existing to Remain				Native	
CB	17	Conocarpus erectus	Buttonwood	45G	12' HT	8' W	STD, 3' CT, SP	Native	3" Caliper
CR	2	Conocarpus erectus	Buttonwood	Existing to Remain				Native	
CO2	2	Conocarpus erectus 'Sericeus'	Butter Buttonwood	45G	12' HT	8' W	STD, F, SP	Native	3" Caliper
QV	25	Quercus virginiana	Southern Live Oak	65G	14'-16" HT	10" W	F, SP	Native	3" Caliper
QVE	1	Quercus virginiana	Southern Live Oak	Existing to Remain				Native	
QV4	3	Quercus virginiana	Southern Live Oak	FG	22-24" HT	16" W	RANCH, CH, F, SP	Native	8" Caliper
TG	3	Tibouchina granulosa	Purple Glory Tree	25G	6' HT	4' W	Specimen		
PALMS	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	CALIPER
ADS	4	Adonidia merrillii	Double Christmas Palm	FG	14' OA		DBL, F, SP		
CMR	29	Cocos nucifera	Coconut Palm	Relocated on Site					
CMH	27	Cocos nucifera 'Green Malayan'	Coconut Palm	FG	10'-18" GW		HVY CAL, CV TR, SP		
SPE	25	Sabal palmetto	Sabal Palm	Existing to Remain				Native	
SP	14	Sabal palmetto	Sabal Palm	FG	10'-18" CT		HVY CAL, SLK, SP	Native	
SPR	16	Sabal palmetto	Sabal Palm	Relocated on Site				Native	
SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	
AWB	203	Acalypha wilkesiana 'Louisiana Red'	Red Copperleaf	7G	36" HT	24"W	FTB, SP		
CHR	1,236	Chrysobalanus icaco 'Horizontal'	Green Horizontal Cocoplum	3G	24" HT	18"W	F, SP	Native	
CLU	65	Clusia grandifolia	Small-Leaf Clusia	7G	36" HT	24"W	FTB		
CVI	104	Coccoloba uvifera	Sea Grape	7G	3' HT	3' W	F	Native	
CCE	214	Conocarpus erectus 'Sericeus'	Silver Buttonwood	3G	3' HT	2' W	F	Native	
HMM	32	Hamelia patens	Fire Bush	3G	3' HT	2' W	F	Native	
HAM	43	Hamelia patens 'Compacta'	Dwarf Firebush	3G	36" HT	30"W	FTB		
NCI	173	Nerium oleander 'Ice Pink'	Ice Pink Oleander	3G	2' HT	18"W	F		
SAR	69	Schefflera arboricola	Green Schefflera	3G	24" HT	24"W	F		
SER	5	Serenoa repens 'Cinerea'	Silver Saw Palmetto	FG	5' HT	5' W	F, SP	Native	
ACCENTS	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	
ALI	33	Alcantarea imperialis	Imperial Bromeliad	7G	30" OA		SP		
AOO	24	Alcantarea odorata	Giant Silver Bromeliad	25G	30" OA		SP		
ABS	46	Androlepis skinneri	Big Red Bromeliad	7G	30" OA		SP		
PNN	420	Pennisetum setaceum 'White'	White Fountain Grass	3G	2' HT	2' W	F		
STR	17	Strelitzia reginae	Orange Bird Of Paradise	7G	36" OA				
TF	61	Tripsacum dactyloides	Fakahatchee Grass	3G	24" OA			Native	
ZAF	33	Zamia floridana	Coontie Palm	15G	24" OA		F	Native	
NATIVE GRASSES	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	SPACING
SPB	974	Spartina bakeri	Sanc Cordgrass	3G	18" OA		F	Native	24" o.c.
GRASSES	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	SPACING
MUH	147	Muhlenbergia capillaris	Pink Muhly	3G	18" OA		F	Native	24" o.c.
TRI	154	Tripsacum floridanum	Florida Gamagrass	3G	24" OA	18"W		Native	24" o.c.
GROUND COVERS	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	SPACING
GIF	603	Ficus microcarpa 'Green Island'	Green Island Ficus	3G	18"HT	12"W	Full		24" o.c.
ILS	299	Ilex vomitoria 'Stokes Dwarf'	Dwarf Yaupon	3G	12"HT	12"W	Full	Native	18" o.c.
LMG	659	Liriope muscari	Big Blue	1G					

Existing Zoning: LC
Future Land Use: Commercial Limited
Existing Use: Apartment / Hotel

**Proposed 2-Story
Building Expansion**
4,466 sf
(FFE 8.70)

**Existing
1 Story Building**
6,345 sf
(FFE 8.70)

**Relocated
Storage Building ±750 sf (FFE 9.25)**

25' Shoreline Protection Zone
-All native vegetation to be retained.
-All exotic vegetation to be removed.
-Refer to Shoreline Protection Zone Landscape Plan (sht 3)

25' Shoreline Protection Zone


Proposed Rip Rap
(Up to 12"-36" Above Ground)
5' Off of MHWL Typ.

Proposed Drainage
Outfall
Mean High
Water Line
Upland Retaining Wall
(Min. 30' From MHWL)
SPZ Section
(See Detail Below)

**Existing
Conchy
Joe's**
(FFE 5.77)

lucido & associates
701 SE Ocean Blvd., Stuart, Florida 34994 (772) 220-2100, Fax (772) 223-0220

Key / Location:



Project Team:

Applicant / Property Owner:

F.M. AYRES 2 LLC, and
SUNRISE RESTAURANTS, LLC
3945 NE Indian River Drive
Jensen Beach, Florida 34957

Land Planner / Landscape Architect:

Lucido & Associates
701 E. Ocean Blvd
Stuart, Florida 34994

Engineer:

The MCo Group
10975 SE Federal Highway
Hobe Sound, Florida 33455

Surveyor:


Betsy Lindsay Surveying & Mapping
7997 SW Jack James Drive
Stuart, Florida 34997

Conchy Joe's

Martin County, Florida

Landscape Plan

Date	By	Description
03.11.19	SAW	Initial Submittal
09.24.19	SAW	Resubmittal 1
12.18.19	SAW	Resubmittal 2




SCALE: 1" = 20'
0 10' 20' 40'

REG. # 1018
Thomas P. Lucido

Designer	JJ	Sheet
Manager	DF	
Project Number	17-425	
Municipal Number	---	
Computer File	18-041 Conchy Joes landscape plan.dwg	


LA-1

© Copyright Lucido & Associates. These documents and their contents are the property of Lucido & Associates. Any reproductions, revisions, modifications or use of these documents without the express written consent of Lucido & Associates is prohibited by law.






Surveyor:
Betsy Lindsay Surveying & Mapping
7997 SW Jack James Drive
Stuart, Florida 34997

Landscape Plan

[illegible]

© Copyright Lucido & Associates. These documents and their contents are the property of Lucido & Associates. Any reproductions, revisions, modifications or use of these documents without the express written consent of Lucido & Associates is prohibited by law.





Project Team:

Applicant / Property Owner:
F.M. AYRES 2 LLC, and
SUNRISE RESTAURANTS, LLC
3945 NE Indian River Drive
Jensen Beach, Florida 34957

Land Planner / Landscape Architect:
Lucido & Associates
701 E. Ocean Blvd
Stuart, Florida 34994

Engineer:
The MilCor Group
10975 SE Federal Highway
Hobe Sound, Florida 33455


Surveyor:
Beisy Lindsay Surveying & Mapping
7997 SW Jack James Drive
Stuart, Florida 34997

Conchy Joe's

Martin County, Florida

Shoreline Protection Zone Landscape Plan

Date	By	Description
03.11.19	SAW	Initial Submittal
09.24.19	SAW	Resubmittal 1
12.18.19	SAW	Resubmittal 2




SCALE: 1" = 20'

0 10' 20' 40'

REG. # 1018
Thomas P. Lucido

Designer JJ Sheet
Manager DF
Project Number 17-425
Municipal Number ---
Computer File 18-041 Conchy Joes landscape plan.dwg

LA-3





SHORELINE PROTECTION ZONE PLAN
1" = 20'-0"

PLANT SCHEDULE SHORE PROTECTION

SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE
	35	Conocarpus erectus	Buttonwood	3G	36" HT	30"W	FTB, SP	Native
	25	Rhizophora mangle	Red Mangrove	3G	3' HT	2' W	F	Native


NATIVE GROUNDCOVERS	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE
	39	Borrchia frutescens	Sea Oxeye Daisy	1G	10" OA		F	Native
	54	Ipomoea pes-caprae	Railroad Vine	1G	10" RUNNERS		F	Native
	41	Sesuvium portulacastrum	Shoreline Seapurslane	1G	10" OA		F	Native

NATIVE GRASSES	QTY	BOTANICAL NAME	COMMON NAME	CONTAINER	HEIGHT	WIDTH	NOTES	NATIVE	SPACING
	646	Spartina bakeri	Sand Cordgrass	3G	18" OA		F	Native	24" o.c.



SHORELINE PROTECTION ZONE SECTION
1/4" = 1'-0"

Key / Location:



Project Team:

Applicant / Property Owner:

F.M. AYRES 2 LLC, and
SUNRISE RESTAURANTS, LLC
3945 NE Indian River Drive
Jensen Beach, Florida 34957

Land Planner / Landscape Architect:


Lucido & Associates
701 E. Ocean Blvd
Stuart, Florida 34994

Engineer:

The MJC Group
10975 SE Federal Highway
Hobe Sound, Florida 33455


Surveyor:

Betsy Lindsay Surveying & Mapping
7997 SW Jack James Drive
Stuart, Florida 34997



TREE PLANTING & STAKING

NOT TO SCALE



BRACING DETAIL

NOT TO SCALE

WRAP TRUNK IN BURLAP & SECURE
BATTENS W/ 3/4\"/>

2x4x36\"/>

PALM PLANTING - ANGLE STAKE

NOT TO SCALE

THIN BRANCHES BY 1/4 OF TOTAL
MASS. RETAIN NAT. SHAPE
1/2\"/>

WHITE FILM
PLANT SO THAT ROOTBALL IS
3\"/>

REMOVE BURLAP 1/3 OF BALL
FORM SAUCER WITH 3\"/>



2\"/>

FINISHED GRADE
TOPSOIL

2 x BALL DIA.


MULTI-TRUNK PLANTING & GUYING

NOT TO SCALE




SHRUB PLANTING

NOT TO SCALE



GROUNDCOVER PLANTING DETAIL

NOT TO SCALE




THIS DETAIL SHOWN DEPICTS A MEDIAN AND/OR LANDSCAPE ISLAND AND IS
FOR GRAPHIC PURPOSES ONLY; SOIL PREPARATION SHALL APPLY TO ALL
TREE, SHRUB, & GROUND COVER AREAS. THIS DOES NOT INCLUDE SOD AREAS

LANDSCAPE AREA PREPARATION DETAIL


NOT TO SCALE

- *TOPSOIL SHALL BE NATURAL, FRIABLE, FINE LOAMY SOIL, POSSESSING CHARACTERISTICS OF REPRESENTATIVE TOPSOIL IN THE VICINITY OF THE PROJECT SITE THAT PRODUCES HEAVY GROWTH.
- TOPSOIL SHALL HAVE A PH RANGE OF 6.5-7.4, FREE FROM SUBSOIL, WEEDS, LITTER, SODS, CLAY, STONES, STUMPS, ROOTS, TRASH, HERBICIDES, TOXIC SUBSTANCES, OR ANY OTHER MATERIAL WHICH MAY BE HARMFUL TO PLANT GROWTH, OR HINDER PLANTING OPERATIONS.
- TOPSOIL SHALL CONTAIN A MINIMUM OF 3% ORGANIC MATERIAL.
- TOPSOIL MUST PERCOLATE WATER AT A RATE OF 1\"/>
- LANDSCAPE AREA SOILS SHALL BE APPROVED BY LANDSCAPE ARCHITECT/OWNER PRIOR TO PLANTING



DRAINAGE TESTING DETAIL


NOT TO SCALE



SPECIAL APPLICATIONS ROOT BARRIER DETAIL

NOT TO SCALE

- NOTES:
- 1- ROOT BARRIER SHALL BE INSTALLED WHEN ROOT BALL IS LOCATED WITHIN 8\"/>
 - 2- ROOT BARRIER SHALL BE \"BIO-BARRIER 29\" DEPTH OR APPROVED EQUAL.
 - 3- ROOT BARRIER SHALL BE INSTALLED PER MANUFACTURE'S SPECIFICATIONS AND RECOMMENDATIONS.



TREE PROTECTION BARRICADE


NOT TO SCALE

- NOTES:
- 1- SEE LANDSCAPE PLAN FOR FENCE ALIGNMENT.
 - 3- NO PRUNING SHALL BE PERFORMED EXCEPT BY APPROVED ARBORIST.
 - 4- NO EQUIPMENT SHALL OPERATE INSIDE THE PROTECTIVE FENCING INCLUDING DURING FENCE INSTALLATION AND REMOVAL.

DRAINAGE TESTING/DRAINAGE CHANNEL REQUIREMENTS.

PRIOR TO PLANTING, ALL PLANTING PITS SELECTED FOR TESTING SHALL BE TESTED IN THE FOLLOWING MANNER.

- DIG EACH PLANTING PIT TO THE MINIMUM SPECIFIED SIZE.
- FILL PLANTING PIT WITH TWELVE INCHES (12\") OF WATER. IF THE WATER LEVEL DROPS FOUR (4\") OR MORE WITHIN FOUR (4) HOURS, THE DRAINAGE IS SUFFICIENT AND A DRAINAGE CHANNEL IS NOT REQUIRED. IF THE WATER LEVEL DROPS LESS THAN FOUR INCHES (4\") WITHIN THE FOUR (4) HOUR PERIOD, A DRAINAGE CHANNEL IS REQUIRED.
- WHERE REQUIRED, THE DRAINAGE CHANNEL MUST EXTEND DOWN THROUGH THE NON POROUS SOIL AND INTO POROUS SOIL. (SEE DETAIL)
- ALL MATERIAL REMOVED FROM THE DRAINAGE CHANNEL SHALL BE DISCARDED.
- WHEN BACKFILLING PLANTING PITS WITH NATIVE TOPSOIL, CARE MUST BE TAKEN TO KEEP THE CONSISTENCY OF THE SOIL MIX THE SAME THROUGHOUT THE PLANTING PIT AND DRAINAGE CHANNEL.



SCALE: 1\"/>

0 0' 0' 0'

REG. # 1018
Thomas P. Lucido

Designer	JJ	Sheet
Manager	DF	
Project Number	17-425	
Municipal Number	---	
Computer File	18-041 Conchy Joes landscape plan.dwg	

LA-5

Drawing Name: C:\Users\swloff\appdata\local\temp\AcPublish_10352\ Jan 07, 2020 -- 1:33pm 18-041 Conchy Joes landscape plan.dwg

LANDSCAPE SPECIFICATIONS

PART 1: GENERAL CONDITIONS

- 1.01

A.

SCOPE:
The landscape contract includes the supplying and planting of all trees, shrubs, vines, and ground cover together with all necessary labor, equipment, tools and materials needed for the successful completion, execution and maintenance of the landscape plans.
- 1.02

A.

AGENCY STANDARDS:
Grades and standards of plant materials to be used shall be true to name, size, condition and graded Florida #1 or better as stated in: Grades and Standards of Florida Plant Materials published by the State of Florida Department of Agriculture, Tallahassee, Florida.
- 1.03

A.

SITE EXAMINATION:
The Landscape Contractor shall personally examine the site and fully acquaint him/herself with all of the existing conditions in order that no mis-understanding may afterwards arise as to the character or extent of the work to be performed, and, additionally, in order to acquaint him/herself with all precautions to be taken in order to avoid injury to property or persons. No additional compensation will be granted because of any unusual difficulties which may be encountered in the execution or maintenance of any portion of the work.
- 1.04

A.

ERRORS AND OMISSIONS:
The plant list is a part of the drawings and is furnished as a convenience. The plant list indicates the name, size and quantilies of specific plant materials as called for and is located on the drawings. The Landscape Contractor is responsible for his/her own quantity count, and any discrepancy between drawings and plant list shall be considered as correct on the drawings.
- B.

The Landscape Contractor shall not take advantage of errors or omissions in the specifications or contract drawings. Full instruction will be given if such errors are discovered. Upon the discovery of any discrepancies in, or omissions from the drawings or documents, or should the Landscape Contractor be in doubt as to their meaning, the Landscape Architect shall be notified and will determine the actions necessary to each query.
- C.

If plans and specifications are found to disagree after the contract is awarded, the Landscape Architect shall be the judge as to which was intended.
- 1.05

A.

EXECUTION OF THE WORK:
The Landscape Contractor shall have his labor crews controlled and directed by a Foreman well versed in plant materials, planting methods, reading plans, and coordination between job and nursery in order to execute installation correctly and in a timely manner.
- B.

The Landscape Contractor shall provide a competent English-speaking Foreman on the project at all times, who shall be fully authorized as the Contractor's agent on the work. The Foreman shall be capable of reading and thoroughly understanding the Plans, Specifications and other Contract Documents. If the Superintendent is deemed incompetent by the Landscape Architect, he (the superintendent) shall be immediately replaced.
- C.

The Landscape Contractor shall be available for any meetings with the Owner and/or Landscape Architect during implementation of the job. Any additional work or changes required as a result of failure to communicate with the Owner or Landscape Architect during implementation will be the responsibility of the Landscape Contractor.
- 1.06

A.

PROTECTION OF PUBLIC AND PROPERTY:
The Landscape Contractor shall protect all materials and work against injury from any cause and shall provide and maintain all necessary safeguards for the protection of the public. He shall be held responsible for any damage or injury to persons or property which may occur as a result of his fault or negligence in the execution of the work, i.e. damage to underground pipes or cables.
- 1.07

A.

CHANGES AND EXTRAS:
The Contractor shall not start work on any changes or "extras" in the project until a written agreement setting forth the adjusted prices has been executed by the Owner and the Contractor. Any work performed on changes or "extras" prior to execution of a written agreement may or may not be compensated for by the Owner at his discretion.
- 1.08

GUARANTEE:
The Landscape Contractor shall furnish a written guarantee warranting all materials, workmanship and plant materials, except sod, for a period of 18 MONTHS from the time of completion and acceptance by the Landscape Architect and Owner. Sod shall be guaranteed to 90 calendar days after acceptance by the Landscape Architect and Owner. All plant material shall be alive and in satisfactory condition and growth for each specific kind of plant at the end of the guarantee period. The guaranteeing of plant material shall be construed to mean complete and immediate replacement with plant material of the same variety, type, size, quality and grade as that of the originally specified material. During the guarantee period it shall be the Landscape Contractor's responsibility to immediately replace any dead or unhealthy material as determined by the Landscape Architect. The guarantee will be null and void if plant material is damaged by lightning, hurricane force winds, or any other acts of God, as well as vandalism or lack of proper maintenance.
- B.

At the end of the specified guarantee period, any plant required under this contract that is dead or not in satisfactory condition, as determined by the Landscape Architect, shall be replaced. The Landscape Contractor shall be responsible for the full replacement cost of plant materials for the first replacement and share subsequent replacement (s) costs equally with the Owner, should the replacement plant fail to survive.
- 1.09

A.

CARE AND MAINTENANCE:
The Landscape Contractor shall be responsible for the care and maintenance of all plant materials and irrigation when applicable until final acceptance by the Owner or Landscape Architect.
- B.

The Owner agrees to execute the instructions for such care and maintenance.
- 1.10

A.

SAFETY:
It shall be the responsibility of the Landscape Contractor to protect all persons from injury and to avoid property damage. Adequate warning devices shall be placed and maintained during the progress of the work.
- B.

It shall be the contractor's responsibility to conform to all local, state, and federal safety laws and codes including the Federal Occupational Safety And Health Act (O.S.H.A.).
- 1.11

A.

CONTRACTOR QUALIFICATION:
The Owner may require the apparent contractor (s) to qualify him/herself to be a responsible entity by furnishing any or all of the following documentary data:

1.

A financial statement showing assets and liabilities of the company current to date.

2.

A listing of not less than (3) completed projects of similar scope and nature.

3.

Permanent name and address of place of business.

4.

The number of regular employees of the organization and length of time the organization has been in business under the present name.

1.12

A.

INSURANCE AND BONDING:
The contractor (s) shall submit proof of insurance for this job for the time period that the work is done. The minimum amount of insurance shall be \$300,000.00 per person and \$300,000.00 per aggregate or as required by owner and agreed to in the contract. The successful bidder shall be required to have this coverage in effect before beginning work on the site.

B.

The Owner shall have the right to require the Contractor to furnish bonds covering faithful performance of the Contract and payment obligations arising thereunder as stipulated in bidding requirements or specifically required in the Contract Documents on the date of execution of the Contract.

1.13

A.

PERMITS AND CERTIFICATES:
All contractors shall secure and pay for all permits and certificates required for his/her class of work.

PART 2: MARTERIALS

- 2.01

A.

PLANT MATERIALS:
A complete list of plants is shown on the drawings, including a schedule of quantities, sizes, and such other requirements deemed necessary. In the event discrepancies occur, the specifications on the drawings shall govern.
- B.

Substitutions: Substitutions of plant materials or changes in size or spacing of materials will be permitted ONLY upon written authorization by the Owner or the Landscape Architect. If plant material is not of sufficient size to meet applicable codes, a letter of variance from the appropriate agency must be obtained by the Contractor prior to issuance of any change order. If material of smaller size is to be accepted, the quantity of material shall be increased, at no additional cost to the Owner, to meet the intent of the drawings.
- C.

All plant materials shall have a habit of growth that is normal for the species and shall be healthy, vigorous and equal to or exceed the measurements specified in the plant list, which are the minimum acceptable sizes. Plants shall be measured before pruning with branches in normal position. Any necessary pruning shall be done at the time of planting.
- D.

All plant materials shall be nursery grown, unless otherwise noted, Florida #1 or better and shall comply with all required inspections, grading standards and plant regulations as set forth by the Florida Department of Agriculture's Grades and Standards for Nursery Plants, most current addition and Grades and Standards for Nursery Plants, most current addition.
- E.

Plants that do not have the normal balance of height and spread typical for the respective plant shall not be acceptable.
- F.

The Landscape Contractor shall install each plant to display its best side. Adjustments may be required if plants are not installed properly and/or approved by the Landscape Architect at no additional cost to owner.

2.02 INSPECTION

- A.

The Landscape Architect and Owner may inspect trees and shrubs at place of growth or at site before planting, for compliance with requirements for genus, species, variety, size and quality. The Landscape Architect and Owner retain the right to further inspect trees and shrubs for size and condition of balls and root systems, insects, injuries and latent defects, and to reject unsatisfactory or defective material at any time during progress of work. Rejected plant materials shall be immediately removed from project site.
- 2.03

A.

PROTECTION OF PLANT MATERIALS:
Balled and burlapped plants (B & B) shall be dug with firm natural balls of earth of sufficient diameter and depth to encompass the fibrous and feeding root system necessary for full recovery of the plant. Balls shall be firmly wrapped with burlap similar materials and bound with cord, rope, or wire mesh. All collected plants shall be balled and burlapped.
- B.

Plants with broken, damaged or insufficient rootballs will be rejected.
- C.

All plant material shall be protected from possible bark injury or breakage of branches. All plants transported by open trucks shall be adequately covered to prevent windburn, drying or damage to plants.
- D.

Plants which cannot be planted immediately on delivery to the site shall be covered with moist soil, mulch or other protection from the drying of wind and sun. All plants shall be watered as necessary by the Landscape Contractor until planted.
- 2.04

A.

STORAGE
All plant materials shall be stored on the site in designated areas, specified by the Landscape Architect or Owner's agent.
- B.

No plant material shall be stored longer than seventy-two (72) hours unless approved by Landscape Architect and/or owner.
- C.

The Landscape Architect reserves the right to reject any plant materials not in conformance with these specifications.
- D.

All rejected material shall be immediately removed from the site and replaced with acceptable material at no cost to the Owner.
- 2.05

A.

PROTECTION DURING PLANTING:
Trees moved by winch or crane shall be thoroughly protected from chain marks, girdling or bark slippage by means of burlap, wood battens or other approved methods. Battens shall NOT be attached to the tree with nails
- 2.06

A.

TOP SOIL:
Planting soil for all plantings shall consist of topsoil and be natural, friable, fertile, fine loamy soil possessing characteristics of representative topsoil in the vicinity of the project site that produces heavy growth. Topsoil shall have a PH range of 5.5-7.4, free from subsoil, weeds, litter, sods, clay, stones, stumps, roots, trash, herbicides, toxic substances, or any other material which may be harmful to plant growth, or hinder planting operations. Topsoil shall contain a minimum of 3% organic material. Topsoil must percolate water at a rate of 1" per hour (See also drainage testing detail for trees)
- B.

Landscape Area Preparation. The intent of this section is to ensure a healthy growing environment for all planting material in all landscaped areas. Landscape Contractor to examine existing soils prior to planting to ensure conformance to all definitions of "Topsoil" (see Landscape Area Preparation Detail). In addition, a 3" layer of high organic (min 40%) potting soil shall be added to the topsoil and mixed in at time of planting. East Coast Recycling Inc. is a recommended source for imported Topsoil (if needed) as well as the top 3" layer of potting soil.
- Existing soils must meet all definitions of "Topsoil" as described above in all planting areas throughout the site. If existing soils do not meet all definitions of Topsoil, please refer to the "Landscape Area Preparation" detail. Examination may require existing soils to be tested by an accredited testing laboratory. Should a soil test be necessary, Contractor shall contact soil testing lab directly to confirm such lab's soil collection and transmittal protocol; all costs if any shall be borne by the Contractor. Contractor shall provide to Landscape Architect for review the results of the soil test if conducted. Contractor shall schedule an on-site meeting with Landscape Architect to review existing and/or imported soils prior to planting. The Landscape Area Preparation is the responsibility of the Landscape Contractor. He/she shall except all responsibility of planting soils and shall honor all guarantee items in section 1.08.
- 2.07

A.

FERTILIZER:
Commercial fertilizer shall comply with the state and local fertilizer laws. Nitrogen shall not be less than 40% from organic source. Inorganic chemical nitrogen shall not be derived from the sodium form of nitrate. Fertilizers shall be delivered to the site in unopened original containers, each bearing the manufacturer's guaranteed analysis. Any fertilizer that becomes caked or otherwise damaged shall be rejected.
- B.

Thoroughly mixed 3 lbs. of commercial fertilizer to each cubic yard of planting soil.
- C.

Tabletized fertilizer shall be Agriform planting tablets 20-10-5 formula, 21 gram or equal. All trees and shrubs shall be fertilized with tabletized fertilizer as follows. While backfilling plant holes, fertilizer tablets shall be equally spaced and placed adjacent to the ball mid-way in depth in accordance with the following rates:

1 gallon container

1 tablet

3 gallon container

2 tablets

5 gallon container

3 tablets

7 gallon container

5 tablets

Large tubs, wire baskets, grow bags, and balled and burlapped material shall have 1 tablet for each 1/2 inch of trunk diameter (measured 3 feet from ground) or for each foot of height or spread of larger shrub material. The Landscape Architect reserves the right to inspect and review the application of fertilizer.

2.08

A.

MULCH:
Mulch material shall be clean, dry, free of weeds, seeds and pests, moistened at the time of application to prevent wind displacement. Cypress &/or Red mulch is prohibited.

B.

All trees and shrub beds shall receive 3" mulch immediately after planting and thoroughly watered. Apply 2" max on tree & palm rootballs, keep 6" away from tree & palm trunks or as required by local jurisdiction.

PART 3

3.01

A.

EXECUTION DIGGING:
The Landscape Contractor shall exercise care in digging and other work so as not to damage existing work, including overhead wires, underground pipes and cables and the pipes and hydrants of watering systems. Should such overhead or underground obstructions be encountered which interfere with planting, the Owner shall be consulted and contractor will adjust the location of plants to clear such obstruction. The Contractor shall be responsible for the immediate repair of any damage caused by his work.

3.02

A.

GRADING:
Grading for drainage, swales, etc. to within 4 inches of the finished grade to be provided by others.

B.

It shall be the responsibility of the Landscape Contractor to provide the final grading during the course of landscape installation so as to bring sod and planting areas to their proper elevations in relation to walks, paving, drain structures, and other site conditions. The site grading plan must be checked prior to installation of sod to insure that drainage and other conditions will NOT be modified.

3.03

A.

PLANTING:
Planting shall take place during favorable weather conditions.

B.

The Contractor shall call for utility locates and ascertain the location of all utilities and easements so proper precautions can be taken not to damage or encroach on them.

C.

Tree Planting shall be located where it is shown on the plan. No planting holes shall be dug until the proposed locations have been staked on the ground by the Contractor.

D.

Excavation of holes shall extend to the required subgrades as specified on the planting diagrams located in the landscape plans. Plant pits shall be circular in outline and shall have a profile which conforms to the aforementioned "Tree and Shrub Planting Diagrams".

E.

A representative number of planting pits (a minimum of one in every 25 feet throughout the entire site) shall be tested for proper drainage. See Landscape Details for complete testing methods and requirements.

F.

Planting pits shall be excavated to the following dimensions and backfilled with Topsoil- see Landscape Area Preparation Detail;
1 Gallon material (1 gal.): 12" x 12" x 12" min.
3 Gallon material (3 gal.): 20" x 20" x 18" min.
Lerio material (7 gal.): 30" x 30" x 24" min.
Field grown material and trees: 1-1/2 times width of ball and depth of ball plus 12" min.

G.

No planting or laying of sod shall be initiated until the area has been cleaned of existing sod or other plant materials, rough grass, weeds, debris, stones etc. and the ground has been brought to an even grade, with positive drainage away from buildings and towards drain inlets and swales and approved by Landscape Architect or owner's rep.

H.

Each plant shall be planted in an individual hole as specified for trees, shrubs, and vines.

- I.

All plants shall be set to ultimate finished grade. No filling will be permitted around trunks or stems. All ropes, wire, stakes, etc., shall be removed from sides and top of the ball and removed from hole before filling in.
- J.

All flagging ribbon shall be removed from trees and shrubs before planting.
- K.

Excess excavation (fill) from all holes shall be removed from the site, at no additional expense to Owner.
- L.

All palms shall be backfilled with sand, thoroughly washed in during planting operations and with a shallow saucer depression left at the soil line for future watering's. Saucer areas shall be top-dressed two (2") inches deep with topsoil raked and left in a neat, clean manner.
- 3.04

A.

PRUNING:
Remove dead and broken branches from all plant material. Prune to retain typical growth habit of individual plants with as much height and spread as possible in a manner which will preserve the plant's natural character.
- B.

Make all cuts with sharp instruments flush with trunk or adjacent branch, in such a manner as to insure elimination of stubs. Cuts made at right angles to line of growth will not be permitted.
- C.

Trees shall not be poled or topped.
- D.

Remove all trimming from site.
- 3.05

GUYING:

A.

All trees over six (6') feet in height shall, immediately after setting to proper grade, be guyed with three sets of two strands, No. 12 gauge malleable galvanized iron, in tripod fashion. See Detail.

B.

Wires shall not come in direct contact with the tree but shall be covered with an approved protection device at all contact points. Wires shall be fastened in such a manner as to avoid pulling crotches apart.

C.

Slake & Brace all trees larger than 12" oa. See detail. Stakes shall be 2" x 2" lumber of sufficient length to satisfactorily support each tree.

D.

Turnbuckles for guying trees shall be galvanized or cadmium plated and shall be of adequate size and strength to properly maintain tight guy wires.
- 3.06

A.

WATER:
Each plant or tree shall be thoroughly watered in after planting. Watering of all newly installed plant materials shall be the responsibility of the Landscape Contractor until final acceptance by the Landscape Architect.
- B.

Prior to installing any irrigation system components, the contractor shall obtain a water sample from the proposed water supply and conduct a particle size and count analysis on the sample using the services of a reputable lab certified in such analysis. Submit the test results to the owner/owner's representative for review and approval. Do not proceed further with system installation until given written approval to do so.
- 3.07

A.

SOD:
The Landscape Contractor shall sod all areas indicated on the drawings.
- B.

It shall be the responsibility of the Landscape Contractor to fine grade all landscape areas, eliminating all bumps, depressions, sticks, stones, and other debris.
- C.

The sod shall be firm, tough texture, having a compacted growth of grass with good root development. It shall contain no noxious weeds, or any other objectionable vegetation, fungus, insects, or disease. The sod embedded in the sod shall be good clean earth, free from stones and debris.
- D.

Before being cut and lifted, the sod shall have been mowed at least three times with a lawn mower, with the final mowing not more than seven days before the sod is cut. The sod shall be carefully cut into uniform dimensions.
- E.

6-6-6 fertilizer with all trace elements is to be applied at the rate of 40 lbs. per 1,000 sq. ft. prior to laying sod.
- F.

Solid sod shall be laid with closely abutting, staggered joints with a tamped or rolled, even surface.
- G.

The finished level of all sod areas after settlement shall be one (1") inch below the top of abutting curbs, walks, paving and wood borders to allow for building turf.
- H.

If in the opinion of the Landscape Architect, top dressing is necessary after rolling, clean yellow sand will be evenly applied over the entire surface and thoroughly washed in.
- 3.08

A.

SEEDING:
The Landscape Contractor shall remove all vegetation and rocks larger than (1") in diameter from areas to be seeded, scarify the area, then apply fertilizer at a rate of 500 lbs. per acre.
- B.

Application: Argentine Bahia Grass seed- 200 Pounds per acre mixed with common hulled Bermuda seed- 30 lbs. per acre. All other seed mixtures shall be applied per the manufacturer's instructions.
- C.

Roll immediately after seeding with a minimum 500 pound roller, then apply straw mulch at the rate of 2,500 pounds per acre.
- D.

Apply fertilizer at the rate of 150 lbs. per acre 45-60 days after seeding.
- 3.09

A.

CLEANING UP:
The contractor shall at all times keep the premises free from accumulations of waste materials or rubbish caused by his employees or work. He shall leave all paved areas "broom clean" when completed with his work.
- 3.10

A.

MAINTENANCE:
Maintenance shall begin immediately after each plant is installed and shall continue until all planting has been accepted by the Owner or Landscape Architect. Maintenance shall include watering, weeding, removal of dead materials, resetting plants to proper grades or upright positions, spraying, restoration of planting saucer and/or any other necessary operations.
- B.

Proper protection to lawn areas shall be provided and any damage resulting from planting operations shall be repaired promptly.
- C.

Replacement of plants during the maintenance period shall be the responsibility of the Contractor, excluding vandalism or damage on the part of others, lighting, or hurricane force winds, until final acceptance.
- D.

In the event that weeds or other undesirable vegetation become prevalent, it shall be the Contractor's responsibility to remove them.
- E.

Trees or other plant material which fall or are blown over during the maintenance period will be reset by the Contractor at no additional expense to the Owner, the only exception being hurricane force winds.
- 3.11

A.


COMPLETION, INSPECTION AND ACCEPTANCE:
Completion of the work shall mean the full and exact compliance and conformity with the provisions expressed or implied in the Drawings and in the Specifications, including the complete removal of all trash, debris, soil or other waste created by the Landscape Contractor.
- B.

Inspection of work to determine completion of contract, exclusive of the possible replacement of plants, will be made by the Owner and/or Landscape Architect at the conclusion of all planting and at the request of the Landscape Contractor.
- C.

All plant material shall be alive and in good growing condition for each specified kind of plant at the time of acceptance. The rating of each plant according to Florida Grades and Standards shall be equal to or better than that called for on the plans and in these Specifications at the time of final inspection and acceptance.
- D.

After inspection, the Landscape Contractor will be notified by the Owner of the acceptance of all plant material and workmanship, exclusive of the possible replacement of plants subject to guarantee.
- E.

All trees & shrubs shall be straight and in correct position per the landscape plans, details and specifications. All nursery, shipping and identification tags & ribbons shall be removed from trees & shrubs immediately after planting.



Project Team:

Applicant / Property Owner:

F.M. AYRES 2 LLC, and
SUNRISE RESTAURANTS, LLC
3945 NE Indian River Drive
Jensen Beach, Florida 34957

Land Planner / Landscape Architect:

Lucido & Associates
701 E. Ocean Blvd
Stuart, Florida 34994

Engineer:

The MilCor Group
10975 SE Federal Highway
Hobe Sound, Florida 33455

Surveyor:

Betsy Lindsay Surveying & Mapping
7997 SW Jack James Drive
Stuart, Florida 34997

Conchy Joe's

Martin County, Florida

Landscape Specifications

Date	By	Description
03.11.19	SAW	Initial Submittal
09.24.19	SAW	Resubmittal 1
12.18.19	SAW	Resubmittal 2

NORTH

SCALE: 1" = n.t.s.

0

0'

0'

0'

REG. # 1018
Thomas P. Lucido

Designer

JJ

Sheet

Manager

DF

Project Number

17-425

Municipal Number

Computer File

18-041 Conchy Joes landscape plan.dwg

LA-6

LANDSCAPE ALTERNATIVE COMPLIANCE REQUEST

Conchy Joe's Revised Final Site Plan Application January 7, 2020

Landscape Alternative Compliance Request

The project meets or exceeds all required landscape codes, however alternative compliance is necessary to comply with Section 4.663.A.4.b, *VUA Requirements for Non-Residential Uses*, which requires interior landscape islands counted towards the interior landscape area to be a minimum of 500 sf in size, and the minimum width of all interior landscape islands to be 12 feet wide.

All of the interior landscape islands greatly exceed the minimum 500 sf size requirement but do not meet the minimum 12' width in some areas. In order to maintain parking spaces and the integrity of the site plan, alternative compliance is requested based on the following areas of the landscape plan that exceed minimum requirements:

- A minimum 9,244 sf of interior landscape area is required to be planted. A total of 10,697 sf is provided not including 10,805 sf along each side of Indian River Drive, which practically function as interior landscape islands because they are between parking and vehicular use areas.
- Terminal landscape islands have been expanded where possible to accommodate larger trees and a greater quantity of native shrubs;
- Total landscape area exceeds minimum code by 52%
- The number of tree credits exceeds minimum code by 42%.
- The number of shrubs exceeds minimum code by 99%.
- The min. 10' wide landscape strip along Indian River Drive have been expanded to average more than 20 feet wide to accommodate larger trees and a greater quantity of perimeter shrubs. The expanded landscape strip maintains and enhances the views along Indian River Drive and provides an effective buffer between the parking on site and the parallel parking the applicant is constructing on Indian River Drive.
- The size of trees and shrubs exceeds minimum code requirements.
- The building foundation landscaping exceeds minimum requirements.
- To improve water quality, the project is designed with bioswales planted with native species and exfiltration trench to treat stormwater prior to discharge off site.
- The applicant is voluntarily electing to construct a living shoreline within the shoreline protection zone that will help stabilize the shoreline while providing refuge for native plants and animals.

With this understanding, the following is an itemized response (*see italics*) to **Sec. 4.667 - Alternative compliance**:

4.667.A. Evaluation. The applicant must provide documentation to justify a landscape plan not meeting the minimum standards of this division. Such documentation shall include a quantitative analysis of areas not meeting minimum standards or dimensions, required vs. provided dimensions, and materials not meeting minimum Code requirements.

As discussed above the alternative compliance request is limited to the minimum 12' width required for interior landscape islands as per Section 4.663.A.4.b. All other landscape requirements are met or exceeded.

In evaluating proposed alternative compliance landscape plans, considerations shall be given to proposals which preserve native vegetation and use drought-tolerant plantings and other low water use landscape design principles and where the design may accomplish one or more of the following:

1. **Ensures preservation of the maximum predevelopment vegetation on the site.**

Maximum preservation of existing native trees has been documented.

2. **Is designed to assure that the overall appearance and function of the proposed project is compatible with other properties in the immediate area; is demonstrably responsive to the environmental attributes of soil, slope, hydrology, and vegetative communities unique to the site; is consistent with sound planning and site design principles, and contingent upon:**

a. Structures and other improvements are designed as to utilize existing site characteristics of topography, existing vegetative communities, and any unique environmental feature.

The overall appearance and compatibility with surrounding properties has been established since Conchy Joe's was originally constructed in the 1950s. The purchase and renovation of the vacant Admiral's Table restaurant will enhance the Conchy Joe's experience and improve the appearance and function of the existing project and surrounding areas. The design of a river walk and living shoreline along the Indian River Lagoon will enhance the beauty and improve the biological function of this unique environmental feature.

b. Conflicts between vehicular and pedestrian circulation are avoided.

The site is designed with expansive sidewalks and pedestrian crossings that will greatly improve the existing condition and minimize pedestrian and vehicular conflicts.

c. Planting plans indicate a diversity of plant species in the categories of ground covers, shrubs, and trees.

The plant palate is composed of 100% drought-tolerant plant species. The overall landscape plan utilizes 6 species of native trees and palms, 5 species of native shrubs and 8 species of native grasses and groundcover.

d. Integration of proposed and existing vegetation is demonstrated in the plans with an emphasis on maintaining native community buffers and corridors, preserving or restoring forest community types, and providing for the natural ecological function of each type by using such techniques as preserving a diversity of upperstory, midstory, and understory.

Due to the existing development on the property, no native habitat exists on site and surrounding areas are already developed. However, the natural, ecological function of the shoreline will be

improved by the design of a living shoreline with native plantings to stabilize the shoreline and create natural shoreline habitat for native plants and animals.

e. Plant schedules contain botanical and common names, sizes of materials by dimension and containerize, location by dimension, and notation describing species diversity.

The proposed landscape plan provides a detailed description of plant types and specifications that ensure successful establishment and long-term maintenance of plant materials.

f. Planting specifications and species selected for the site are suitable for individual site environmental characteristics of soil slope, aspect, wetness and microclimate.

Plant types were selected based on existing soil characteristics, groundwater level, surrounding native plant communities, habitat value and drought-tolerance.

g. Plans indicate compatibility with adjacent site environmental features.

The proposed native plant materials within the living shoreline component of the shoreline protection zone were selected to blend in with the native shoreline plant communities.


2. Implements a EcoArt element as approved by the Growth Management Department Director.

Conchy Joe's is an iconic, historically significant restaurant site that features the history of the local area. The local history and culture will be further revealed and expanded upon by way of the proposed expansion.

3. Provides foundation landscaping, comprised entirely of native vegetation around principle structures with educational signage identifying native plant species.

Native landscaping around buildings has been provided.

Key / Location:



Project Team:

Applicant / Property Owner:

F.M. AYRES 2 LLC, and
SUNRISE RESTAURANTS, LLC
3945 NE Indian River Drive
Jensen Beach, Florida 34957

Land Planner / Landscape Architect:

Lucido & Associates
701 E. Ocean Blvd
Stuart, Florida 34994

Engineer:

The MilCor Group
10975 SE Federal Highway
Hobe Sound, Florida 33455

Surveyor:

Betsy Lindsay Surveying & Mapping
7997 SW Jack James Drive
Stuart, Florida 34997


Conchy Joe's

Jensen Beach
Martin County, Florida

VUA
Exhibit

Date By Description

12.05.2019 S.L.S. Initial Submittal



SCALE: 1" = 30'

0 15' 30' 60'

REG. # 1018
Thomas P. Lucido

Designer S.L.S.

Manager M.C.

Project Number 18-041

Municipal Number ---

Computer File Conchy Joe's - Final Site Plan.dwg

1 of 1

© Copyright Lucido & Associates. These documents and their contents are the property of Lucido & Associates. Any reproductions, revisions, modifications or use of these documents without the express written consent of Lucido & Associates is prohibited by law.

Proposed 2-Story
Building Expansion
4,466 sf
(FFE 8.70)

Existing Zoning: LC
Future Land Use: Commercial Limited
Existing Use: Apartment / Hotel

Gated
Dumpster & Recycle
Enclosure

Loading Area
6' Wide Sidewalk

2' Parking
Overhang

Existing
1 Story Building
6,345 sf
(FFE 8.70)

8' Wide Sidewalk

10' Wide Multimode Path

Bike Rack

Stop Sign &
Stop Bar (Typ.)

2' Parking Overhang (Typ.)

2,455 sf

Light Pole (Typ.)

Light Pole
(Typ.)

Stop Sign &
Stop Bar (Typ.)

2' Parking Overhang (Typ.)

2' Parking Overhang (Typ.)

893 sf

939 sf

812 sf

2' Parking Overhang (Typ.)

986 sf

1,710 sf

2' Parking Overhang (Typ.)

Stop Sign & Stop Bar (Typ.)

Relocated
Storage Building ±750 sf (FFE 9.25)

Existing
Office
±1,356 sf
(FFE 8.58)

Bike Rack

Existing Office Building
(To Remain)

Existing Zoning: Pitchford's Landing PUD
Future Land Use: Low Density
Existing Use: Mobile Home / RV Park

6' High 100% Opaque Fence

½ Modified Type 2 Buffer

Existing Zoning: Pitchford's Landing PUD
Future Land Use: Low Density
Existing Use: Mobile Home / RV Park

Gated
Dumpster & Recycle
Enclosure

12.5' Type 2 Buffer

VUA Data


4.b. Vehicular Use Area Interior 92,432 sf

1,500 sf. of planting area/5000 sf. of VUA
(92,432/5000*500=9,244 sf.)


Required 9,244 sf.

Provided 10,697 sf.

VUA Areas



10,697 sf.



10,805 sf.

NE CHERI DRIVE

Existing
Preserve
Area

Existing Zoning: RS-4
Future Land Use: Low Density
Existing Use: Pineapple Bluffs Subdivision
Preserve Area

Existing
Preserve
Area

Existing Zoning: Pitchford's Landing PUD
Future Land Use: Low Density
Existing Use: Mobile Home / RV Park

Existing Right of Way

Proposed Right of Way Easement

Existing Right of Way

Pedestrian Crossing (Typ.)

OBSERVATION PIER
(NO MOORING)
SUBJECT TO
FDEP PERMIT NO. 43-0147285-003
ACOE PERMIT NO. SAJ-1983-10512

6' Wide Sidewalk

25' Shoreline Protection Zone

5' Setback

Upland Retaining Wall

Indian River
Lagoon

SHORELINE/INTERTIDAL OBSERVATION PIER WITH
RAILING AND NO MOORING SIGNS
SUBJECT TO
FDEP PERMIT NO. 43-0147285-003
ACOE PERMIT NO. SAJ-1983-10512

8' Wide
Sidewalk

APPROX. RIPARIAN LINE

Entry Only

NE INDIAN RIVER DRIVE
(aka STATE ROAD 707)

Existing
Conchy
Joe's
(FFE 5.77)

Existing / Proposed Loading Area

Existing Zoning: PUD
Future Land Use: Low Density
Existing Use: Recreation Area

PORTION OF EXISTING
DOCK TO BE REPLACED
AND RELOCATED 5'±
NORTH OF EXISTING
LOCATION

①

⑦